



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

STEAM ENGINE
BY BAKER

LEALE'S RUDIMENTARY, SCIENTIFIC, AND EDUCATIONAL SERIES.

The following are the Works already published in
CIVIL ENGINEERING, &c.

(The Volumes are bound in limp cloth, except where otherwise stated.)

CIVIL ENGINEERING, the Rudiments of; for the Use of Beginners, for Practical Engineers, and for the Army and Navy. By HENRY LAW, C.E. Including a Section on HYDRAULIC ENGINEERING, by GEORGE R. BURNELL, C.E. Illustrated with Plates and Diagrams. 5s.

THE DRAINAGE OF DISTRICTS AND LANDS. By G. DRYSDALE DEMPSEY, C.E. New Edition, revised and enlarged. Illustrated. 1s. 6d.

THE DRAINAGE OF TOWNS AND BUILDINGS. By G. DRYSDALE DEMPSEY, C.E. New Edition, Illustrated. 2s. 6d.
. With "*Drainage of Districts and Lands*," in one vol., 3s. 6d.

RAILWAY CONSTRUCTION, Rudimentary and Practical Instructions on the Science of; for the Use of Engineers and others. By Sir MACDONALD STEPHENSON, C.E. New Edition, revised and enlarged by EDWARD NUGENT, C.E. Plates and Diagrams. 3s.

RAILWAYS: their Capital and Dividends. With Statistics of their Working in Great Britain and Ireland, &c. By E. D. CHATTAWAY. 1s.

. With "*Railway Construction*," in one vol., 4s.

EMBANKING LANDS FROM THE SEA, the Practice of. Treated as a Means of Profitable Employment for Capital. With Examples and Particulars of actual Embankments, and also Practical Remarks on the Repair of old Sea Walls. By JOHN WIGGINS, F.G.S. New Edition. 2s.

SUBTERRANEAN SURVEYING, an Elementary and Practical Treatise on. By THOMAS FENWICK. Also the Method of Conducting Subterranean Surveys without the use of the Magnetic Needle, and other modern Improvements. By THOMAS BAKER, C.E. Illustrated. 2s. 6d.

GAS-WORKS, and the Practice of Manufacturing and Distributing Coal Gas. By SAMUEL HUGHES, C.E. New Edition, revised by W. RICHARDS, C.E. Illustrated. 3s.

, 7, STATIONERS' HALL COURT, E.C.

WATER-WORKS, for the Supply of Cities and Towns.

With a Description of the principal Geological Formations of England as influencing Supplies of Water; Details of Engines and Pumping Machinery for raising Water. By SAMUEL HUGHES, F.G.S., C.E. New Edition, revised and enlarged, with numerous Illustrations, 4s.

WELL-DIGGING, BORING, AND PUMP WORK.

By JOHN GEORGE SWINDELL, R.I.B.A. New Edition, revised by G. R. BURNELL, C.E. Illustrated. 1s. 6d.

TUBULAR & OTHER IRON GIRDER BRIDGES.

Particularly describing the BRITANNIA and CONWAY TUBULAR BRIDGES. With a Sketch of Iron Bridges, and Illustrations of the Application of Malleable Iron to the Art of Bridge Building. By G. D. DEMPSEY, C.E. New Edition, with Illustrations. 1s. 6d.

CONSTRUCTING AND REPAIRING COMMON

ROADS, the Art of. Containing a Survey of the Metropolitan Roads, by S. HUGHES, C.E. The Art of Constructing Common Roads, by HENRY LAW, C.E. Remarks on the Maintenance of Macadamised Roads, by Field-Marshal Sir JOHN F. BURGOYNE, Bart., G.C.B. Illustrated. 1s. 6d.

CIVIL ENGINEERING IN NORTH AMERICA, a

Sketch of. By DAVID STEVENSON, F.R.S.E., &c. Plates and Diagrams. 3s.

HYDRAULIC ENGINEERING, the Rudiments of.

By G. R. BURNELL, F.G.S. Illustrated. 3s.

RIVERS AND TORRENTS. With the Method of

Regulating their Courses and Channels. By Professor PAUL FRISI, F.R.S., of Milan. To which is added, "AN ESSAY ON NAVIGABLE CANALS." Translated by Major-General GARSTIN, of the Bengal Engineers. Plates. 2s. 6d.

THE SLIDE RULE, AND HOW TO USE IT;

containing full and easy Instructions, by C. HOARE, C.E. With a Slide Rule in Tuck of Cover. 3s.

MATHEMATICAL INSTRUMENTS: their Construc-


tion, Adjustment, Testing, and Use, by J. F. HEATHER, M.A. Illustrated. 1s. 6d.

SURVEYING AND ASTRONOMICAL INSTRU-

MENTS. Including Instruments used for determining the Geometrical Features of a Portion of Ground, and in Astronomical Observations. By J. F. HEATHER, M.A. Numerous Woodcuts. 1s. 6d.

DICTIONARY OF TERMS used in Architecture,

Building, and Engineering; Mining, Surveying, and Construction; Early and Ecclesiastical Art; the Fine Arts, &c. New Edition, revised and enlarged, by ROBERT HUNT, F.G.S. 5s.



MATHEMATICAL THEORY OF
THE STEAM ENGINE



THE MATHEMATICAL THEORY OF
THE STEAM ENGINE

WITH RULES AT LENGTH, AND EXAMPLES WORKED OUT FOR THE
USE OF PRACTICAL MEN

By T. BAKER, C.E.

AUTHOR OF "STATICS AND DYNAMICS," "LAND AND ENGINEERING SURVEYING,"
"ELEMENTS OF MECHANISM," "MINING SURVEYING," ETC.

With numerous Diagrams

SIXTH EDITION, REVISED BY PROFESSOR J. K. YOUNG



LONDON
LOCKWOOD & CO., 7, STATIONERS' HALL COURT
LUDGATE HILL
1876



PREFACE.

A WORK of this kind, on the Mathematical Theory of the Stationary, Marine, and Locomotive Engines, has long been a desideratum; not only as an introduction to Tredgold's large and important work on the same subject, but also for the use of a numerous class of students, who either have not time to read or the means of purchasing the large work just referred to. The author of this "Introduction" has taken great pains to supply this link in the chain of scientific research so much required, as well as to adapt it to the wants of practical men, by giving rules in words at length for their use; also for students who have not yet accustomed themselves to the application of mathematical formulæ, by which their progress in studies of this kind will be greatly facilitated, until at length they arrive at full competence in both the theoretical and practical parts of these important subjects, and thus be prepared to understand with ease the various complexities of Tredgold's large and complete work.

The author has, moreover, given in this "Introduction" a new and important method of showing the positions of the slide-valves, corresponding to the various openings of the steam and exhausting ports, by geometrical construction,

in addition to the rules usually given by calculation, which method has been presented to him by the eminent engineer, C. E. Amos, Esq., M.I.C.E., of the well-known firm of Easton, Amos, and Sons. It is given in as clear a manner as the subject seems to admit of, since any intelligent workman may, with rule and compasses, draw the figure to any convenient scale, and as respects locomotive engines, he may draw it to the full size.

The work concludes with an Appendix, on the strength, &c., of several important parts of the Steam Engine; to which are added Tables of Hyperbolic Logarithms, and Tables of Friction, which are used in the calculations in the preceding parts of the work.

T. BAKER

CONTENTS.

	Page
Mariotte's law of compression	1
Expansive power of steam	1
Unit of work	2
To find the units of work done on the piston in one stroke	2
To find the load	3
To find the pressure at which the steam is admitted	3
To find the horse power	3
Examples on the four preceding rules	4
To find the work done by expanded steam without the use of logarithms	6
To find the advantage derived from working steam expansively	10
Resistance to the pressure of steam in condensing and non-condensing engines	12
To find the useful load	12
Evaporating power of the boiler	13
Table showing the volume which a cubic foot of water has in the form of steam at different pressures, and the corresponding temperatures	13
Examples on the use of the table	15
Theoretical investigation of the properties of steam	17
To find when the velocity of the piston is a maximum	19
Pambour's theory of the steam engine	20
Arago and Dulong's experiments to determine the relation between pressure and temperature	22
Gay-Lussac's law for relation of temperature and volume in elastic fluids	23
Pole's formula of the relation between pressure and volume (under expansion)	24
Navier's formula (for same)	25
On the work done on the piston in a given time	26
On the duty of the engine	30
To find the point at which the steam must be cut off to obtain the greatest quantity of work	31
On the safety-valve	33
To find the pressure on the valve to each square inch when the whole weight is put upon the valve	34
On the lever of the safety-valve	34
To graduate the lever, its weight being considered	35
Fly-wheel	37
When the force acts in one direction to find the limits within which the angular velocity varies	37
To find the units of work in the fly-wheel and the number of revolutions before it stops	38
Rules and examples for the fly-wheel of the double-acting engine	39
Rules and examples for the fly-wheel of the single-acting engine	41

	Page
The governor	42
Rules and examples on the governor	44
To find the distance at which the balls revolve from their point of suspension	44
To find the radius of the circle described by the balls	44
Principles of the crank	45
The eccentric	53
To construct an eccentric wheel	54
Parallel motion	55
Paddle wheels	57
On different kinds of paddle wheels	58
To find the centre of pressure in the float-boards of Morgan's paddle	60
Marine screw propellers	62
The action explained	63
Theory of the screw propeller—the pressures in different directions	67
On boilers	70
Steam pipes	71
Air pump and condenser	72
Side valves of the steam engine	72
Construction of the locomotive engine	77
Action of the locomotive engine described	79
First notice and use of steam	80
Review of the progress of the locomotive engine	80
On moving a train on a level railway	84
On moving a train against the joint resistances of friction and gravity on an inclined plane	86
Safety-valves	88
On the variable resistances to locomotive engines	88
On the steam blast, or steam jet, in locomotives	92
On chimneys	93
Miscellaneous examples	95


APPENDIX.

On the strength, friction, &c., of several important parts of the steam engine	98
On gudgeons	98
Cranks.	
Friction of an axle	99
Friction on a pivot	100
Friction in a cylinder	100
On winding machines	101
To find the position of meeting in the cages drawing in a coal shaft	102
To find where the ascending and descending curves will meet in the shaft	103
Table of hyperbolic logarithms	105
Table of friction of gudgeons, or axle ends, in motion on their bearings	17
Table of friction of plane surfaces in motion one upon the other	1

THE
MATHEMATICAL THEORY
 OF THE
STEAM ENGINE.

THE preliminary step in this important subject is to treat of the law of the expansion of steam, which was discovered by Mariotte, and confirmed by Arago and Dulong, to all pressures as far as up to 27 atmospheres. *This law is the simplest that can be applied to the steam engine*; it may be enunciated thus:—If a given weight of steam be made to vary its volume without changing its temperature, the *elastic force* of the steam will vary in the *inverse ratio of the volume* it is made to occupy.

Thus let A B C D be a cylinder, E F and G H any two positions of the piston; then the pressure in the position E F is to the pressure in the position G H as the space G H C D is to the space E F C D.



Although this is by far the most simple and general law that we can apply, yet it is not strictly correct; but sufficiently so for the purpose of showing the great advantages that can be gained by working steam expansively; the results, however, will be alway a little greater than the truth, since *during the time the expansion is going on in the cylinder, the temperature does not remain exactly the same*; therefore, the various properties of steam given by Arago, Dulong, Tredgold, Pambour, Pole, and others, shall hereafter be produced in detail.

UNIT OF WORK.

In applying this principle to estimate and compare the different kinds of work performed under different circumstances, it becomes necessary to have a distinct measure or *unit of work*, by which the various results may be calculated and the amounts ascertained.

The English unit of work is the power necessary to raise one pound through a space of one foot.

Thus, if 1 lb. be raised 1 foot by a machine, then one unit of work has been performed; if 4 lbs. be raised 6 feet, then $4 \times 6 = 24$ units of work have been performed; and so on for other combinations. *Hence the units of work performed are measured by the product of the weight of the body in pounds, and the space or height in feet, through which it is raised*; also pressures or resistances of every kind, in whatever direction they are exerted, may be expressed in pounds, and therefore measured by the unit of work here described.

Let this unit of work be referred to one minute, as the unit of time. Taken in this point of view the unit of work will be represented as 1 lb. raised 1 foot high in 1 minute. It is assumed that a horse is able to raise 33,000 lbs. one foot high in one minute; and this is, therefore, called a horse-power. Hence, to find the number of horse-powers consumed in any proposed work, it will only be required to divide the units in that work by 33,000 times the number of minutes in which it is done.

To find the units of work done on the piston in one stroke.

Given the length of the stroke of the piston (l), the distance moved by the piston before the steam is cut off (q), and the pressure at which the steam is admitted to the cylinder (p); to find the work done upon each square inch of the piston in one stroke.

The required work on each square inch of the piston is, by Mariotte's law,

$$q p \left(1 + \log \frac{l}{q} \right) *$$

* The logarithms here used are the hyperbolic; the investigation of this and the other formulæ will be hereafter given.

But that this Treatise may be useful to such practical men as are not accustomed to use formulæ, the following rule is given :—

RULE 1.—Divide the whole length of the stroke by the distance moved by the piston before the steam is cut off, and find the hyperbolic logarithm of the quotient, to which add 1, and multiply the sum by the product of the pressure of the steam and the distance moved by the piston before the steam is cut off, and the result is the whole work done on each square inch of the piston.

To find the load.

The load is generally defined to be the mean pressure of the steam.

Let L be the load; then

$$L = \frac{qp}{l} \left(1 + \log \frac{l}{q} \right).$$

Or, in words at length, we have the following :—

RULE 2.—Divide the work done upon one square inch in one stroke by the length of the stroke, and the quotient will be the load.

To find the pressure at which the steam is admitted.

$$p = \frac{L \cdot l}{q \left(1 + \log \frac{l}{q} \right)}$$

Or, in words at length, there results the following :—

RULE 3.—Divide the whole length of the stroke by the number of feet described by the piston before the steam is cut off; to the hyperbolic logarithm of this quotient add unity, and multiply the sum by the number of feet moved by the piston before the steam is cut off, for a divisor; and for a dividend multiply the length of the stroke by the load. The quotient is the pressure in pounds per square inch at which the steam is admitted.

To find the horse-powers.

Let A = area of the piston in square inches, and N = number of strokes per minute; then,

$$\text{Horse-power} = \frac{A N q p \left(1 + \log \frac{l}{q} \right)}{33,000}.$$

Or, in words at length, we have the following :—

RULE 4.—Multiply the work done on one square inch in one stroke, by the area of the piston in square inches, and by the number of strokes per minute, and this product being divided by 33,000, gives the horse-powers.

Example 1.—The pressure of the steam upon the piston is 60 lbs. per square inch, the length of the stroke is 12 feet, the steam is cut off at $\frac{1}{6}$ of the stroke; required the number of units of work upon each square inch of the piston, and the horse-powers, the diameter of the cylinder being 50 inches, and the piston making 20 strokes per minute.

By Rule 1,

$$\log \frac{12}{2} = \log 6 = 1.79175, \text{ and}$$

$$1.79175 + 1 = 2.79175,$$

$\therefore 2 \times 60 \times 2.79175 = 335.01 =$ whole work done on one square inch of the piston in one stroke.

Again, $50 \times 50 \times .7854 = 1963.5$ area of the piston in square inches, and by Rule 4,

$$\frac{335.01 \times 1963.5 \times 20}{33,000} = 398.66 \text{ horse-powers.}$$

$$\text{By the formula } q p \left(1 + \log \frac{l}{q} \right) = 2 \times 60 (1 + 1.79175)$$

$= 335.01 =$ whole work done on one square inch of the piston in one stroke.

Also,

$$\frac{A N q p \left(1 + \log \frac{l}{q} \right)}{33,000} = \frac{1963.5 \times 20 \times 2 \times 60 (1 + 1.79175)}{33,000} =$$

398.66 horse-powers.

Example 2.—The things given being the same as in *Example 1*, it is required to find the load of the engine.

Here the work done on one square inch in one stroke of

the piston, is 335·01 units; whence $\frac{335\cdot01}{12} = 27\cdot9175 =$

load in lbs. on one square inch of the piston, by Rule 2.

Example 3.—Required the pressure per square inch at which the steam must be admitted, when the load is 44 lbs. per square inch; the steam is cut off at 2 feet, and the length of the stroke 5 feet.

By Rule 3,

$$1 + \log 2\cdot5 = 1 + \cdot9163 = 1\cdot9163,$$

$$2 \times 1\cdot9163 = 3\cdot8326, \text{ and}$$

$$44 \times 5 \div 3\cdot8326 = 57\cdot4 \text{ lbs. per square inch nearly.}$$

Example 4.—The pressure of steam upon the piston is 60 lbs. per square inch; the resistance from imperfect condensation 4 lbs. per square inch; the length of the stroke is 12 feet, and the steam is cut off at $\frac{1}{3}$ of the stroke. Required, the number of units of work done upon each square inch of the piston, and the number of units of work gained by working the steam expansively,

Here, as in Example 1, 335·01 units of work are done on one square inch of the piston in one stroke.

But, as the resistance from uncondensed vapour is 4 lbs. per square inch, it will be $12 \times 4 = 48$ lbs. for the resistance for the whole length of the stroke; therefore the effective work will be $335\cdot01 - 48\cdot00 = 287\cdot01$ units of work on one square inch.

Now, to find the advantage gained by working the steam expansively; we have when the engine works without expansion $12 \times 60 = 720 =$ units of work done upon each square inch.

But, as in this case the steam is not cut off till the end of the stroke, there is $\frac{12}{2} = 6$ times the steam used; hence for the same quantity there results,

$$\frac{720}{6} = 120 \text{ lbs. per square inch.}$$

While by working expansively there has been obtained 335·01 units of work; hence $335\cdot01 - 120 = 215\cdot01$ lbs. gained in this example.

Also, $\frac{335.01}{120} = 2.79$ times as much work done by the

same quantity of steam when worked expansively.

When it is stated that the steam is cut off at $\frac{1}{8}$, $\frac{1}{6}$, $\frac{1}{4}$, &c., of the stroke, there is no necessity for dividing the whole distance moved by the piston by the distance it moves before expansion, whatever may be the fractional part; we need only find the hyperbolic logarithm of the denominator of the fraction, and add unit to it; then multiply the sum by the product of the pressure and the part of the stroke before expansion begins, and the last product is the whole work done upon each square inch of the piston. For example, let the length of the stroke be 12 feet, and the steam be cut off at $\frac{1}{3}$ of the stroke, the pressure upon the piston being 60 lbs. per square inch.

Here the denominator of the fraction is 3, and its hyperbolic logarithm is 1.0986, to which add unity, and we shall have 2.0986; whence $4 \times 60 \times 2.0986 = 503.664 =$ whole work done upon each square inch of the piston in one stroke.

To find the work done by expansion without the use of logarithms.

RULE.—Divide that part of the stroke through which expansion takes place into any even number of equal parts, and calculate the pressure per square inch upon the piston at each division of the stroke by Mariotte's law; take the sum of the extreme pressures in pounds per square inch, four times the sum of the even pressures, and twice the sum of the odd pressures; multiply the sum of all these by one-third of the common distance between the positions of the piston, and the result will be the work done upon each square inch of the piston after expansion begins. The work done before expansion begins being evidently equal to the pressure per square inch multiplied by the number of feet moved before expansion; and the whole work done during a single stroke is equal to the sum of the works done before and after expansion.

Example 1.—The pressure of the steam upon the piston is 80 lbs. per square inch, the length of the stroke of the piston is 10 feet, the steam is cut off at $\frac{1}{5}$ of the stroke; it is

required to find the whole amount of work done upon each square inch of the piston.

The piston moves $\frac{1}{2}$ of the stroke, which is 2 feet, with the full pressure of the steam; let the remaining part of the stroke, which is 8 feet, be divided into four equal parts, each of which will be 2 feet; let these pressures be represented by $P, P_1, P_2, \&c.$; then, by Mariotte's law,

$$4 : 2 :: 80 : P_1 = \frac{80 \times 2}{4} = 40 \text{ lbs. pressure.}$$

$$6 : 2 :: 80 : P_2 = \frac{80 \times 2}{6} = 26.66 \text{ lbs. ,,}$$

$$8 : 2 :: 80 : P_3 = \frac{80 \times 2}{8} = 20 \text{ lbs. ,,}$$

$$10 : 2 :: 80 : P_4 = \frac{80 \times 2}{10} = 16 \text{ lbs. ,,}$$

Then, by the rule just given,

80 = greatest extreme pressure.

16 = least extreme pressure.

96 = sum of extreme pressures.

40

20

60 = sum of the even pressures.

4

240 = 4 times the sum of the even pressures

26.66' = the odd pressure, there being only one

2

53.33' = twice the odd pressure.

96 = sum of extreme pressures.

240 = 4 times sum of even pressures.

53.33' = twice the odd pressure.

389.33' = sum.

The above sum, *i.e.*, 389.33 being multiplied by $\frac{1}{2}$ of 2 feet, the common distance, gives

$$\frac{389.33 \times 2}{3} = 259.55 =$$

the number of units of work done upon each square inch of the piston after expansion begins, and $80 \times 2 = 160 =$ the number of units of work done upon each square inch before expansion begins. Hence

$$\begin{array}{r} 259.55 \\ 160 \\ \hline 419.55 = \end{array}$$

number of units of work done upon each square inch, during a single stroke of the piston.

Example 2.—The pressure of steam upon the piston is 60 lbs. per square inch, the resistance arising from imperfect condensation, 4 lbs. per square inch, the length of the stroke is 12 feet, and the steam is cut off at $\frac{1}{3}$ of the stroke; it is required to determine the number of units of work done upon each square inch of the piston, the number of units of work gained by working expansively, the load per square inch, and the position of the piston when the velocity is greatest.

Let the remaining part of the stroke, *i. e.* $12 - 2 = 10$ feet be divided into 10 equal parts; then

$$3 : 2 :: 60 : P_1 = \frac{60 \times 2}{3} = 40,$$

$$\text{and similarly } P_2 = \frac{60 \times 2}{4} = 30,$$

$$P_3 = \frac{60 \times 2}{5} = 24,$$

$$P_4 = \frac{60 \times 2}{6} = 20,$$

$$P_5 = \frac{60 \times 2}{7} = 17.142,$$

$$P_6 = \frac{60 \times 2}{8} = 15,$$

$$P_7 = \frac{60 \times 2}{9} = 13.333,$$

$$P_8 = \frac{60 \times 2}{10} = 12,$$

$$P_9 = \frac{60 \times 2}{11} = 10.909,$$

$$P_{10} = \frac{60 \times 2}{12} = 10,$$

$60 + 10 = 70 =$ sum of extreme pressures.

40.000
24.000
17.142
13.333
10.909

105.384 = the sum of the even pressures.
4

421.536 = 4 times the sum of the even pressures.

30.000
20.000
15.000
12.000

77.000 = the sum of the odd pressures.
2

154.000 = twice the sum of the odd pressures.

421.536 = 4 times the sum of the even pressures.

70.000 = sum of the extreme pressures.

3)645.536

215.178

120 = $60 \times 2 =$ work done before expansion.

335.178 = whole work done upon each square inch.

By the formula, the whole work done per stroke is

$$\begin{aligned}
 &= qp \left(1 + \log \frac{l}{q} \right) = 2 \times 60 \left(1 + \log \frac{12}{2} \right) \\
 &= 120 (1 + \log 6) = 120 (1 + 1.79175) \\
 &= 120 \times 2.79175 = 335.01,
 \end{aligned}$$

which is very nearly the same as that deduced by the rule.

Since the resistance from uncondensed vapour is 4 lbs. per square inch, then $12 \times 4 = 48$ lbs. = whole resistance, and by subtracting this from 335.178, the whole work done per square inch, there will remain $335.178 - 48 = 287.178$ for the effective work.

To find the advantage derived from working steam expansively.

When the steam works without expansion, then $12 \times 60 = 720$ = work done upon each square inch; but as the steam is cut off at $\frac{1}{3}$ of the stroke in working it expansively, there is only $\frac{1}{3}$ of the quantity of steam used in this case, or $\frac{720}{3} = 240$ lbs. per square inch, and $335.178 - 240 = 95.178$ lbs. gained in this case; or $\frac{335.178}{240} = 1.3965$ = nearly 1.4 times as much work done by the same quantity of steam, when worked expansively.

The work required to move the load to the end of the stroke is 12 L, and the work of the steam has been expended to produce this effect;

$$\therefore 12 L = 335.178$$

$$\text{or, } L = \frac{335.178}{12} = 27.9315 \text{ lbs. per square inch.}$$

If s be the distance moved over by the piston, when it attains its greatest velocity, then by Mariotte's law,

$$s : 2 :: 60 : 27.9315,$$

$$\text{whence } s = \frac{60 \times 2}{27.9315} = 4.3.$$

By the formula,

$$s = \frac{l}{1 + \log \frac{l}{q}} = \frac{12}{1 + \log 6} = \frac{12}{2.79175} = 4.3$$

nearly, the same as above.

Example 3.—To find the pressure per square inch at which the steam must be admitted when the load is 22 lbs. per square inch, the length of the stroke 5 feet, and the steam is cut off at 2 feet; the resistance from uncondensed vapour being 2 lbs. per square inch.

Let k = pressure per square inch; then $P = x$, and by taking the distances at every $\frac{1}{2}$ foot beyond 2 feet, where the steam is cut off, there will result

$$\frac{5}{2} : 2 :: x : P_1,$$

$$\therefore P_1 = \frac{4x}{5};$$

and by proceeding in a similar manner, the successive pressures for every $\frac{1}{2}$ inch of the remaining 3 inches, there will result,

$$P_2 = \frac{2x}{3}, P_3 = \frac{4x}{7}, P_4 = \frac{x}{2}, P_5 = \frac{4x}{9}, \text{ and } P_6 = \frac{2x}{5},$$

$x + \frac{2}{5}x = \frac{7}{5}x$ = the sum of the greatest and least extreme pressures per square inch;

$4 \left(\frac{4x}{5} + \frac{4x}{7} + \frac{4x}{9} \right) = \frac{2288x}{315}$ = 4 times the sum of the even pressures;

and $2 \left(\frac{2x}{3} + \frac{x}{2} \right) = \frac{7x}{3}$ = twice the sum of the odd pressures;

$\therefore \frac{2288x}{315} + \frac{7x}{3} + \frac{7x}{5} = \frac{3464x}{315}$ = the sum of all the pressures after expansion. This sum, multiplied by $\frac{1}{2}$ of the intervening space, i. e. by $\frac{1}{2}$ of $\frac{1}{2}$ an inch = $\frac{1}{4}$, gives $\frac{1732x}{945}$ = work after expansion, and $2x$ is the work done before expansion;

$\therefore 2x + \frac{1732x}{945} = 22 \times 5 = 110$, or $x = 29$ lbs. per square inch nearly.

Note.—In the examples just given, referring to condensing engines, no account has been taken of the friction, clearance of the piston, and other minutiae; but after the mathematical theory has been given, examples will be added, in which all these resistances will be included, referring both to condensing and non-condensing engines. The object of giving the preceding examples is to enable the student to obtain an idea of the method of speedily arriving at something like an approximation to finding the horse-powers of any proposed condensing engine.

On the Resistances to the Pressure of the Steam in Non-condensing and Condensing Engines.

From the experiments made by Pambour and others, these resistances in non-condensing engines are as follow:—

The pressure of the atmosphere, which produces a resistance of about 15 lbs. per square inch; also the resistance arising from various parts of the engine—at a mean, the estimate is 1 lb. to the square inch for the unloaded engine; and an additional friction of $\frac{1}{7}$ of the effective pressure or useful load, for overcoming the friction of the loaded engine.

Supposing the pressure of the steam to be 90 lbs. per square inch; the resistances are 15 lbs. per square inch from the atmosphere, and 1 lb. for the friction of the unloaded engine; therefore $15 + 1 = 16$ lbs. must be taken from 90, which leaves 74; hence the load $+ \frac{1}{7}$ of the load is equal to 74 lbs., or $\frac{8}{7}$ of the load $= 74$; therefore the load $= \frac{74 \times 7}{8} = 64\frac{1}{2}$ lbs. = the effective pressure per square inch on the piston.

Hence the following RULE.—*To find the Load when Resistances are taken into account, viz., The Useful Load.*

From the pressure of the steam in the cylinder subtract 16, multiply the remainder by 7, and divide this product by 8, and the quotient will be the useful load.

Example.—Given the pressure of the steam in the cylinder 60 lbs. per square inch, to find the useful load.

By the rule,

$$\frac{(60 - 16) \times 7}{8} = 38\frac{1}{2} \text{ lbs.}$$

For condensing or low-pressure engines, instead of the

resistance of the atmosphere, we must take into account the resistance of the vapour in the condenser, which is generally estimated at 4 lbs. per square inch; in this case there results

load $+ \frac{1}{2}$ load $+ 1 + 4 =$ whole pressure of the steam.

Hence the following RULE.—*To find the Load when Resistances are taken into account, in the Condensing Engine.*

From the mean pressure of the steam subtract 5, and $\frac{1}{2}$ of the remainder is the useful load.

On the Evaporating Power of the Boiler.

The evaporating power of the boiler is of the utmost importance, and as it is the source of all efficient work produced by the steam engine, many very ingenious contrivances have been made to augment this evaporating power; these contrivances will hereafter be explained. The quantity of work done depends on the quantity of water evaporated, as well as on the temperature, and the pressure at which the steam is generated. Formulæ shall hereafter be given to find the relation between the volume of steam and the pressure, but the following experimental table will give results sufficiently correct for all practical purposes; it shows the volume which a cubic foot of water produces in the form of steam at the several different pressures, as well as the corresponding temperatures.

Total pressure in pounds per sq. inch.	Corresponding temperature by Fahrenheit's thermometer.	Volumes of the steam compared to the volume of the water that has produced it.	Total pressure in pounds per sq. inch.	Corresponding temperature by Fahrenheit's thermometer.	Volumes of the steam compared to the volume of the water that has produced it.
1	102.9	20954	14	209.0	1777
2	126.1	10907	15	213.0	1669
3	141.0	7455	16	216.4	1572
4	152.3	5696	17	219.6	1487
5	161.4	4624	18	222.6	1410
6	169.2	3901	19	225.6	1342
7	176.0	3380	20	228.3	1280
8	182.0	2985	21	231.0	1224
9	187.4	2676	22	233.6	1172
10	192.4	2427	23	236.1	1125
11	197.0	2222	24	238.4	1082
12	201.3	2050	25	240.7	1042
13	205.3	1903	26	243.0	1006

Total pressure in pounds per sq. inch.	Corresponding temperature by Fahrenheit's thermometer.	Volumes of the steam compared to the volume of the water that has produced it.	Total pressure in pounds per sq. inch.	Corresponding temperature by Fahrenheit's thermometer.	Volumes of the steam compared to the volume of the water that has produced it.
27	245.1	971	69	303.2	411
28	247.2	939	70	304.2	406
29	249.2	909	71	305.1	401
30	251.2	882	72	306.1	396
31	253.1	855	73	307.1	391
32	255.0	831	74	308.0	386
33	256.8	808	75	308.9	381
34	258.6	786	76	309.9	377
35	260.3	765	77	310.8	372
36	262.0	746	78	311.7	368
37	263.7	727	79	312.6	364
38	265.3	710	80	313.5	359
39	266.9	693	81	314.3	355
40	268.4	677	82	315.2	351
41	269.9	662	83	316.1	348
42	271.4	647	84	316.9	344
43	272.9	634	85	317.8	340
44	274.3	620	86	318.6	337
45	275.7	608	87	319.4	333
46	277.1	596	88	320.3	330
47	278.4	584	89	321.1	326
48	279.7	573	90	321.9	323
49	281.0	562	91	322.7	320
50	282.3	552	92	323.5	317
51	283.6	542	93	324.3	313
52	284.8	532	94	325.0	310
53	286.0	523	95	325.8	307
54	287.2	514	96	326.6	305
55	288.4	506	97	327.3	302
56	289.6	498	98	328.1	299
57	290.7	490	99	328.8	296
58	291.9	482	100	329.6	293
59	293.0	474	105	333.2	281
60	294.1	467	120	343.3	249
61	294.9	460	135	352.4	224
62	295.9	453	150	360.8	203
63	297.0	447	165	368.5	187
64	298.1	440	180	375.6	173
65	299.1	434	195	382.3	161
66	300.1	428	210	388.6	150
67	301.2	422	225	394.6	141
68	302.2	417	240	400.2	133

Examples on the Use of the foregoing Table.

Example 1.—Given the area of the piston of a high-pressure engine 400 square inches, the length of the stroke 4 feet, the evaporation of water in the boiler half a cubic foot per minute, the pressure of the steam in the cylinder 60lbs. per square inch; to find the useful load and the horse-powers of the engine.

By the rule, page 12,

$$\frac{(60 - 16) \times 7}{8} = 38.5 \text{ lbs.} = \text{useful load.}$$

To a pressure of 60 lbs. the corresponding volume in the table is 467, which being multiplied by the evaporating power of the boiler gives $467 \times \frac{1}{2} = 233\frac{1}{2}$ = number of cubic feet evaporated per minute.

The number of cubic feet discharged per stroke is equal to the area of the piston in feet, multiplied by the length of the stroke in feet $= \frac{400}{144} \times 4 = \frac{1600}{144} = 11\frac{1}{3}$.

The whole volume discharged per minute is equal to the number of strokes per minute, multiplied by the volume discharged at one stroke; and the volume discharged per minute must be equal to the volume evaporated per minute.

Number of strokes per minute $\times 11\frac{1}{3}$ = whole discharge in one minute = $233\frac{1}{2}$ lbs. evaporated also in one minute.

Hence the number of strokes

$$= \frac{233\frac{1}{2}}{11\frac{1}{3}} = 21.$$

But the useful work done in one stroke is

$$38.5 \times 400 \times 4 = 61600;$$

therefore the useful work per minute is

$$61600 \times 21 = 1293600;$$

and hence the horse-powers

$$= \frac{1293600}{33000} = 39\frac{1}{3}.$$

Example 2.—In a condensing engine the area of the

cylinder is 1440 square inches; the length of the stroke, including clearance, is 5 feet; the steam is cut off at 1 foot of the stroke; the clearance is $\frac{1}{4}$ of a foot; the pressure of the steam is 30 lbs. per square inch; the elasticity of the vapour in the condenser is 4 lbs.; the effective evaporation of the boiler is $\frac{1}{3}$ of a cubic foot per minute, and the resistances as usual: required, the useful load and the horse-powers.—*Tate's Mechanics*.

The space through which the piston moves before the steam is cut off is $= 1 - \frac{1}{4} = \frac{3}{4}$, and the whole length of the stroke is $= 5 - \frac{1}{4} = 4\frac{3}{4}$.

Then $\log(4\frac{3}{4} \div \frac{3}{4}) = \log 6.33 = 1.8453$, and $1.8453 + 1 = 2.8453$.

Hence $30 \times \frac{3}{4} \times 2.8453 = 64.01925 =$ the whole work done in one stroke.

$$\text{Mean pressure} = \frac{64.01925}{4\frac{3}{4}} = 13.48 \text{ lbs.}$$

By the rule, page 12, the useful load

$$= \frac{(13.48 - 5) \times 7}{8} = 7.42.$$

By the Table, one cubic foot of water expands into 882 cubic feet of steam, at a pressure of 30 lbs. per square inch.

Hence the volume of steam evaporated per minute is

$$\frac{1}{3} \times 882 = 176.4 \text{ cubic feet.}$$

The volume of steam discharged in one stroke is

$$\frac{1440}{144} \times 1 = 10 \text{ cubic feet.}$$

Hence the number of strokes per minute is

$$\frac{176.4}{10} = 17.64.$$

Now, the useful work per minute is found by multiplying together the area of the piston, the useful load, the length of the stroke, and the number of strokes per minute; hence

$$\text{Horse powers} = \frac{1440 \times 7.42 \times 4\frac{3}{4} \times 17.64}{33000} = 27.13.$$

THEORETICAL INVESTIGATION OF THE PROPERTIES OF STEAM.

Let s = number of feet described at any part of the stroke of the piston; p' = pressure when that part is described; q = number of feet described before the steam is cut off, and l = length of the stroke in feet: by Mariotte's law,

$$p' : p :: q : s,$$

$$\text{whence } p' = \frac{qp}{s}.$$

Hence the variable work $\int \frac{qp ds}{s}$ done by expansion, taken between proper limits, is

$$\int_q^l \frac{qp ds}{s} = qp (\log l - \log q) = qp \log \frac{l}{q}.$$

Put $\lambda = \frac{l}{q}$; then the work done by expansion will be represented by $qp \log \lambda$; and the work done before expansion is evidently represented by qp .

Hence the whole work done per square inch, both before and after expansion, is

$$qp + qp \log \lambda = qp (1 + \log \lambda). \quad (\text{Rule 1, page 3}).$$

Let L = load per square inch; then Ll = work exerted upon the load by each stroke; and as the work of the steam must be equal to the work done upon the load, there results

$$Ll = qp (1 + \log \lambda),$$

$$\therefore L = \frac{qp}{l} (1 + \log \lambda). \quad (\text{Rule 2, page 3}).$$

From the above formula there evidently results

$$p = \frac{Ll}{q (1 + \log \lambda)}. \quad (\text{Rule 3, page 3}).$$

To determine the velocity of the piston when any part of

* The logarithms here used are the hyperbolic.

the stroke is described, the principle of *vis viva** must be applied. Poncelet has demonstrated, in his *Mechanique Industrielle*, that the work accumulated in any body or machine is half the *vis viva*; so that if U = the units of work done upon any load or body, the weight of which is W , and through any space s , U' = the units of work expended upon the resistance which opposes the motion of the body through the same space; then $U - U'$ = the units of work accumulated in the body; now, if V = velocity of the body, and g = accelerative force of gravity, the *vis viva* is $\frac{W}{g} \cdot V^2$; therefore the accumulated work is

$$\frac{1}{2} \cdot \frac{W}{g} \cdot V^2 = U - U'.$$

Assuming that the whole mass or body moves with the same velocity as the piston, the work done upon each square inch by the steam, when s feet of the stroke have been described, is

$$qp \left(1 + \log \frac{s}{q} \right);$$

and the work expended on the load up to that point is $L \cdot s$; therefore the work accumulated upon each square inch of the piston will be expressed by

$$qp \left(1 + \log \frac{s}{q} \right) - Ls;$$

or, if r = radius of the piston, and $\pi = 3.1416$, then

$$\pi r^2 \left\{ qp \left(1 + \log \frac{s}{q} \right) - Ls \right\} = U - U',$$

which is the accumulated work on the whole piston;

$$\therefore \frac{WV^2}{2g} = \pi r^2 \left\{ qp \left(1 + \log \frac{s}{q} \right) - Ls \right\},$$

$$\text{and } V^2 = \frac{2\pi g r^2}{W} \left\{ qp \left(1 + \log \frac{s}{q} \right) - Ls \right\};$$

* The *vis viva* of a body is its mass multiplied by the square of its velocity.

whence, by substituting for L its value, $\frac{qp}{l}(1 + \log \lambda)$, there results

$$\begin{aligned} V^2 &= \frac{2\pi g r^2}{W} \left\{ qp \left(1 + \log \frac{s}{q} \right) - \frac{qp^2}{l} (1 + \log \lambda) \right\} \\ &= \frac{2\pi g qp r^2}{W} \left\{ 1 + \log \frac{s}{q} - \frac{s}{l} (1 + \log \lambda) \right\}. \end{aligned}$$

To find when the velocity of the piston is a maximum, the part of the above formula within the vinculum must be a maximum, that is,

$$1 + \log \frac{s}{q} - \frac{s}{l} (1 + \log \lambda) \text{ must be a maximum;}$$

$$\text{or, } 1 + \log s - \log q - \frac{s}{l} (1 + \log \lambda) = \text{maximum,}$$

which put $= u$; then by differentiation,

$$\frac{du}{ds} = \frac{1}{s} - \frac{1}{l} (1 + \log \lambda) = 0,$$

$$\text{whence } s = \frac{l}{1 + \log \lambda}.$$

The maximum is indicated by $\frac{d^2u}{ds^2}$, being evidently negative; hence the value of s , being substituted in the formula for the velocity, gives

$$\begin{aligned} V^2 &= \frac{2\pi g q p r^2}{W} \left\{ 1 + \log \frac{l}{q(1 + \log \lambda)} - \frac{1}{1 + \log \lambda} (1 + \log \lambda) \right\} \\ &= \frac{2\pi g q p r^2}{W} \left\{ \log \frac{l}{q(1 + \log \lambda)} \right\} \text{ for the greatest or} \end{aligned}$$

maximum velocity.

This result can be obtained without the aid of the Differential Calculus. See Professor Hann's edition of "Tredgold on the Steam Engine;" see also his "Theory of the Steam Engine," page 98.

PAMBOUR'S THEORY OF THE STEAM ENGINE.

Pambour, in his excellent work on this subject, grounds his theory on the two following principles:—

First, *that the engine having attained uniform motion, there is necessarily an equilibrium between the pressure of the steam in the cylinder, and the resistance against the piston, that is*

$$p = R \dots \dots \dots (1)$$

R being the whole resistance against the piston.

Secondly, *that there is necessarily an equality between the production of steam and its expenditure.*

Let P = pressure of steam in the boiler, A = area of the piston, v = velocity of the piston in a unit of time, S = volume of water evaporated in the same unit of time, m = ratio of the volume of steam formed under the pressure P of the boiler to the volume of water that has produced it; then $m S$ will be the volume of steam formed in the same unit of time under the pressure P; and assuming, according to Mariotte's law, that the temperature remains the same, the volume $m S$ of steam supplied each unit of time by the boiler

when transmitted to the cylinder, will become $m S \cdot \frac{P}{p}$; and

A v being the expenditure of steam, the second principle can be expressed as follows:—

$$A v = m S \cdot \frac{P}{p} \dots \dots \dots (2)$$

But by equation (1) $p = R$,

$$\therefore A v = m S \cdot \frac{P}{R} \dots \dots \dots (3)$$

If the unit of time be one minute, and N the number of strokes in that time, l being the length of the stroke, and q the space described before the steam is cut off; then

$$v = N l, \text{ or } N = \frac{v}{l};$$

and since the expenditure of steam per minute is

$$A q N,$$

there evidently results $\frac{A q v}{l} = \text{expenditure of steam.}$

Hence, by substitution, equation (2) becomes

$$\frac{A q v}{l} = m S \cdot \frac{P}{p}$$

$$\therefore p = \frac{m S P l}{A q v}.$$

Now, the whole work done per square inch, both before and after expansion, is

$$q p (1 + \log \lambda), \lambda \text{ being } = \frac{l}{q}, \text{ as before ;}$$

and the pressure of the steam in the cylinder is evidently

$$A q p (1 + \log \lambda);$$

and, if R be the resistance per square inch against the piston, the whole resistance will be expressed by

$$R \cdot A l;$$

hence, by the first principle, there results

$$A q p (1 + \log \lambda) = R \cdot A l,$$

$$\text{or, } q p (1 + \log \lambda) = R l \dots\dots\dots (4)$$

$$\text{but } p = \frac{m S P l}{A q v}$$

$$\therefore \frac{m S P l}{A v} (1 + \log \lambda) = R l;$$

$$\text{hence } v = \frac{m S P}{A R} (1 + \log \lambda) \dots (5)$$

This is the same formula as that deduced by Pambour, in a different manner, at page 107 of his work, when the clearance is neglected.

But when the clearance is taken into account, the work done per square inch, both before and after expansion, becomes

$$p (q + c) \log \left(\frac{l + c}{q + c} \right) + q p$$

hence the first relation becomes

$$A \left\{ p (q + c) \log \left(\frac{l + c}{q + c} \right) + qp \right\} = R A l,$$

$$\text{or } p (q + c) \left\{ \frac{q}{q + c} + \log \left(\frac{l + c}{q + c} \right) \right\} = R l.$$

For the second relation there will result

$$\frac{A v (q + c)}{l} = m S \cdot \frac{P}{p},$$

$$\therefore v = \frac{m S P}{A R} \left\{ \frac{q}{q + c} + \log \left(\frac{l + c}{q + c} \right) \right\} \dots\dots (6)$$

c being the clearance.

The relation between the pressure and temperature of steam is of such great importance that numerous experiments have been made, both in this country and in France, to ascertain the pressure when the temperature is known, or to determine the temperature when the pressure is known. These important subjects will be forthwith detailed.

Arago and Dulong made the most extensive and careful experiments ever yet undertaken on this important subject, at the expense of the French government; these experiments range from 15 lbs. to 360 lbs. per square inch of pressure, or from 1 to 24 atmospheres; and the following formula has been the result of the researches of these eminent philosophers, which will represent temperature as compared with the pressure, without any sensible error,

$$p = (26973 + .0068031 t)^5 \dots\dots\dots (7)$$

$$\text{whence } t = 146.96 \sqrt[5]{p} - 39.644;$$

in which p is the pressure in pounds per square inch, and t the temperature in degrees of Fahrenheit.

Tredgold's formula for pressures from 1 to 4 atmospheres is sufficiently accurate, and is as follows,

$$p = \left(\frac{103 + t}{201.18} \right)^6 \dots\dots\dots (8)$$

$$\text{whence } t = 201.18 \sqrt[6]{p} - 103.$$

Pambour's formula for the same range is the following,

$$p = \left(\frac{98.8 + t}{198.56} \right)^6 \dots\dots\dots (9)$$

$$\text{whence } t = 198.56 \sqrt[6]{p} - 98.8.$$

An important property of elastic fluids has been discovered by the famous Gay-Lussac, *i. e.*, that if the temperature of a given weight of any elastic fluid be made to vary, it will acquire augmentations of volume exactly proportional to the augmentations of temperature, and for every increase of one degree of temperature of Fahrenheit's thermometer there will be produced an increase of .00202 of the volume of the fluid from the temperature of 32°.

If v be the volume of any given weight of elastic fluid under any pressure, and at 32° of Fahrenheit's scale, the volume v_1 which it will occupy under the same pressure, and at any other temperature t of Fahrenheit, will be

$$v_1 = v + v \times .00202 (t - 32).$$

This will also hold if we put the ratio of the relative volumes u and u_1 , instead of the ratio of the absolute volumes v and v_1 ; there will thence result,

$$\frac{u}{u_1} = \frac{1 + .00202 (t - 32)}{1 + .00202 (t' - 32)}.$$

Neither the law of Gay-Lussac nor that of Mariotte will apply to the variations which take place in the steam while in contact with the water from which it is evaporated; but from the two laws a third law may be obtained, by which the variations of the volume of steam, when there is a change in both the temperature and pressure at the same time, may be determined. When it is required to find the volume of a given weight of steam, which changes from the temperature t' and the pressure p' to the temperature t and the pressure p , it may be assumed that the steam passes first from the pressure p' to the pressure p without changing its temperature, then by Mariotte's law there will result,

$$u'' = u, \frac{p'}{p}.$$

Again, assume that the steam passes from the temperature

t' to the temperature t without any change of pressure; then, by the law of Gay-Lussac, there results,

$$u = \frac{\{1 + \cdot00202 (t - 32)\}}{\{1 + \cdot00202 (t' - 32)\}} u_n = \frac{p'}{p} \frac{\{1 + \cdot00202 (t - 32)\}}{\{1 + \cdot00202 (t' - 32)\}} u_i.$$

As this formula gives the law of the relative volumes, when both temperature and pressure change at the same time, there must be substituted in the above formula the values of p' and t' , the pressure and temperature corresponding to each other in steam in contact with water, and there will result the required relative volumes. It is well known that under the pressure of the atmosphere, which is 14·7 lbs. per square inch, and at the temperature of 212° of Fahrenheit, the relative volume of steam in contact with the water from which it has been generated, is 1700 times that of the water, whence

$$u = 1700 \times \frac{14\cdot7}{p} \times \frac{1 + \cdot00202 (t - 32)}{1 + \cdot00202 (t' - 32)}.$$

By this equation, and any one of the equations, Arts. (7), (8), and (9), t may be eliminated. It will be preferable to use Tredgold's formula for pressures from 1 to 4 atmospheres, and from 4 and upwards, that of Dulong and Arago.

It will now be proper to give the formulæ, showing the relation between the pressure and volume, derived from experiment, where the principle of expansion is used in the steam engine.

Pole gives the following formula,

$$P = \frac{24250}{V - 65} \dots\dots\dots (a)$$

$$\text{whence} \quad V = \frac{24250}{P} + 65.$$

Here P is the pressure in pounds per square inch, and V its relative volume compared with that of its constituent water.

The accuracy of this formula may be relied upon throughout the range generally required in the Cornish engines, *i. e.*, from 65 lbs. to 5 lbs.

Pambour gives for condensing engines,

$$u = \frac{10000}{\cdot4227 + \cdot00258 p}; \dots\dots\dots (b)$$

and for non-condensing engines,

$$u = \frac{10000}{1.421 + .0023 p}; \dots\dots\dots (c)$$

in which u is the volume and p the pressure in pounds per square foot.

Navier gives the following formula,

$$u = \frac{1000}{.09 + .0000484 p}; \dots\dots\dots (d)$$

in which u is the volume corresponding to the pressure p expressed in kilogrammes per square metre.

Let it be assumed that a volume of water E is converted into steam at a pressure p , and that M is the volume of steam which can be produced by it; then, by giving the preceding formulæ more general application, we may take

$$u = \frac{M}{E} = \frac{1}{\alpha + \beta p} \dots\dots\dots (e)$$

Now, if the same volume of water be converted into steam at the pressure p_1 , and M_1 be the corresponding volume of steam, there will result $\frac{M_1}{E} = \frac{1}{\alpha + \beta p_1}$; whence, between the absolute volumes of steam, which correspond to the same weight E of water, there will result, by eliminating E by means of formula (e), the following relation,

$$\frac{M}{M_1} = \frac{\frac{\alpha}{\beta} + p_1}{\frac{\alpha}{\beta} + p},$$

$$\therefore p = \frac{M_1}{M} \left(\frac{\alpha}{\beta} + p_1 \right) - \frac{\alpha}{\beta}, \dots\dots\dots (f)$$

in which α and β are the constants in Pambour's formula.

By proceeding in the same manner with Pole's formula there results,

$$\frac{M_1}{M} = \frac{\frac{\alpha}{P_1} + \beta}{\frac{\alpha}{P} + \beta}, \dots\dots\dots (g)$$

for the ratio of the volumes, where $\alpha = 24250$ and $\beta = 66$.

Pambour states that he has found, from a great number of experiments, that the steam, during its action in the cylinder, is always in the condition of maximum density for its temperature, and that when the pressure of the steam changes therein, its temperature changes at the same time, and that they always preserve that relation, which connects the pressures and temperatures of the steam in contact with the water from which it is generated.

ON THE WORK PERFORMED ON THE PISTON OF A STEAM ENGINE IN A GIVEN TIME.

Put A = area of the piston in square feet,

P = pressure in the boiler,

p = pressure at the x th foot of the stroke,

p' = pressure in the cylinder before expansion,

l = actual length of the stroke,

q = that part of the stroke before the steam is cut off,

c = the clearance,

E = number of cubic feet of water converted into steam per minute,

N = number of single strokes per minute,

and U = units of work of the steam per minute.

Since each cubic foot of water, converted into steam existing in the cylinder before expansion, begins under a pressure p' , it therefore occupies a relative space by formula (e), represented by

$$u = \frac{1}{\alpha + \beta p'};$$

while the number of cubic feet of water which is evaporated in the boiler, and passes into the cylinder in the form of steam at every stroke of the piston, is represented by $\frac{E}{N}$; therefore the space occupied in cubic feet in the cylinder, when the valve is closed and expansion begins, will be represented by

$$\frac{E}{N} \left(\frac{1}{\alpha + \beta p'} \right).$$

In the same manner the space occupied at the x th foot

of the stroke, when the pressure p' becomes p , will be expressed by

$$\frac{E}{N} \left(\frac{1}{\alpha + \beta p} \right).$$

But that space in the cylinder, filled with steam before expansion begins, is also represented by $A (q + c)$; and the space in the cylinder occupied at the x th foot of the stroke by $A (x + c)$. Hence there results the following equations,

$$\frac{E}{N} \left(\frac{1}{\alpha + \beta p} \right) = A (x + c),$$

$$\text{and } \frac{E}{N} \left(\frac{1}{\alpha + \beta p'} \right) = A (q + c);$$

whence from the former equation,

$$N (\alpha + \beta p) = \frac{E}{A (x + c)} \dots \dots (k)$$

and from the latter,

$$N = \frac{E}{A (q + c) (\alpha + \beta p')};$$

$$\therefore p = \frac{E}{AN} \cdot \frac{1}{\beta (x + c)} - \frac{\alpha}{\beta} \dots \dots \dots (k)$$

But the work done by expansion per square foot upon the piston is expressed by $\int_q^l p dx$, and by substitution from (k) there results,

$$\begin{aligned} \int_q^l p dx &= \frac{E}{AN\beta} \cdot \int_q^l \frac{dx}{x + c} - \int_q^l \frac{\alpha dx}{\beta} \\ &= \frac{E}{AN\beta} \cdot \log \left(\frac{l + c}{q + c} \right) - \frac{\alpha}{\beta} (l - q); \end{aligned}$$

which expresses the whole work done by expansion; and, since the pressure upon the piston, before expansion begins, is represented by p' , and that it moves q feet under this

pressure, whence the work performed on each square foot is, by formula (k), represented by

$$qp = \frac{E}{A N \beta} \left(\frac{q}{q+c} \right) = \frac{a q}{\beta};$$

therefore the sum of these two values is the whole work done upon each square foot of the piston, both before and after expansion, which sum is

$$\frac{E}{A N \beta} \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\} - \frac{a}{\beta} l;$$

which, being multiplied by $A N$, will give the whole work done on the piston per minute, or

$$U = \frac{E}{\beta} \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\} - \frac{a A N l}{\beta} \dots (m)$$

Now, the work produced by the power per minute must be equal to the resistance, when the engine has attained uniform motion, and R being the whole resistance, there results

$$\frac{E}{\beta} \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\} - \frac{a}{\beta} \cdot A N l = A N R l,$$

$$\text{and } A N l \left(R + \frac{a}{\beta} \right) = \frac{E}{\beta} \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\}.$$

By substituting v , in the last formula, for its equal $N l$, which represents the velocity of the piston per minute, there results

$$A v \left(R + \frac{a}{\beta} \right) = \frac{E}{\beta} \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\},$$

$$\text{whence } v = \frac{E}{A (a + \beta R)} \cdot \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\} \dots (n)$$

The quantity R , being the whole resistance acting on a unit of surface of the piston, comprehends the resistance arising from the useful load, and from friction.

Let the resistance from the motion of the useful load $= \rho$, the friction of the unloaded engine $= f$, the quantity the friction is augmented by each unit of the useful load $= \delta$, and the resistance from imperfect condensation $= h$; then

$$Z = \rho (1 + \delta) + f + h.$$

By substituting this value of R in formula (n) there results

$$v = \frac{E}{A} \cdot \frac{1}{\alpha + \beta \{ (1 + \delta) \rho + f + h \}} \cdot \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\} \dots (o)$$

When the engine does not work expansively; then $q = l$, and

$$v = \frac{E}{A} \cdot \frac{1}{\alpha + \beta \{ (1 + \delta) \rho + f + h \}} \cdot \left(\frac{l}{q+c} \right) \dots\dots (p)$$

since $\log \left(\frac{l+c}{q+c} \right)$ becomes $\log \left(\frac{l+c}{l+c} \right) = \log 1 = 0$.

One of Pambour's fundamental formula is (o), by means of which he determines the load for a given velocity, by finding ρ from it, which is the resistance for a unit of surface of the piston; and hence the load on the whole piston is $A\rho$, and

$$A\rho = \frac{E \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\}}{(1 + \delta) \beta v} - \frac{A}{1 + \delta} \cdot \left(\frac{\alpha}{\beta} + h + f \right) \dots (q),$$

and from formula (o), the evaporation of an engine to give motion to a load ρ , at the velocity v , is

$$E = A v \cdot \frac{\alpha + \beta \{ (1 + \delta) \rho + h + f \}}{\log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c}} \dots\dots\dots (r)$$

From formula (q), the useful effect which an engine can produce in a unit of time, at the velocity v , is

$$A\rho v = \frac{E \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\}}{(1 + \delta) \beta} - \frac{A v}{1 + \delta} \cdot \left(\frac{\alpha}{\beta} + h + f \right) \dots (s)$$

The useful effect in terms of the load is found by multiplying formula (o) by $A\rho$, and there results

$$A\rho v = \frac{E\rho \left\{ \log \left(\frac{l+c}{q+c} \right) + \frac{q}{q+c} \right\}}{\alpha + \beta (1 + \delta) \rho + h + f} \dots\dots\dots (t)$$

which, being divided by 33,000, will give the horse-powers of the engine.

Pambour takes $h = 4$ lbs. per square inch, and $f = .5$ lbs., consequently $h + f = 4.5$ lbs. per square inch, or $144 \times 4.5 = 648$ lbs. per square foot, $c = .05 l$, and $1 + \delta = 1.14$ lbs.

ON THE DUTY OF THE STEAM ENGINE.

The *duty* of an engine is the amount of work yielded by that engine from the combustion of a given quantity of coals, as a bushel or cwt.; and is, therefore, a measure of cost with respect to fuel.

Mr. Pole, who is the highest authority in this country on these subjects, when speaking of the great duty of the Cornish engines, observes, "Another cause of the great duty is the *use of high-pressure steam*. This is not only advantageous indirectly, inasmuch as it enables the expansive principle to be applied with greater effect, but there is a totally distinct economical advantage in the use of high-pressure steam *per se*, which is often overlooked, and deserves special mention. It is founded on the principle, *that the pressure of the steam* increases in a greater ratio than its density; whence it follows that the higher the pressure the steam is raised to, the less *proportionate* quantity of water it contains, and therefore the less fuel is consumed, since a given quantity of fuel will evaporate the same weight of water at all temperatures."

Mr. Pole gives, at page 169 of his work on the Cornish Engine, the following example:—

Example.—A Cornish engine, with a cylinder 70 inches in diameter, and a 10-foot stroke, has the steam admitted at a pressure of 45 lbs. to the square inch (*i. e.*, 30 lbs. above the atmospheric pressure) during $\frac{1}{3}$ of the stroke, and during the remainder the steam is allowed to expand; required the duty of the engine.

The diameter of the cylinder being 70 inches, the area is 3848 square inches, which multiplied by 45 lbs., the pressure on each square inch, give the whole pressure on the piston = 173160 lbs. This weight is moved through $1\frac{2}{3}$ feet, the space during which the steam is admitted; hence a quantity of work = $173160 \times 1\frac{2}{3} = 288600$ lbs. raised one foot high before the steam is cut off.

Hence the whole work on the piston, both before and after the expansion, by Rule 1, is

$$288600 (1 + \log 6) = 288600 \times 2.79176 = 805702 \text{ lbs.}$$

Since the area of the cylinder is 3848 square inches, and the steam is admitted during $1\frac{2}{3}$ feet = 20 inches of the stroke, the quantity of fuel consumed to do the above work

$= 20 \times 3848 = 76960$ cubic inches; and since the relative densities of water and steam at 45 lbs. pressure are as 1 to 608 (see table, p. 13), this volume of steam will contain $\frac{76960}{608} = 126$ cubic inches of water; and as each cubic foot of water $= 1728$ cubic inches, weighs 62.5 lbs., we shall have

$$1728 : 126 :: 62.5 : 4.55,$$

that is, 126 cubic inches of water weighs 4.55 lbs.

Now it has been found by experiment that 1 lb. of coal will evaporate 9.27 lbs. of water; hence the quantity of coal required for each stroke $= \frac{4.55}{9.27} = .49$ lbs. $=$ nearly $\frac{1}{2}$ lb. of coal, which is required for each stroke, to produce a motive power of 805702 lbs. raised one foot high. At this rate, one bushel $= 94$ lbs. of coal will give the following amount,

$$\frac{805702 \times 94}{.49} = 154,563,445 \text{ lbs.,}$$

which is a very large duty; but this duty will be somewhat reduced by taking in the minutiae given in formula (t).

If B = number of bushels of coals consumed in an engine in any given time $= t$ minutes, D = duty of the engine, and U = units of work per minute; then $U t$ = units of work yielded by the engine while B bushels of coals are being consumed; hence $\frac{U t}{B}$ will be the units of work yielded by each bushel of coals consumed by that engine; therefore,

$$D = \frac{U t}{B}.$$

To find the Point at which the Steam must be cut off to obtain the greatest quantity of Useful Work.

By multiplying formula (h) by l there results

$$N l = \frac{E l}{A (q + c) (\alpha + \beta p')},$$

and, since $N l = v$, by substitution,

$$v = \frac{E l}{A (q + c) (\alpha + \beta p')},$$

in which, by putting P the pressure in the boiler for p' , there will result the *velocity v' for the maximum useful effect*,

$$v' = \frac{E l}{A (q + c) (a + \beta P)};$$

which, being substituted in formula (s), gives

$$A p v' = \frac{E}{(1 + \delta) \beta} \left\{ \log \left(\frac{l + c}{q + c} \right) + \frac{q}{q + c} - \frac{l}{q + c} \cdot \frac{a + \beta(h + f)}{a + \beta P} \right\}.$$

By differentiating this formula for q , the part of the stroke where the steam should be cut off so as to give the useful effect a maximum, or the greatest possible, there results

$$\frac{q}{l} = \frac{a + \beta(h + f)}{a + \beta P},$$

$$\text{or} \quad \frac{q}{l} = \frac{1}{a + \beta(h + f)},$$

that is, in other words,

$$\frac{q}{l} = \frac{\text{volume at pressure } P}{\text{volume at pressure } p'}$$

By formula (u), given by Pole, this will become

$$\frac{q}{l} = \frac{\frac{a}{P} + \frac{a}{h + f} + \beta}{\frac{a}{h + f} + \beta}, \quad \text{or} \quad q = l \cdot \frac{\frac{a}{P} + \beta}{\frac{a}{h + f} + \beta},$$

in which $a = 24250$, and $\beta = 65$.

Example 1.—Let the length of the stroke of the piston be 10 feet, the pressure of the steam 40 lbs. per square inch, and the useless resistance $h + f = 5$ lbs.; it is required to find at what part of the stroke the steam must be cut off to give the greatest amount of useful work.

By the preceding formula

$$q = 10 \cdot \frac{\frac{24250}{40} + 65}{\frac{24250}{5} + 65} = 1.36 \text{ feet,}$$

the required part of the stroke where the steam must be cut off to give the greatest amount of useful work.

Example 2.—The length of the stroke, including clearance, which is $\frac{1}{2}$ foot, is 10.5 feet, the pressure of the steam in the cylinder is 50 lbs. per square inch, the elasticity of vapour in the condenser is 4 lbs., and the whole resistance from friction $2\frac{1}{2}$ lbs. per square inch; required the point at which the steam must be cut off to produce the maximum or greatest effect.

By Pole's formula,

$$q = \frac{\frac{a}{P} + \beta}{\frac{a}{h+f} + \beta} \cdot l = \frac{\frac{24250}{50} + 65}{\frac{24250}{6.5} + 65} = \frac{550 \times 10.5}{3795.7} = 1.52,$$

which is the part of the stroke where the steam must be cut off, including clearance.

Example 3.—Let the surface of the piston A be 1800 square inches, the effective evaporation E be .927 cubic feet per minute, the length of the stroke before the steam is cut off q be $1\frac{1}{2}$ feet, the other data being as in Example 2; required the number of strokes per minute.

$$\frac{A N q}{144} = E \left(\frac{24250}{50} + 65 \right),$$

$$\therefore N = \frac{144 \times 550 \times .927}{1800 \times 1.5} = 27,$$

which is the number of strokes of the piston to produce the maximum, or greatest effect.

Having now given the mathematical theory of the steam engine, with a variety of examples of its use, it will now be proper to advert to the different appendages of that splendid power.

ON THE SAFETY VALVE OF THE STATIONARY ENGINE.

In the appendix to "Tredgold on the Steam Engine," the following rule is given to find the area of the aperture for the safety valve:—

Divide the area of the fire-surface by the excess of pressure in the boiler above that of the atmosphere in pounds per

square inch, and the quotient will be the square of the diameter of the narrowest part of the aperture in inches.

The safety valve is usually loaded by means of a lever, with a weight to move along it to suit the required pressure.

To find the Pressure on the Valve to each Square Inch, when the whole Weight is put upon the Valve.

Multiply the square of the diameter of the valve by $\cdot 7854$, and the product will give the area, or number of square inches in the valve; then divide the whole weight upon the valve in pounds by the number of square inches in the valve, and the quotient will give the number of pounds of pressure to each square inch in the valve.

Example.—If a weight of 112 lbs. be placed upon the valve, the diameter of which is 3 inches, required the pressure to each square inch.

$3^2 \times \cdot 7854 = 7$ square inches nearly; then $112 \div 7 = 16$ lbs., the required pressure per square inch.

ON THE LEVER OF THE SAFETY VALVE.

In addition to the weight moving along the lever, the weight of the lever must also be taken into the calculation; for when the lever is large, and the aperture of the valve small, the weight of the lever is such as to produce a very sensible pressure upon the valve.

The calculation for graduating the lever is as follows:—Divide the length by the distance between the fulcrum and valve, and the quotient is the leverage, which, multiplied by the weight, gives the whole weight on the valve; and this product, divided by the number of square inches in the valve, gives the pressure per square inch in the boiler.

Or, if the weight per square inch be known, multiply that weight by the number of square inches in the aperture of the valve, and this product gives the whole weight upon the valve, which, divided by the leverage, gives the weight which must be put on the end of the lever.

Example.—Given the whole length of the lever 32 inches, the distance between the fulcrum and valve 4 inches, the diameter of the valve $2\frac{1}{2}$ inches; required the weight to be put on at the end of the lever, so as to have a pressure of 50 lbs. *per square inch upon the valve*; also to divide the lever so as

to have 40, 30, 20 lbs., &c., upon the valve with the same weight.

$$32 \div 4 = 8 = \text{leverage,}$$

$$(2.5)^2 \times .7854 = 4.9 = \text{area of the valve,}$$

$$4.9 \times 50 = 245 \text{ lbs.} = \text{whole weight on the valve,}$$

$$\frac{245}{8} = 30\frac{5}{8} \text{ lbs.} = \text{weight which must be put on at the}$$


end of the lever to give 50 lbs. per square inch,

$$\text{and } \frac{4.9 \times 40}{30\frac{5}{8}} = 6.4; \text{ then } 6.4 \times 4 = 25.6 \text{ inches} =$$

distance from the fulcrum at which the weight must be put to have a pressure on the valve of 40 lbs. And $32 - 25.6 = 6.4$ inches, the distance which the weight must be moved towards the fulcrum to have 40 lbs. pressure per square inch; and for 30 lbs. per square inch it must be moved 6.4 inches more, &c.

To graduate the Lever of the Safety Valve, the Weight of the Lever being considered.

Let A F be a graduated lever, turning on F as fulcrum; V the valve, which is raised when the elastic force of the steam becomes too great for the pressure of the weight W, B being a portion of the boiler.



Put $A F = L$, $V F = l$, W = weight at A, ω = weight of the lever A F, r = radius of the valve, and P = greatest pressure of the steam in the boiler. Then πr^2 = area of the aperture of the valve, $\pi r^2 P$ = pressure on the valve, and by the property of the lever,

$$L \times W + \frac{1}{2} L \times \omega = \pi r^2 P \times l, \text{ whence}$$

$$W = \frac{\pi r^2 l P - \frac{1}{2} L \omega}{L} \dots\dots\dots (1)$$

The weight W at the end of the lever may be determined from formula (1); after which the length L' , corresponding to any other pressure P' , may be found from the following formula, which is derived by substituting L' for L, and P' for P, in formula (1), and transposing, which gives

$$L' = \frac{\pi r^2 l P' - \frac{1}{2} L w}{W} \dots\dots\dots (2)$$

Example 1.—Required the weight W , when $A F = 24$, $V F = 3$ inches, weight of lever = 4 lbs., radius of the aperture of the valve = $1\frac{1}{2}$ inches, and the pressure P of the steam in the boiler = 40 lbs. per square inch.

Here the area of the valve $\pi r^2 = 3.1416 \times (1\frac{1}{2})^2 = 7.07$ square inches nearly, which, by omitting the small decimal, may be taken as 7 square inches; whence

$$W = \frac{\pi r^2 l P - \frac{1}{2} L w}{L} = \frac{7 \times 3 \times 40}{24} = 35 \text{ lbs.}$$

That is, 35 lbs. put at the end of the lever will give the required pressure. We have next to find the distance L' from F , at which the weight must be put on to give any other required pressure P' .

Example 2.—Let the pressure P' be 30 lbs. per square inch, all the other dimensions and weights being the same as in the last example; required the distance L' .

By formula (2),

$$L' = \frac{\pi r^2 l P' - \frac{1}{2} L w}{W} = \frac{7 \times 3 \times 30 - 12 \times 4}{35} = 16\frac{2}{3} \text{ inches,}$$


and $24 - 16\frac{2}{3} = 7\frac{1}{3}$ inches, which the weight W must be moved on towards F to give a pressure of 30 lbs. per square inch on the valve. Similarly, the distance on the lever may be found for a pressure of 20 lbs. to be $10\frac{2}{3}$ inches, or the weight W must be suspended at $24 - 10\frac{2}{3} = 13\frac{1}{3}$ inches from F , or $6\frac{2}{3}$ inches nearer to F than in the latter case, and a further distance of $6\frac{2}{3}$ towards F , to give a pressure of 10 lbs. per square inch: thus the graduation of the lever may be completed for any given pressure on the safety valve; for instance, if the intermediate pressures of 25 lbs., 15 lbs., &c., be required, the distance $6\frac{2}{3}$ inches must everywhere be divided into two equal parts, that is, $6\frac{2}{3} \div 2 = 3\frac{1}{3}$ inches, which will give the places where the weight must be suspended for these pressures.

THE FLY WHEEL.

When a moving power is supplied irregularly, as by the piston of a steam engine, the action of which is intermitting, or by impulses,—while numerous machines, with the exception of the pumping engines and a few others, require a regular force,—the method of regulating the motion of such machines is by means of a fly wheel, which is usually fixed on the crank-shaft of a stationary engine. The rim of this wheel consists of a ponderous mass of metal, revolving freely on its axis, and by its inertia produces a reservoir as well as a regulator of force; since a small surplus of force, acting for a short time, will accumulate a considerable power in the fly wheel; and this power, being applied suddenly for a short time, is capable of supplying the short intermissions of the moving power, and producing a near approximation to perfect regularity in the motion of the machinery. This method of regulating motion is not, for obvious reasons, applied to marine and locomotive engines.*

When the Force acts in one Direction only, to find the Limits within which the Angular Velocity of the Fly Wheel varies.

Let $ARQS$ be the fly wheel, O its centre, OR a crank, on which the rod PR acts in directions parallel to the diameter EF , and let P be a constant force acting on the rod PR ; also let Q be a weight equivalent to the resistance of the machine, and acting perpendicularly at Q the extremity of the radius OQ . Draw RH ; rh perpendicular to EF , and indefinitely near to each other; also put $RO = r$, $QO = l$, and $\pi =$ circumference to radius $= 1$. Now let the point R move through the indefinitely small space Rr ; then the force of P is measured by the product of the resolved part Rn of the force P and the small space Rr , which product is evidently $= P \times Rr = P \times Hh$, since the force nr is wholly ineffectual. Let the force P act from E to F , then Hh becomes $=$ the diameter EF , and the whole force from E to F will be $= P \times EF = P \times 2r$; and the whole dynamical effect of the resistance



* See pages 162, 163 of "A Treatise on Marine Engines." Weale's Ser

of the machine in one entire revolution, which is represented by Q , will be $= Q \times 2\pi R$; but since the whole effect of the force P is consumed by the useful and useless resistance of the machinery taken together, there will result

$$2Pr = 2Q\pi R,$$

$$\text{or,} \quad P = \frac{\pi QR}{r}.$$

Now, let the resistance Q just balance the force P , when the crank is in the two positions OR , OS ; and put the angle $ROA = \frac{1}{2}$ the angle $ROS = \phi$; then

$$Pr \cos \phi = QR;$$

and by substituting the value of P in this equation, there will result, after reduction,

$$\cos \phi = \frac{1}{\pi} = \frac{1}{3.1416} = .3183;$$

$$\therefore \phi = 71^\circ 26',$$

$$\text{and the arc } RAS = 2\phi = 142^\circ 52'.$$

Corollary.—For the double-acting engine we find in a similar manner,

$$\cos \phi = \frac{2}{\pi} = \frac{2}{3.1416} = .6366;$$

$$\therefore \text{arc } RS = 2\phi = 100^\circ 54'.$$

To find the Units of Work in the Fly Wheel, and the number of Revolutions which it will make before it stops.

Let the weight of the wheel $= W$ lbs., the external and internal radii of the rim respectively $= R$ and r feet, its number of revolutions per second $= s$, the diameter of its axis $= d$ inches, and the friction upon it $= \frac{1}{n}$ of the whole weight of the wheel, the inertia of the axle and spokes of the wheel being neglected as not materially affecting the result. (See last figure.)

$$\text{Then the radius of gyration } k = \sqrt{\frac{R^2 + r^2}{2}}. \quad (\text{See}$$

Baker's "Statics and Dynamics," Weale's Series.)

Units of work in the wheel

$$= s \left(2\pi \sqrt{\frac{R^2 + r^2}{2}} \right)^2 \times \frac{W}{2g}$$

$$= \frac{\pi^2 s^2 W}{g} (R^2 + r^2),$$

circumference of axis $= \frac{\pi d}{12},$

work destroyed by friction in one revolution

$$= \frac{\pi d}{12} \times \frac{W}{n} = \frac{\pi g W}{12 n}.$$

Now, put N = number of revolutions made by the wheel before it stops; then

whole work destroyed by friction $= \frac{\pi d W}{12 n} \times N,$

$$\therefore \frac{\pi d W}{12 n} \times N = \frac{\pi^2 s^2 W (R^2 + r^2)}{g};$$

whence $N = \frac{12 n \pi s^2 (R^2 + r^2)}{g d}.$

Note.—This result is independent of the weight of the wheel.

Example.—The external and internal radii of the rim of a fly wheel are 5 and 3 feet, it makes 3 revolutions per second, the diameter of the axle is 2 inches, and the friction upon it $\frac{1}{10}$ of the weight of the wheel, or $n = 10$; how many revolutions will it make before it stops?

By the preceding formula, the number of revolutions, or

$$N = \frac{12 \times 10 \times 3.1416 \times 3^2 (5^2 + 3^2)}{2 \times 32\frac{1}{2}} = 1720.$$

Practical Rules and Examples for the Fly Wheel of the Double-acting Engine.

The mean radius, the horse-powers, and the number of revolutions, or the number of double strokes per minute being given, to find the weight of the wheel.

RULE 1.—Multiply the number of horse-powers of the engine by 2275, and again by the denominator of the fraction

showing the variation from the mean velocity. Multiply the square of the mean radius by the cube of the number of revolutions per minute. Divide the former product by the latter, and the quotient will be the weight of the fly wheel in tons. See Hann and Gener's "Treatise on the Steam Engine," formula (21), p. 136.

Example.—A double-acting engine makes 15 revolutions per minute, the radius of the fly wheel is 15 feet, the horse-powers are 60; what must be the weight of the fly wheel, when the variation is $\frac{1}{40}$ from the mean velocity?

By the rule,

$$\frac{2275 \times 60 \times 40}{15^2 \times 15^3} = \frac{5460000}{759375} = 7.2 \text{ tons.}$$

RULE 2.—Multiply the number of horse-powers by the denominator of the fraction showing the variation from the mean velocity, divide the product by the area of the section of the rim of the fly wheel, and extract the cube root of the quotient.

Multiply the cube root just found by 12.17, and divide the product by the number of revolutions per minute, and the quotient will be the *mean radius*. See Hann and Gener's "Treatise," formula (22), p. 136.

Example.—A double-acting steam engine makes 10 revolutions per minute, the horse-powers are 60, the area of the section of the rim is 1.3 square feet, and the variation $\frac{1}{40}$ from the mean velocity; required the mean radius of the fly wheel.

By the rule,

$$\sqrt[3]{\frac{60 \times 40}{1.3}} = \sqrt[3]{1846.15} = 12.27,$$

$$\text{and } \frac{12.27 \times 12.17}{10} = 14.93 \text{ feet} = \text{mean radius of the wheel.}$$

RULE 3.—Multiply 1803 by the number of horse-powers, and again by the denominator of the fraction showing the variation from the mean velocity, and divide this product by the product of the cubes of the mean radius and of the number of revolutions per minute, and the quotient will be the *area of the section of the rim*.

Example.—A double-acting engine of 60 horse-powers makes 10 revolutions per minute, the mean radius of the

wheel is 12 feet, and the variation from the mean velocity is $\frac{1}{10}$; required the section of the rim of the fly wheel.

By the rule,

$$\frac{1803 \times 60 \times 20}{12^3 \times 10^3} = \frac{2163600}{1728000} = 1.252 \text{ feet.}$$

Practical Rules and Examples for the Fly Wheel of the Single-acting Engine.

The number of single strokes per minute, the mean radius, and the horse-powers being given, *to find the weight of the wheel.*

RULE 1.—Multiply the number of horse-powers by 94880, and again by the denominator of the fraction showing the variation from the mean velocity, and divide this product by the product of the square of the mean radius and of the cube of the number of single strokes per minute, and the quotient will be the weight of the wheel in tons. See Hann and Gener "On the Steam Engine," formula (14), p. 133.

Example.—A single-acting engine of 20 horse-powers makes 30 single strokes per minute, the mean radius of the wheel is 13 feet, and the variation is $\frac{1}{10}$ from the mean velocity; required the weight of the fly wheel.

By the rule,

$$\frac{20 \times 94880 \times 25}{13^2 \times 30^3} = \frac{47440000}{4563000} = 10.4 \text{ tons nearly.}$$

RULE 2.—Multiply the number of horse-powers by the denominator of the fraction showing the variation from the mean velocity, divide the product by the area of the section of the rim, and extract the cube root of the quotient; multiply the cube root, thus found, by 42.2, and divide the product by the number of single strokes per minute, and the quotient will be *the mean radius of the wheel.*

Example.—A single-acting engine of 60 horse-powers makes 40 single strokes per minute, the area of the section of the rim of the fly wheel is 1.2 square feet, and variation from the mean velocity $\frac{1}{10}$; required the mean radius of the wheel.

By the rule,


$$\sqrt[3]{\frac{60 \times 60}{12}} = \sqrt[3]{3000} = 14.4,$$

and $\frac{42.2 \times 14.4}{40} = 15.2$ feet nearly, the mean radius of the wheel.

THE GOVERNOR.

The governor is an apparatus for regulating the supply of steam from the boiler to the cylinder so as to give a constant and steady velocity to the engine.

A B is a vertical shaft turning freely on the sole B by its connection with the machinery of the steam engine ; C P,



C Q are two bars moving freely on the centre C, and carrying the two weights or balls P, Q ; F D, F E are two rods connected to the bars at D and E, and attached to the collar I, which is capable of sliding freely up and down the shaft A B. This collar is united to a

lever, which opens or closes the throttle valve, which supplies the cylinder with steam. When A B revolves too fast, the balls, by their centrifugal force, fly outwards, raising the slide I, and partially closing the throttle valve ; and when the shaft moves too slowly, the balls collapse, and the slide consequently descending, admits a more full supply of steam, thus regulating the engine to almost complete uniformity.

The ball or weight P is acted upon by two forces, *i.e.*, the centrifugal force in the direction P n, and gravity in the direction P o ; to represent these two forces, complete the parallelogram P n m o ; then we shall have the triangles P m o, A P O similar ; and, if *f* represent the centrifugal force, and W the weight of the ball P, then,

$$\frac{f}{W} = \frac{P O}{O O}.$$

Also, by Art. 277, Baker's "Statics and Dynamics," Weale's Series,

$$f = \frac{W \cdot V^2}{g \cdot P O},$$

and by substituting the value of f in the preceding equation, there results after reduction,

$$O O = \frac{g \cdot P O^2}{V^2},$$

or, if v = angular velocity per second of the governor, at a unit's distance from the shaft A B, then $V = P O \cdot v$, and by substitution,

$$O O = \frac{g}{v^2}.$$

Now, if n = number of revolutions per minute, then $\frac{n}{60}$ = number per second,

$$\therefore v = \frac{2\pi n}{60} = \frac{\pi n}{30},$$

$$\begin{aligned} \text{whence } O O &= \frac{30^2 \times g}{\pi^2 n^2} \text{ in feet,} \\ &= \frac{30^2 \times 32\frac{1}{8} \times 12}{(3.1416)^2 n^2} \text{ in inches,} \\ &= \frac{35200}{n^2} \text{ inches nearly.} \end{aligned}$$

Since the throttle valve of the steam engine cannot be opened without an adequate force exerted by the governor, which may be measured by finding what weight will produce that force: let p be the required weight, W being the weight of one the balls of the governor, as before; then Hann has shown in his works on the steam engine that

$$\frac{p}{W} = \frac{21}{100} \cdot \frac{O P}{C D},$$

and that, if $\frac{CP}{CD} = \frac{3}{2}$, which is the usual proportion in the governor,

$$\frac{p}{W} = \frac{21}{100} \cdot \frac{3}{2} = \frac{63}{200};$$

$$\therefore W = \frac{200p}{63} = 3.174p;$$

and, if $p = 10$ lbs., then $W = 31\frac{3}{4}$ lbs. nearly, the required weight of one of the equal balls.

PRACTICAL RULES AND EXAMPLES ON THE GOVERNOR.

There are two conditions in calculations for the governor; which are, to find the position of the point F, attached to the collar I (see last fig.), when the governor performs the required number of revolutions; and to find what should be the range of the balls, or the radius of the circle described by them, that the supply of steam through the throttle valve may give the engine a steady speed.

To find the Distance of the Plane, in which the Balls revolve, from their Point of Suspension.

RULE.—Divide 35200 by the square of the number of revolutions per minute, and the quotient will be the distance required.

Example.—Required the distance of the plane, in which the balls of the governor revolve, from the point of suspension, when it makes 30 revolutions per minute.

By the rule,

$$\frac{35200}{30^2} = \frac{35200}{900} = 39.11 \text{ inches.}$$

To find the Radius of the Circle described by the Balls.

RULE.—First, find the distance of the plane, in which the balls revolve, from their point of suspension, by the last rule. Secondly, from the square of the length of the arm subtract

the square of the distance last found, and the square root of the remainder will be the distance required.

Example.—The length of the arms of a governor is 30 inches, and it revolves 40 times per minute; required the radius of the circle described by the balls.

First, $\frac{35200}{40^2} = \frac{35200}{1600} = 22$ inches, the distance between the point of suspension and the plane of revolution.


Second, $\sqrt{30^2 - 22^2} = \sqrt{416} = 20.4$ inches, the radius of the circle described by the balls.

PRINCIPLES OF THE CRANK.

The crank is used for converting rectilinear into rotatory motion.

To establish the principle that there is no loss of power in the use of the crank in steam engines, the celebrated mathematician, Mr. Woolhouse, has given, in his edition of "Tredgold's Steam Engine," the following dynamical investigation.

In the annexed figure let $CD = r$ be the length of the connecting rod, $OD = \rho$ the radius of the crank, the angle $DOE = \alpha$, the velocity at $C = v$, the velocity at $D = v'$, and the distance $AC = x$;



then the perpendicular $DG = \rho \sin^2 a$, $CG = \sqrt{r^2 - \rho^2 \sin^2 a}$,
 $OG = \rho \cos a$, $CO = \sqrt{r^2 - \rho^2 \sin^2 a} + \rho \cos a$, $AO =$
 $r + \rho$, and \therefore the value of AC , or, $AO - CO$, is

$$\begin{aligned} x &= r + \rho - (\sqrt{r^2 - \rho^2 \sin^2 \alpha} + \rho \cos \alpha) \\ &= \rho (1 + \cos \alpha) + (r - \sqrt{r^2 - \rho^2 \sin^2 \alpha}) \dots (1) \end{aligned}$$

By differentiating this expression of the distance traversed by C, and dividing by dt , we obtain the velocity of the extremity C, viz.,

$$\frac{dx}{dt} = \frac{\rho d\alpha}{dt} \sin \alpha \left(\frac{\rho \cos \alpha}{\sqrt{r^2 - \rho^2 \sin^2 \alpha}} + 1 \right); \text{ that is,}$$

$$v = v' \sin \alpha \left(\frac{\rho \cos \alpha}{\sqrt{r^2 + \rho^2 \sin^2 \alpha}} + 1 \right) \dots\dots\dots (2)$$

But, if P denote the moving force acting at C in the direction CB , P' the effective force of D , and c the angle DCO ; then the force P , transferred in the direction of the connecting rod, becomes $P \sec c$, and this resolved in the direction of the tangent to the circle $= P \sec c (c + \alpha) =$

$$P (\tan c \cos \alpha + \sin \alpha); \text{ also } \tan c = \frac{\rho \sin \alpha}{\sqrt{r^2 - \rho^2 \sin^2 \alpha}};$$

$$\therefore H' = P \sin \alpha \left(\frac{\rho \cos \alpha}{\sqrt{r^2 - \rho^2 \cos^2 \alpha}} + 1 \right) \dots\dots\dots (3)$$

Equation (2) hence reduces to $v = v' \frac{P'}{P}$, and, therefore,

$$P v = P' v' \dots\dots\dots (4)$$

that is, the moving *power* at C is always equal to the effective power at D .

The moving force P being nearly uniform, the force P' expressed by the equation (*) will be materially different at different positions of the crank, and the velocity of the engine will, in consequence, be subject to small fluctuations in the course of each revolution. To ascertain the law of these variations, it will be necessary to have recourse to the usual equation of rotatory motion. Let R denote the real moment of the resistance, including friction, reduced to the point D , or the force, which uniformly applied along the circumference ED would just suffice to preserve the mean velocity of the engine without any variation; then P' being the force actually applied, the effective accelerating force, or the part tending to produce acceleration, will be $P' - R$; and where this is

negative, the velocity $\frac{d\alpha}{dt}$ must be retarded instead of acce-

lerated. If we now multiply the force $P' - R$ by ρ , the leverage at which it acts, the product $\rho (P' - R)$ is its moment or tendency to generate angular motion. Hence, if M designate the moment of the inertia to be overcome, and if we neglect, as comparatively insignificant, the slight varia-

tions of the resistance R due to the small changes of velocity; and suppose it to continue uniform, we shall have

$$M \frac{d^2 \alpha}{dt^2} = \rho (P' - R);$$

this being multiplied by $\frac{2 d \alpha}{dt}$, there results

$$\begin{aligned} M \frac{2 d \alpha}{dt} \frac{d^2 \alpha}{dt^2} &= 2 P' \rho \frac{d \alpha}{dt} - 2 R \rho \frac{d \alpha}{dt} \\ &= 2 \left(P' v' - R \rho \frac{d \alpha}{dt} \right) \\ &= 2 \left(P v - R \rho \frac{d \alpha}{dt} \right) \\ &= 2 \left(P \frac{d \alpha}{dt} - R \rho \frac{d \alpha}{dt} \right). \end{aligned}$$

Consequently, by integration,

$$\begin{aligned} M \left(\frac{d \alpha}{dt} \right)^2 &= 2 (P c + P x - R \rho \alpha), \\ \therefore \frac{d \alpha}{dt} &= \sqrt{\frac{2}{M} (P c + P x - R \rho \alpha)} \dots\dots\dots (5) \end{aligned}$$

Now the engine being supposed to have acquired her permanent speed, there can be no progressive acceleration, the same velocity must recur at the period of each revolution. The velocity at E is obtained by putting $x = 0$, $\alpha = 0$, and is

$$\left(\frac{d \alpha}{dt} \right)' = \sqrt{\frac{2}{M} P c} \dots\dots\dots (a)$$

Also, the velocity at H is obtained by putting $x = 2 \rho$, $\alpha = \pi$, and is

$$\left(\frac{d \alpha}{dt} \right)'' = \sqrt{\frac{2}{M} (P c + 2 P \rho - R \rho \pi)} \dots\dots\dots (b)$$

Again, it is to be observed that the preceding investigation equally applies to returning motion along HD° , pro-

vided, in that case, the symbol α represents the angle HOD° , and α' , which is accentuated for distinction, the retrograde distance BC . If $\therefore \alpha \alpha'$, being each $= 0$, the velocity at H will be

$$\left(\frac{d\alpha}{dt}\right)'' = \sqrt{\frac{2}{M} P c'} \dots\dots\dots (c)$$

and when $\alpha = \pi$, $\alpha' = 2\rho$, the recurring velocity at E will be

$$\left(\frac{d\alpha}{dt}\right)''' = \sqrt{\frac{2}{M} (P c' + 2 P \rho - R \rho \pi)} \dots\dots (d)$$

Thus it appears that the squares of the three velocities $\left(\frac{d\alpha}{dt}\right)', \left(\frac{d\alpha}{dt}\right)'', \left(\frac{d\alpha}{dt}\right)'''$ are in arithmetical progression, and that this progression would go on indefinitely if the resistance R did not augment so as to destroy the common difference $2 P \rho - R \rho \pi$, and cause the same velocity to recur at each period. It hence follows that, so long as the smallness of R renders $2 P \rho - R \rho \pi$, or $2 P - R \pi$, positive, the engine will be acquiring additional speed; and when R becomes such that $2 P - R \pi = 0$, the power will just be capable of maintaining unaltered the periodical movement, and the general speed will not admit of any further increase. For permanent speed we must therefore have

$$R = \frac{2}{\pi} P \dots\dots\dots (6)$$

This result shows that the general effect of the moving force P , acting obliquely on OD at D , is the same as if $\frac{2}{\pi} P$, or very nearly $\frac{7}{11} P$, were always applied perpendicularly at the same point.

It is not to be inferred from this that the effect of any portion of the power is lost. The quantity of power developed by a constant force is measured by the force multiplied into the distance through which it has acted. In a semi-revolution, the power developed by P is hence $P \times 2\rho$; that expended by R would similarly be $R \times \pi\rho$; and,

according to the equation (6), it appears that the expenditure would be the same in both cases, and that no loss is sustained through the obliquity of the action of the crank, except that which arises from the additional friction caused by the stress on the shaft.

Substitute the value of R from (6) in (5), and there results, for permanent speed, the angular velocity of the shaft of the engine at any period of the stroke, the following formula,

$$\frac{d\alpha}{dt} = \sqrt{\frac{2P}{M} \left(c + x - \frac{2\rho}{\pi} \alpha \right)} \dots\dots\dots (7)$$

and for any position D from E to H, if β denote the angle E O D, this becomes

$$\omega = \sqrt{\frac{2P}{M} \left\{ c + \rho(1 - \cos \beta) - \frac{2\rho}{\pi} \beta + (r - \sqrt{r^2 - \rho^2 \sin^2 \beta}) \right\}}. \quad (8)$$

For a point D° in the returning half stroke from H to E, if β denote the angle H O D°, the value of A C' is obtained by substituting $\pi - \beta$ for α in the value of x expressed by equation (1), and is therefore

$$AC = \rho(1 + \cos \beta) + (r - \sqrt{r^2 - \rho^2 \sin^2 \beta});$$

and if we deduct this from the whole distance AB = 2 ρ , we obtain the expression for BC or x' , viz.,

$$x' = \rho(1 - \cos \beta) - (r - \sqrt{r^2 - \rho^2 \sin^2 \beta}) \dots\dots (9)$$

Therefore by equation (7) the velocity at D° is

$$\omega^\circ = \sqrt{\frac{2P}{M} \left\{ c + \rho(1 - \cos \beta) - \frac{2\rho}{\pi} \beta - (r - \sqrt{r^2 - \rho^2 \sin^2 \beta}) \right\}}. \quad (10)$$

The velocities ω' ω'' at D' D'' will now be determined by substituting $\pi - \beta$ for β in equations (8) and (10); thus we find

$$\omega' = \sqrt{\frac{2P}{M} \left\{ c - \rho(1 - \cos \beta) + \frac{2\rho}{\pi} \beta - (r - \sqrt{r^2 - \rho^2 \sin^2 \beta}) \right\}}. \quad (11)$$

$$\omega'' = \sqrt{\frac{2P}{M} \left\{ c - \rho(1 - \cos \beta) + \frac{2\rho}{\pi} \beta + (r - \sqrt{r^2 - \rho^2 \sin^2 \beta}) \right\}}. \quad (12)$$

To put these in a more convenient form for comparison, let (ω) denote the velocity at E, as expressed by equation (a), and assume

$$\left. \begin{aligned} A &= \rho \left(\frac{2}{\pi} \beta - 1 + \cos \beta \right) \\ h &= r - \sqrt{r^2 - \rho^2 \sin^2 \beta} \end{aligned} \right\} \dots\dots\dots (13)$$

Then the angular velocities at any four corresponding points D^o , D, D' , D'' , will be

$$\left. \begin{aligned} \omega^o &= \sqrt{(\omega)^2 - \frac{2P}{M} (A + h)} \\ \omega &= \sqrt{(\omega)^2 - \frac{2P}{M} (A - h)} \\ \omega' &= \sqrt{(\omega)^2 + \frac{2P}{M} (A - h)} \\ \omega'' &= \sqrt{(\omega)^2 + \frac{2P}{M} (A + h)} \end{aligned} \right\} \dots\dots\dots (14)$$

which are here arranged respectively in the order of their magnitudes, that at D^o being the least, and that at D'' the greatest.

These formulæ may be put in a still more convenient form by neglecting the higher powers of the very small variations; we shall then have

$$\omega^o = (\omega) - \frac{P}{M(\omega)} (A + h),$$

$$\omega = (\omega) - \frac{P}{M(\omega)} (A - h),$$

$$\omega' = (\omega) + \frac{P}{M(\omega)} (A - h),$$

$$\omega'' = (\omega) + \frac{P}{M(\omega)} (A + h).$$

But for h we may now substitute $\frac{\rho^2}{2r} \sin^2 \beta$, and there will result

$$\left. \begin{aligned} \omega^o &= (\omega) - \frac{P}{M(\omega)} \left(A + \frac{\rho^2}{2r} \sin^2 \beta \right) \\ \omega &= (\omega) - \frac{P}{M(\omega)} \left(A - \frac{\rho^2}{2r} \sin^2 \beta \right) \\ \omega' &= (\omega) + \frac{P}{M(\omega)} \left(A - \frac{\rho^2}{2r} \sin^2 \beta \right) \\ \omega'' &= (\omega) + \frac{P}{M(\omega)} \left(A + \frac{\rho^2}{2r} \sin^2 \beta \right) \end{aligned} \right\} \dots\dots (15)$$

in which the values of A in parts of ρ are from (13) found to be as follows,

β	A	β	A	β	A
0°	0.0000	40°	+ .2080	70°	+ .1198
10 +	.0959	45 +	.2071	75 +	.0922
20 +	.1619	50 +	.1984	80 +	.0625
30 +	.1994	60 +	.1667	90 +	0.0000

From these last results we conclude that the velocity (ω) , which occurs at E and H, is the *mean velocity*, and that the greatest and least velocities occur in the quadrants of D' and D°, at the points where

$$A + \frac{\rho^2}{2r} \sin^2 \beta, \text{ or } \frac{2}{\pi} \beta + \cos \beta + \frac{\rho^2}{2r} \sin^2 \beta,$$

attains its maximum value. If we assume these points to be the middle of the respective quadrants, so that $\beta = 45^\circ$,—which will be very nearly the case with all the proportions observed in practice, and cannot sensibly affect the accuracy of the results,—the greatest and least velocities will be

$(\omega) \pm \frac{P\rho}{M(\omega)} \left(\frac{\rho}{2r} + 0.207 \right)$, and the deviation from the mean value will be

$$\frac{P\rho}{M(\omega)} \left(\frac{\rho}{2r} + 0.207 \right).$$

D 2

Again, by substituting the values of P' , R , the force $P' - R$, which at each position tends to accelerate motion, is found to be

$$P' - R = P \left\{ \sin \alpha \left(\frac{\rho \cos \alpha}{\sqrt{r^2 - \rho^2 \sin^2 \alpha}} + 1 \right) - \frac{2}{\pi} \right\}. \quad (16)$$

It hence appears that the motion is

accelerated $\left\{ \begin{array}{l} \text{when } \sin \alpha \left(\frac{\rho \cos \alpha}{\sqrt{r^2 - \rho^2 \sin^2 \alpha}} + 1 \right) \text{ is } \left\{ \begin{array}{l} \text{greater} \\ \text{lesser} \end{array} \right\} \text{ than } \frac{2}{\pi} \end{array} \right.$
retarded

In the preceding investigation we have only considered the action of a single crank; but it will be found to apply, with a slight modification, when the rotatory motion of the shaft is maintained by the action of any number of cranks making given angles with each other. We have only to substitute, in place of P' , in the right-hand member of the equation of motion, the sum of the forces P' , arising from the several cranks; and, by following out the same process, formula (5) will become

$$\frac{d\alpha}{dt} = \sqrt{\frac{2}{M} \left\{ P c + \Sigma (P x) - R \rho \alpha \right\}},$$

in which $\Sigma (P x)$ includes the same term for each crank. Let (ω) denote the value of this angular velocity, when $x = 0$, $\alpha = 0$, and the formula, for any other position, will become

$$\omega = \sqrt{(\omega)^2 + \frac{2}{M} \left\{ \Sigma (P x) - R \rho \alpha \right\}} \dots\dots (17)$$

By attending to the nature of the integration, it is evident that this formula applies generally to any assigned position throughout the entire period of each revolution of the shaft, if we give to the symbols x , α the following signification, *i. e.*, x = the entire distance travelled over by the extremity c , for each crank; and α = the angle described by the revolution of each shaft, each being estimated from that position in which the velocity was (ω) .

Let us take the practical case, in which the revolution of

the shaft is maintained by two or more cylinders, and in which the equal arms of the two or more cranks are placed at right angles to each other, so that each of them may be in full action when the other is "on its centre." If we suppose one entire revolution to be performed, and that there are two cylinders, the distance x , traversed by the extremity of each connecting rod, will be 4ρ , the angle α will be 2π , and the velocity will become $\omega =$

$$\sqrt{(\omega)^2 + \frac{2}{M} (4P\rho + 4P\rho - 2R\rho\pi)} =$$

$$\sqrt{(\omega)^2 + \frac{4\rho}{M} (4P - R\pi)}.$$

When the engine has attained its regular speed, this velocity must correspond with ω , since precisely the same motions must recur in successive revolutions; we must hence have $4P = R\pi = 0$, $\therefore R = \frac{4}{\pi}P$; which value is the same as $\frac{2}{\pi}(2P)$, in which $2P$ is now the moving power, and we find it corresponds with formula (6) for the single crank.

We have gone into an investigation of the motion of the crank, as it forms one of the most important appendages of the steam engine, and, previous to the publication of the second edition of Tredgold's work on the steam engine, had met with very little attention from scientific writers. It is doubtless the most simple, and perhaps the most efficient, contrivance that can be devised to convert a reciprocating action into a rotatory motion; and in this respect we cannot be surprised that it has not been superseded by any one of the numerous inventions which have been proposed with the view of dispensing with it.

THE ECCENTRIC.

The eccentric is a circular disc revolving within a strap or ring, and having its axis of revolution on one side of its centre. It is used for giving a reciprocating motion to the slide-valve or to the feed-pump of a steam engine.

In the annexed Fig. E is the centre and A the axis of the eccentric wheel, which is always fixed on the axis of the fly wheel of the stationary engine; a hoop BOD embraces this wheel so as just to allow it to turn freely within its circle, the hoop being generally of two pieces joined at B and C; a frame BFC connects the hoop with the extremity F of the bent lever FGH, which turns on the centre G. When E revolves on its eccentric axis A, the frame BFC will be drawn alternately to the right and left, and the end, F, of the bent lever FGH will describe at every revolution two arcs of a circle; the reciprocating motion of F, thus produced, transmits a like kind of motion to the other end of the lever, to which the slide-valve of the engine is attached.

"The eccentric arm or crank is by far the most simple mode of converting rotation into reciprocation, and it has the valuable property of beginning the motion in each direction gently, and again gradually retarding it so as to avoid jerks. Nevertheless, the law of variation in the velocities is not always the best adapted to the requirements of mechanism; but the reciprocation is produced so simply, that it is often worth while to retain the crank, and correct the law of velocity by combining other pieces with it in a train. By trains of link-work very complex laws of motion may be derived from a uniformly revolving driver."—*Professor Willis.*


To Construct an Eccentric Wheel.

From the centre of the shaft A take AE equal half the length of the stroke which the wheel is intended to work; and from E as a centre, with a radius somewhat greater than ED, describe a circle, which will represent the required wheel.

Example.—Suppose an eccentric wheel is required to give a stroke of 16 inches, the diameter of the shaft being 2 inches, and the thickness of metal for keying it on to the shaft 2 inches; then set off, from A to E, $16 \div 2 = 8$ inches,

$$8 + \frac{6}{2} + 2 = 13 \text{ inches, the radius of the eccentric}$$

is required.




Let S = space the end F is moved through by the eccentric wheel, and s = space through which the slide moves; then $FG \times s = GH \times S$. If in this equation any three of the parts be given the fourth may be found.

PARALLEL MOTION.

This simple and beautiful arrangement of link-work was invented by the celebrated Watt, to convert the reciprocating circular motion of the extremity of the great beam of the steam engine into a reciprocating rectilinear motion adapted to the piston rod.

Let the two equal rods CB , OD , which are connected by a third rod or link BD , move on their fixed centres CO ;



and let M be the middle of BD . Now, if CB be made to move alternately upwards and downwards, which will cause OD to move on its centre O in the same manner, it will be found that the point M will ascend and descend in a line which will not deviate sensibly from a vertical straight line. For when the point B is moved upwards, the upper extremity of the rod BC is drawn a little to the *right*, at the same time extremity D of the rod OD is drawn a little to the *left*. When the extremity B descends, the extremity D also descends; thus the two extremities are again drawn, the one a little to the *right*, and the other a little to the *left*. It will be readily understood that while the ends of the rod or link BD are thus alternately made to move right and left, its middle point M will not sensibly deviate to the right nor to the left, but will move upwards and downwards in a line not sensibly varying from a vertical direction. When $BC=DO$, the point M falls in the line CO .

The complete parallel motion, which is most universally adopted in large steam engines, is shown in the annexed Fig. When so employed the beam of the engine becomes

radius rod CD may be found by transposing the preceding formula, which gives

$$CD = \frac{AE (ED + Dd)}{Dd} \dots\dots\dots (2)$$

When the lengths of the several parts of the parallel motion, as ED , AE , CD , are given, the distance Dd may be readily found by formula (1); and when AE , ED , Dd are given, the length of the radius rod CD may be found by formula (2).

Note.—If the system of link-work in the parallel motion be moved into all the positions it is capable of taking, the actual paths of the points F and d would be found to be (since the extent of the stroke of the piston is small) in curves in the shape of the figure 8; but the small portions of the curves actually described differ insensibly from right lines. See Professor Willis's "Mechanism," Arts. 441 to 452, where various other important investigations on the same subject are given. Professor Hann, in his works on the steam engine, and in his edition of "Tredgold," has also given various important methods of constructing the parallel motion adapted to particular cases; but the methods here given are those most extensively used.

PADDLE WHEELS.

The floats of the paddle wheel may be considered as a series of levers coming into successive action upon the water. Each arm of the wheel to which a float is attached represents one lever; the reaction of the water on the paddle board or float constitutes the fulcrum; the resistance is that of the water to the motion of the vessel at the centre of the wheel; and the power is that produced by the engine. As the fulcrum is produced by the reaction of the water on the paddle board (as there can be no reaction if the surface of the paddle board does not move through the water), the true fulcrum must be at that point on which, if simply immersed, there would be no reaction. This point, moving in the direction of the surface of the paddle board, can meet with no resistance from the water; some power must therefore be exerted to force the paddle boards through the water, in addition to that which would be required to propel the vessel. Hence a *statical theory* may be deduced for the power requisite to move the floats of the paddle wheel.

ON THE DIFFERENT KINDS OF PADDLE WHEELS.

1. *Field's Paddle Wheel*, which is called the cycloidal wheel, differs from the common paddle wheel in the arrangement of the paddle boards, and was exhibited before the Lords of the Admiralty in 1833. However, Mr. Galloway took out a patent for this same invention in 1835; but the credit of it clearly belonged to the first-named gentleman.

Mr. Field thus describes his wheel in the *London Journal* for December, 1835:—

“Each board is divided into several parts, or narrower boards, and arranged in, or nearly in, such cycloidal curves that they all enter the water in immediate succession, thus avoiding the shock produced by the common board, so unpleasant to passengers, injurious to the vessel, and wasteful of the power. As the acting face of each board is radiating, it propels while passing under the centre in the ordinary way, and when it emerges the water escapes simultaneously from each narrow board, and, consequently, cannot lop-up.”

Mr. Barlow gives the following description of these wheels:—

“The principle of this contrivance consists in dividing the paddle into a number of parts, which are placed upon the wheel in the curve of a cycloid, so that they enter the water at the same spot and follow one another so rapidly as to cause little resistance to the engine on entering the water, and afterwards separate so as to afford full scope for their action in passing the centre, and in coming out allow the water to escape readily from them.”

There is some difference of opinion respecting the advantages and disadvantages of these wheels. Mr. Barlow says that “the use of the cycloidal wheel is very likely to become general, and supersede that of Morgan, from its superior strength and simplicity, while it does away with most of the evils to which the common wheel is subject.”

Mr. Mornay, on the contrary, seems rather to underrate it. His opinion is, “that it remains to be decided by experiment, whether the disadvantages of this wheel are overbalanced by the advantages it *seems* to possess.”

This wheel has been improved since the time of its first introduction, in the following rather remarkable manner.

At the time of the adoption of this wheel, it was with six or *seven bars in each set*, instead of the common paddle boards

This number has been much reduced (indeed the wheels now used in her Majesty's service have only two boards in a set), as every reduction was found to be more advantageous. However, these improvements cannot be carried on farther as in that case they would return to the common wheel again.

The *Great Western* and *British Queen* are among the vessels that have been fitted with these wheels.

2. *Paddle Wheels with Oblique Floats.*—One of the most simple of this kind is that of Mr. S. Hall, for which he obtained a patent in 1836. Here the paddle boards are placed obliquely to the rims and the axis of the wheel. The subject of the patent, however, is not the use of the oblique floats, but the making one half of them to enter the water in one diagonal direction, and the other in the reverse.

The objections are (1), that it requires a greater surface of paddle board to produce the same effect, for Mr. Mornay proves that the power in these wheels must exceed that in common wheels in the ratio of $\frac{1}{10}$; and (2), that the shock is very little reduced, and the loss of power from oblique action is greater than with the common wheel.

3. *Morgan's Paddle Wheel with Feathering Floats.*—The construction of this wheel is as follows. The paddles turn on spindles, having a bearing on the framework and on the wheel, which is polygonal, having as many sides as there are paddles. The inside frame or polygon alone is attached to the shaft of the engine, which does not continue beyond the side of the vessel; and the outer one has an independent bearing on a centre attached to the paddle box, so that it derives its motion entirely from the arms or angles of the polygon, the space between the two frames being left entirely free. A crank is fixed to the paddle box, on which the outer polygon revolves; it projects in an inclined direction in the open space between the sides of the wheel. Each paddle has a crank attached to it at an angle of about 70° , and arms connect the extremities of the cranks with a moveable boss, which revolves on a fixed centre; one of these arms is fixed to the boss, and is called the dividing arm.

This wheel is quite free from back-water, and from any shock, as both the upper and lower edges of the float are

nearly tangents to their respective cycloids at the time of entering the water. These wheels have always been praised for their beautiful action, their strength, and their durability, as well as for the safety, comfort, and economy with which they are attended. They have been adopted in many government and mercantile steamers, and always with success. It has been found by experiments, that in light immersions little advantage is gained by these wheels, since, reckoning the power of the engine 1, the effective power = '660 in the common wheel, and '666 in Morgan's. This arises from the loss from the additional velocity required to obtain the resistance or receding of the vessel, being fully equal to that of oblique action in the common wheel. In cases of deep immersion the result is different; the effective power of the common wheel will, in a very deep immersion, equal only '553, while that of Morgan's wheel remains the same.

In the *Firebrand* steamer, Morgan's wheel, with less power and less float, gave a greater speed than the common wheel. We may, therefore, conclude that this wheel has the superiority in sea, and the common wheel in river navigation.

There are other modifications of the paddle wheel with feathering floats, by Buchanan and Oldham; but they have been found to possess no advantages at all comparable to Morgan's, just described, and have, therefore, never been adopted in practice.

To find the Centre of Pressure in Morgan's Paddle Board, &c.

Put R and r = the radii of the wheel and rolling circle respectively, and d = the depth of the paddle board; then the depth of the centre of pressure from the upper edge of the paddle board, as deduced from Mr. Barlow's formula, is

$$\sqrt[3]{\frac{(R - r) + d)^4}{4d}} - (R - r).$$

Example.—The radius of the wheel of the *Messenger* steam vessel is $9\frac{3}{4}$ feet, the radius of the rolling circle is $6\frac{3}{4}$ feet, and the depth of the paddle board 2 feet; required the diameter of the centre of pressure.

By the formula,

$$\sqrt[3]{\frac{(9\frac{2}{3} - 6\frac{2}{3} + 2)^4}{4 \times 2}} - (9\frac{2}{3} - 6\frac{2}{3}) = \sqrt[3]{\frac{625}{8}} - 3 =$$

$$\frac{5}{2} \sqrt[3]{5} - 3 = \frac{5}{2} \times 1.70976 - 3 = 1.2744 \text{ feet} = \text{distance}$$

of the centre of pressure from the upper edge of the paddle. Now, as the radius of the wheel is $9\frac{2}{3}$ feet, and the depth of the paddle 2 feet, the distance from the centre of the wheel to the upper edge of the paddle is $9\frac{2}{3} - 2 = 7\frac{2}{3}$ feet; then $7\frac{2}{3} + 1.2744 = 8.941 =$ distance of the centre of the wheel to the centre of pressure, and $8.941 \times 2 = 17.882 =$ diameter of the centre of pressure.

The speed of the vessel was found to be $9\frac{1}{2}$ miles per hour; therefore $\frac{9\frac{1}{2} \times 5280}{60} = 858$ feet per minute $= 14.3$ per second.

Since the diameter of the centre of pressure, or effective diameter of the wheel, is now known, the velocity of the wheel in excess of that of the vessel, or that at which it recedes in the water to produce the resistance necessary for propelling the vessel, may be found by the following method:—

Multiply the velocity by the area of the paddle board, and by $62\frac{1}{2}$ lbs. (the weight of a cubic foot of water), and divide by twice the force of gravity at the earth's surface, which is $64\frac{1}{3}$; this quotient, multiplied by the velocity of the wheel, will give the power expended on the paddles; and this, being divided by the whole power of the engine, will give the proportion consumed on the vertical paddle.

The diameter of the centre of pressure being 17.882 feet, its circumference is $17.882 \times 3.1416 = 56.2$, and this, multiplied by 22, the number of strokes made by the engine per minute, gives $56.2 \times 22 = 1236.4 =$ velocity of the centre of pressure per minute, or $1236.4 \div 60 = 20.60 =$ velocity per second.

The velocity of the rolling circle, as above, is 14.3 feet per second; hence $20.60 - 14.3 = 6.30$ feet per second, which is the excess of the velocity of the wheel over that of the vessel;

and $(6.30)^2 \times \frac{62\frac{1}{2}}{64\frac{1}{3}} \times \text{area of the paddle board} = \text{pressure}$
in pounds on the vertical paddle; and, since the pad

board is 10 feet long and 2 broad, its area is $10 \times 2 = 20$ square feet; hence,


$$\frac{(6 \cdot 30)^2 \times 62\frac{1}{2} \times 20}{64\frac{1}{2}} = 771 \text{ lbs., nearly,}$$

The velocity of the centre of pressure, found above, is 1238·6 feet per minute;

$$\therefore \frac{2 \times 1238 \cdot 6 \times 771}{33 \cdot 000} = 57 \cdot 77 \text{ horse-powers, nearly.}$$

MARINE SCREW PROPELLERS.

Screw propellers for navigation, by means of steam power, have now become objects of great importance to all nations;




they are especially applicable to vessels of war, the machinery for propulsion being placed so deep in the hold of the ship

as to secure it completely from the reach of gunshot. Screw propellers, however variously they may be modified, all derive their power of propelling by being placed on an axis which is parallel to the keel, and by having threads or blades extending from the axis, which form segments of a helix, or spiral; so that by causing the axis to revolve, the threads or blades worm their way through the water, much in the same way as a carpenter's screw inserts itself into a piece of wood, with the difference in the case of the screw-propeller of its making the water recede. Screw propelling is not of recent invention: M. Duquet in 1727, and Mr. Pancton in 1768, both produced machinery of this kind; other inventions followed until a recent date.

When the *Archimedes* was first tried down the river Thames in 1836, the shape of the screw was as represented in the figure, *i. e.*, a single thread of thin sheet iron, bent to fit sixteen wrought-iron arms fixed round the axis at equal distances, so as to form a helix, or screw. This screw, from its having only one thread of long pitch, *viz.*, 45° , caused a great commotion in the water, and a great deal of vibration in the stern of the vessel, so that on reaching Sheerness the vessel was laid ashore, and portions of the iron plate taken off at equal intervals; but the effect was not improved. The form of the screw was then changed to a double one; and, finally, a series of experiments was made by order of the Admiralty, with three or four-bladed screws, which ended in the adoption of the *two-bladed* screw. These experiments were tried in H. M. ships *Dwarf* and *Rattler*, till a speed had been produced in the *Dwarf* of $12\frac{1}{4}$ knots per hour with Mr. Rennie's conoidal screw of cast-iron, being the greatest speed which had ever been attained by the screw up to that time. The speed attained by the *Archimedes* was about nine knots per hour, which, taken as a first experiment, was a great performance. The *Archimedes* beat most of the fastest steamers then known, and made a voyage all round Great Britain, being a distance of 2096 nautical miles, in $237\frac{1}{2}$ hours, or nearly nine knots per hour through the whole distance. The *Archimedes* afterwards sailed from Plymouth to Oporto in 69 hours, and returned from thence, against strong head-winds and high seas, in 88 hours; and the reports of some of the most eminent officers predicted all that *has since been realised* by the screw.

Griffith's Screw Propeller.—This is probably one of the best modifications of the marine screw which has yet been produced. Its chief peculiarity consists in a large hollow sphere B being substituted for the central portion of the blades of the ordinary screw, the blades A, A, A terminating



upon the sphere instead of upon the usual boss. It has been found by experiment that the central portion of the blades of the common screw absorbs nearly 20 per cent. of the propelling power, without giving out any useful effect, in consequence of that portion of the blades being nearly in a line with the shaft, so that the water is

thrown off at right angles, thus disturbing the more solid water upon which the outer and more effective portion of the screw is about to act. The use of the sphere is, therefore, to fill up the space otherwise occupied by the central portion of the screw blades, a smooth globe of this kind revolving in the water with comparatively little friction or resistance.

It is found also that the vibrations caused by the revolutions of the common screw are considerably lessened by this contrivance. Another feature in Griffith's propeller consists in the peculiar form of the blades, which, unlike the common screw, are larger towards the sphere and smaller towards the extremities: the diameter of the sphere being one-third of the whole diameter of the screw, the breadth of each blade at the root is equal to the full diameter of the sphere, tapering to two-thirds of this breadth at the extremities of the blades. The object in reducing the blades at their ends is to compensate for the varying velocity with which the different parts of their length travel through the water.

There is still another feature in this propeller, *i. e.*, the power of altering the pitch or angle of the blades by a suitable arrangement of apparatus contained within the hollow sphere; or, if it be wished to stop the engines, and sail *under canvas*, the blades may be feathered (as in Maudslay's

feathering screw), so as to present their edges to the water, and thus cause the least amount of resistance to the ship.




“Maudslay's Feathering Screw.”—This screw is represented on the following page. The object sought to be obtained is, that the blades, whenever the vessel is put under canvas, and the screw not required, should be placed in a direction parallel with the line of the keel, and so form, as it were, a portion of the dead wood, as they cause considerable obstruction if they be allowed to remain fixed in their position, or even though they be disconnected from the engine and allowed to revolve. In auxiliary sailing vessels, not fitted with a trunk or aperture for the purpose of raising the screw out of the water, this is particularly valuable; but it will also be found useful in ships of war, by lessening the width of the trunk through which it has to rise, if this be desired, and also by the facility which it gives in emergencies, for placing the vessel under canvas or under steam, as well as for placing the vessel under canvas when it may not be possible to keep the engines at work for want of fuel or other causes. The blades are locked in the vertical position by means of a catch and a screw, passing through the stern of the vessel, as shown in the figure.”

“The Diameter of the Screw should, in most cases, be made as great as the draught of water will admit, and for sailing in smooth water its upper edge need not be more than a few inches below the surface. In the case of sea-going vessels, it is preferable to keep it $1\frac{1}{2}$ or 2 feet below the mean surface of the water.”

“The Area of the Screw.”—By the area of the disc of the screw is understood the area of the circle described by the extremity of its diameter. When the area of the blades is spoken of, their actual oblique surface should always be especially distinguished from the plane projection of the resisting surface. This latter measurement, as representing the actual amount of surface directly employed in the propulsion of the vessel, is probably the most important of these areas.”—*Murray on the Marine Engine, Weale's Series.*

1st. In position for use as a propeller.

2nd. In position for sailing under canvas alone.



THE THEORY OF THE SCREW.

Various authors have given their theoretical deductions for determining the power of the screw. The following is from Hann and Gener's "Treatise on the Steam Engine."

The surface of the screw is generated by a line normal to the axis, round which it revolves uniformly, to the extent of one revolution.

Let v = velocity of the vessel in feet per second,
 ω = angular velocity of the screw,
 h = length or pitch of the screw,
 r = radius of any point P,
 α = angle of inclination of the surface of the screw at that point, with a plane section perpendicular to the axis; and let

$$k = \frac{h}{2\pi} \dots\dots\dots (1)$$

$$u = k\omega = \frac{h}{2\pi} \omega \dots\dots\dots (2)$$

Then, $\tan \alpha = \frac{h}{2r\pi} = \frac{k}{r} \dots\dots\dots (3)$

Effective angular velocity

$$= \frac{r\omega \tan \alpha - v}{\tan \alpha} = \frac{r}{k} (k\omega - v) = \frac{r}{k} (u - v).$$

Velocity perpendicular to the screw

$$\begin{aligned} &= \left(r\omega - v \frac{\cos \alpha}{\sin \alpha} \right) \sin \alpha \\ &= (r\omega \tan \alpha - v) \cos \alpha = (u - v) \cos \alpha. \end{aligned}$$

Elementary surface at P = $\frac{2\pi r}{\cos \alpha} \cdot dr$;

\therefore the elementary pressure

$$\begin{aligned} dp &= \frac{W}{2g} \cdot \frac{2\pi r}{\cos \alpha} \cdot dr (u - v)^2 \cos^2 \alpha \\ &= \frac{W}{g} \cdot \pi r dr \cos \alpha (u - v)^2. \end{aligned}$$

Let $C = \frac{W}{g} \cdot 2\pi(u-v)^2 \dots\dots (4)$

and $dp = Cr dr \cos \alpha = \frac{Cr^2 dr}{\sqrt{k^2 + r^2}}$, from formula (3);

$\therefore d(\text{effective power}) = v(dp \cos \alpha) = Cv \frac{r^2 dr}{k^2 + r^2}$.

But
$$\int \frac{r^3 dr}{k^2 + r^2} = \int \left(r dr - \frac{k^2 r dr}{k^2 + r^2} \right)$$
$$= \frac{1}{2} \left(r^2 - k^2 \log \frac{k^2 + r^2}{k^2} \right).$$

Let, therefore, $A = r^2 - k^2 \log \frac{k^2 + r^2}{k^2} \dots\dots (5)$

$$\left. \begin{array}{l} \text{the effective power} = \frac{1}{2} AC \times v \\ \text{the full power} = \frac{1}{2} AC \times u \end{array} \right\} \dots\dots\dots (6)$$

Multiply by $\frac{60}{33000} = \frac{1}{550}$, and

the effective horse-powers $= \frac{1}{1100} AC \times v$, and

the full horse-powers $= \frac{1}{1100} AC \times u$.

Make $c = \frac{W}{2g} \times \frac{\pi}{550} \dots\dots\dots (7)$

$$\left. \begin{array}{l} \text{then the effective horse-powers} = Ac(u-v)^2 v, \\ \text{and the full horse-powers} = Ac(u-v)^2 u \end{array} \right\} \dots\dots (8)$$

Again, by (6) the effective propelling pressure

$$= \frac{1}{2} AC = \frac{W}{2g} \pi A (u-v)^2.$$

But, if S = the effective surface of resistance of the vessel, the effective resistance $= \frac{W}{2g} \cdot S v^2$;

$$\therefore S v^2 = \pi A (u - v)^2,$$

$$\text{or } \left(\frac{u}{v} - 1\right)^2 = \frac{S}{\pi A},$$

$$\text{whence } u = v \left(1 + \sqrt{\frac{S}{\pi A}}\right), \dots\dots\dots (9)$$

$$\text{the revolutions per second being } = \frac{u}{h}$$

Should the propelling surface of the screw be generated between two limiting valves r, r_1' , it will be requisite to estimate the function A , formula (5), between those limits, *i. e.*,

$$A = \left(r^2 - k^2 \log \frac{k^2 + r^2}{k^2}\right) \sim \left(r_1'^2 - k^2 \log \frac{k^2 + r_1'^2}{k^2}\right). \quad (10)$$

The proportion of the power of the engine usefully effective in the propulsion of the vessel

$$= \frac{\text{effective power}}{\text{full power}} = \frac{v}{u} = \frac{1}{1 + \sqrt{\frac{S}{\pi A}}},$$

$$\text{when } S = \frac{2.5 (\text{tonnage})^{\frac{2}{3}}}{15} = \frac{1}{3} (\text{tonnage})^{\frac{2}{3}},$$

$$\text{or } S = \frac{8 (\text{tonnage})^{\frac{2}{3}}}{15} = \frac{8}{15} (\text{tonnage})^{\frac{2}{3}},$$

according to the form of the vessel.

That is, "till further experiments, and, consequently, better information is produced," says Mr. Woolhouse, "the effective resisting surface of the vessel may be estimated at about

$$\frac{1}{3} \text{ or } \frac{8}{15} (\text{tonnage})^{\frac{2}{3}}.$$

The larger the diameter and the less the pitch of the screw, the greater will be the proportion of the effective power on the vessel."

ON BOILERS.

A boiler for 20 horse-powers is usually 15 feet long and 6 feet wide; therefore 90 feet of surface, or $4\frac{1}{2}$ feet to 1 horse-power; a boiler of 14 horse-powers 60 feet of surface, or 4.3 feet to 1 horse-power; but engineers generally allow 5 feet of surface to 1 horse-power; and Mr. Hicks, of Bolton, proportions his boilers at the rate of $5\frac{1}{2}$ square feet of horizontal surface of water to each horse-power. Mr. Watt allows 25 cubic feet of space to each horse-power.

Length of Boilers for Locomotive Engines.

On the Northern and Eastern Counties Railway, the length of the boiler is 8 feet; while on the North Midland Counties Railway, on the Great Western Railway, and on several others, the length of the boiler is $8\frac{1}{4}$ feet. In Stephenson's locomotive engines, the length of the boiler is between 11 and 12 feet. On the Bordeaux and La Teste Railway the length of the boiler is 8 feet 9 inches; and in America the length varies from 10 to 14 feet.

The *Inside Diameter of a Locomotive Boiler* is usually found by multiplying the diameter of the cylinder in inches by $3\frac{1}{3}$, and the product is the inside diameter of the boiler. Thus, for example, let the diameter of the cylinder be 15 inches; then

$$15 \times 3\frac{1}{3} = \frac{15 \times 28}{9} = \frac{140}{3} = 46\frac{2}{3} \text{ inches,}$$

the inside diameter of the boiler.

The *Inside Diameter of the Steam Dome* may obviously be varied considerably. It is usual, however, in practice to proportion its diameter to the diameter of the cylinder, by multiplying this diameter by 1.43 for the diameter of the steam dome in inches. Thus, for example, let the diameters of the cylinders be 15 inches; then

$$15 \times 1.43 = 21.45 \text{ inches} = \text{diameter of the dome.}$$

The *Height of the Steam Dome* may be considerably varied; but judging from practice, it appears that a uniform height of $2\frac{1}{2}$ feet would answer in all cases.

The *Area of the Fire-grate*, in practice, follows a more

certain rule than any other part of the engine seems to do; but it appears to be in all cases much too small, and causes a great loss of power by urging the blast it renders necessary, and a rapid deterioration of the furnace plates from excessive heat. There is no sufficient reason why the furnace should not be nearly as long as the boiler; it would then resemble the furnace of a marine engine boiler, and be quite as manageable. However, the practical rule to find the area of the fire-grate is to multiply the diameter of the cylinder in inches by $\cdot 77$, and the product is the area of the fire-grate in feet. Thus, for example, let the diameter of the cylinders be 16 inches; then

$$16 \times \cdot 77 = 12\cdot 32 \text{ square feet} = \text{area of the fire-grate.}$$

STEAM PIPES.

It is usual in practice to have the internal diameter of the steam pipe about one-fifth of the diameter of the cylinder of the engine. The area of the passages through the valves in some of Watt's engines are nearly one square inch to each horse-power. This is in some cases too large for steam passages, but rather too small for the exhausting-valve passages. Indeed, the larger the exhausting-valve passages are; the better.

The only proper method of proportioning the steam passages is by taking into consideration the velocity of the steam through them. Mr. Tredgold says, the force of steam in the boiler, multiplied by the velocity and the area of the passage, must be equal to the elastic force on the piston multiplied by its area and velocity. That is,

$$a \cdot f \cdot v = A V p.$$

Where a is the area of the steam passages, f the force of the steam in the boiler in inches of mercury, v the velocity, p the force of the piston in the same denomination as f , A the area of the piston, and V its velocity,

$$\therefore v = \frac{A V p}{a \cdot f},$$

$$\text{or} \quad a = \frac{A V p}{f v}.$$

THE AIR-PUMP, CONDENSER, &c.


The proportion of the diameter of the air-pump, as given by Mr. Watt, is usually about two-thirds of the diameter of the cylinder, when the length of the stroke of the air-bucket is half the length of the stroke of the steam piston.

The area of the passages between the condenser and the air-pump should never be less than one-fourth of the area of the air-pump; the apertures through the air-bucket should have the same proportion, and, if convenient, the discharging flap or valve should be made larger.

The capacity of the condenser should at least be equal to that of the air-pump; and, where convenience will admit it, the larger it is made the better.

THE SLIDE-VALVE OF THE STEAM ENGINE.

When the breadth of the slide face of the valve is just equal to that of the steam port, the travel of the slide is evidently equal to twice the breadth of the steam port; but when the slide has lap, then the length of the stroke or travel of the slide is equal to double the length of the lap, together with double the breadth of the steam port. In the annexed figure, which represents the slide at half stroke, A B or E F



is the lap, and B C or D E the breadth of the steam port. When the slide begins to move from one extremity of its stroke, the point F arrives at D; and when it has passed over half its travel, which is its position as shown in the figure, it is evident that the point F has moved over the space F D, which is equal to the breadth of the steam port added to the lap; the slide next, moving through the other half of its travel, will bring the point A to C, a space which is also equal to the breadth of the steam port added to the lap; therefore the whole travel of the slide is equal to twice


the sum of the breadth of the steam port and the length of the lap. In this figure the slide has no lead.

The following method of showing the positions of the piston, corresponding to the various openings of the steam and exhausting ports, has been presented to me for insertion in this work by the eminent engineer, Mr. Amos, of the well-known firm of Easton and Amos. It is given in as clear and simple a manner as the subject seems to admit of, since any intelligent working man may draw the figure to any convenient scale with rule and compasses, while, for locomotive engines, the figure might be drawn of the full size.

GEOMETRICAL CONSTRUCTION.

From a scale of equal parts take the length of the stroke of the piston, divided into feet and inches, and with radius equal to half the stroke describe the circle AOD , which will represent the crank orbit. Also form a scale of equal parts, the scale being as large as practicable; with the radius OP —equal to the lap of the slide—describe the circle oPQ ; and with the radius Op —equal to the lap and breadth of one steam port—describe the circle pqa —the distance pq represents the travel of the slide; on this latter circle set off lm equal to the lead of the slide, and from m draw the line mn , touching the circle oPQ at P ; and parallel to this line draw AA' , and A will represent the position of the crank-pin, when the slide is at half stroke. When the crank-pin arrives at B , the slide will begin to open; and when it arrives at O , the piston will be at the upper end of its stroke, and the steam port will be open a distance equal to lm , and taking the steam on the upper side of the piston to commence the down stroke. To ascertain the position of the crank and piston when the steam port is fully open, from m and n as centres, describe the arcs de and fg , and their point of intersection r , in the circle AOD , will be the position of the crank-pin; and the line rs , parallel to OH , will be the position of the piston at the same time. When the crank-pin arrives at the point t , the slide will have returned to the line mn , and the steam will be cut off; and the line Tt , drawn parallel to OH , will be the position of the piston, showing the portion of the half stroke performed. When the crank-pin arrives at b , the steam port begins to open for the admission of steam

radius, describe the circle $P o Q$; and parallel to the line $A A'$ draw the lines $x y$, $x' y'$, respectively cutting $p q$ in P and p' ; then the distance $P p'$ will represent the breadth of the steam ports a to the cylinder (see the following figure of the slide), and $p P$ will be equal to the breadth of the exhaust port b . When the crank is at A , the slide is at the middle of its stroke; when it arrives at B , the steam begins to exhaust from the under side of the piston; and when the crank arrives at C , the piston being at the same time at the upper end of its stroke, the slide will be opened the distance $l m$; and when the crank arrives at c , the same port will be open the distance $y' m'$, equal the width $P p'$ of the steam ports; when the crank arrives at r , the slide will be at the end of its travel, as shown in the preceding figure of the slide, $p P$ being equal to the exhaust port b , and s will be the position of the piston in its down stroke. It will be seen that during the time the piston is travelling from c to c' , the bottom port $p' P$ has been fully open, to allow the steam to escape from the under side of the piston. When the crank arrives at w , the lower port is shut, and the slide is in the position shown in the following figure.



Formula and Examples for the Lap and Lead of the Slide.

Let l = lap, l' = lead, S = stroke of the piston, s = stroke of the slide, and d = distance before the steam is cut off; then

$$d = S \left\{ 1 - \left(\frac{2l + l'}{s} \right)^2 \right\} \dots\dots\dots (1)$$

$$l = \frac{1}{2} \left\{ s \sqrt{\frac{S - d}{S}} - l' \right\} \dots\dots\dots (2)$$

Example 1.—Given the lap = 1·85, the lead = 2, the stroke of the piston = 40, and that of the slide = 6, all in inches; required the distance moved by the piston before the steam is cut off.

By formula (1),

$$40 \left\{ 1 - \left(\frac{2 \times 1.85 + .2}{6} \right)^2 \right\} = 40 (1 - .4225) = 23.1 \text{ inches,}$$

which is the distance the piston has moved before the steam was cut off.

Example 2.—The length of the stroke of the piston of an engine is 40, the steam is cut off at 23·1, the stroke of the slide is 6, and the lead $\frac{1}{2}$, all in inches; required the lap of the slide.

By formula (2),

$$\frac{1}{2} \left\{ 6 \sqrt{\frac{40 - 23.1}{40}} - .2 \right\} = \frac{1}{2} (3.9 - .2) = 1.85 \text{ inches,}$$

the lap required.

THE LOCOMOTIVE ENGINE.

Descriptions having now been given of the general and peculiar principles of both the stationary and marine engines, it will next be proper to give a description of the peculiar properties of the locomotive engine, several of its most important general principles having necessarily already been given. This class of engines is adapted to either railways or common roads, but has been more successful on the former. The principle of action being the same in both kinds, a description of the railway variety will be sufficient, which will be given under the following eight heads:—

1st. The boiler, in which the steam as usual is generated, contains internally a fire-box, connected with several small tubes, varying in number from 50 to 300, a regulator, and a steam pipe. Externally, a chimney and two safety-valves are fixed to the boiler.

2nd. The parts which regulate the action of the steam are two slide-valves (covering the passages to and from the cylinders) attached to two sets of valve gear, worked by two eccentrics for the "forward," and two other eccentrics for

the "backward" motion of the engine; but only two of them work at one time, the other two being what is called "out of gear." Four rods, called eccentric rods, encircling the eccentric sheaves at one end, and jointed to the slide-valve gear at the other end, complete the connection of the slide-valves to the eccentrics fixed on the axle of the driving wheels.

3rd. The parts by which the engine-man controls the action of the locomotive are three sets of levers and rods, connected to the slide-valve, eccentric rods, regulator valves, and feed-pipe cocks; by which he can "put on" or "shut off" the steam to the cylinders, water to the boiler, put the slide-valves in a "backward" or "forward" position, at pleasure. These appendages are commonly called the *hand gear*.

4th. The parts essentially concerned in producing locomotion are two cylinders, in which work two steam-tight pistons with their piston rods. On the exterior ends of the piston rods are fixed T pieces, also called crossheads, which slide between or round guide bars, also called motion bars, fixed to the ends of, and parallel to, the cylinders. By this means the piston can only move in a right line in the same direction as the lengths of the cylinders. Two strong rods, called connecting rods, attach the crossheads to the arms of the driving wheels, or to a cranked axle, where there is one used. Whether the pistons are connected with a cranked axle or the arms of the driving wheels, these connections are always made at an angle of 45° to each other; therefore one piston is exerting its greatest force when the other is at the end of the cylinder, and exerting no force. The connection between the pistons and the driving wheels being thus fully completed, it is at once evident that any movement of the pistons must immediately act upon the driving wheels.

5th. The parts which supply water to the boiler are two forcing pumps, connected by two feeding pumps to the boiler, and to a reservoir of water in the tender to the locomotive. The pumps are worked either from the eccentrics on the axle of the driving wheels, or from the crosshead.

6th. The parts which excite the rapid combustion of fuel required in the locomotive engine are the chimney and the *blast-pipe*, so contrived as to cover the exhausting passages

from both cylinders, and terminating in the centre of the chimney, about the level of the top of the boiler. It is the escape through this pipe of each succeeding cylinder-full of steam, or that portion of it allowed to escape by the slide-valves, which causes the "beats" or "pulsations" so distinctly heard when the locomotive commences its motion. The more general properties and utility of the steam-blast will be detailed further on.

7th. The parts which support the locomotive engine are two, four, or six wheels, besides the two driving wheels, a suitable set of springs, and a strong frame, in which the machinery already described is securely fixed, and on which the boiler and cylinders are also securely bound.

8th. From the co-operation of the several parts already described locomotion is produced in the following manner. The boiler is charged with water until it completely surrounds all the tubes and the internal fire-box, and fire being applied, in due time steam is produced from the water, and collected between the surface of the water and the top of the boiler until it has reached the pressure required. The regulator is then opened, and the slide-valves placed in their working position by the engine-man; the steam rushes from the boiler through the steam-pipe to the cylinders, where its force moves the pistons, which, being attached to the driving wheels (as has been already explained), cause them to revolve, thus producing locomotion. The slide-valves and pumps, being wrought by some of the parts set in motion by the pistons, regulate the admission of steam to the cylinder, and of water to the boiler. When the steam has moved the piston to the end of the cylinder, a passage is opened for its escape to the atmosphere through the blast-pipe, and the intermitting velocity of this escaping steam creates a partial vacuum in the chimney, causing a rush or "blast" of air to fill this vacuum, which blast excites the rapid combustion of the fuel, and consequent rapid production of steam. This completes the duties of one admission of steam to the cylinder until its escape to the atmosphere, and when this escape has taken place, another admission of steam to the opposite side of the piston forces it back to the other end of the cylinder; and by means of the crank, the reciprocating motion of the piston is converted into a rotatory on. Thus the locomotion, begun by the first ad-

mission of steam to the cylinders, is continued by the second and succeeding admissions.

The repetition of these simple operations has amazed and gratified the world by safely conveying heavy passenger trains at upwards of sixty miles per hour, and merchandise trains of six hundred tons weight at twenty-five miles per hour! the mere idea of which, not many years since, would have been regarded as purely fabulous.

Such is the modern locomotive engine—an illustrative example of the genius of man; but, like other important inventions, it is the joint production of many minds, and many more are still directed to its further improvement. The records of the Patent Office show that, from January, 1840, to the end of September, 1849, no less than two hundred and twenty-six patents were enrolled, all of them more or less applicable to the steam engine and its appendages. Of these two hundred and twenty-six patents, forty-five were enrolled during the first nine months of 1849. It has been remarked that steam engines and railways were too matter-of-fact subjects for poets and painters, but from the above record it is evident that they deeply impress themselves upon the inventive intellect of the world; and if the prodigies performed by steam remain unsung, or unpourtrayed, they dare, if not realise, the very sublimity of both poetry and painting; for what scene more interesting to delineate than one of these stately machines moving safely along, at eagle-speed, the very *élite* of the land, including even royalty itself, through districts rich in historical associations of past ages, and at the same time teeming with the great works of Nature and Art! Surely, it cannot be that the subject is too lofty a one for poetical or pictorial illustration, for in greatness of idea lies the success of both.

A brief review of the progress of locomotives is all that can be here given. It is now (1862) about two thousand years since the powers of steam were shown and recorded by Hero of Alexandria; but it is little more than two hundred years (in 1650) since it was first usefully employed by the Marquis of Worcester. The first idea of using it for propelling carriages is generally ascribed to Dr. Robinson, in 1759, when it was suggested to him by Watt, who included a steam carriage in his patents of 1769 and 1784; but we *had no railways then*, and his patents were never carried

out, otherwise his scientific and comprehensive mind would speedily have accomplished what several of his less-talented successors were a long series of years in attaining. From 1802 to 1805, Trevithick applied steam carriages to both common roads and railways, with considerable success for first experiments ; and his engines, with Booth's and Stephenson's modern improvements, now constitute the modern locomotive. About the year 1803, it appears that a Mr. Fredericks also made a steam locomotive for a silver mine in Hanover, which in 1811 was employed to convey their Majesties of Westphalia and suite over the mineral railway at a considerable speed. This was probably the first royal trip on a railway. From 1805 to 1814 invention was directed to ensure the adhesion of the wheels upon the rails, and many ingenious plans were tried, some of which succeeded well at slow speeds, but were not at all calculated for high velocities. In 1814, however, Mr. Blackett, of the Wylam Railway, reverting to Trevithick's plan, fully established the fact, that on a level, or moderately inclined railway, the adhesion of a smooth iron wheel upon a smooth iron rail was sufficient to draw heavy loads ; in his experiments he tried both six and eight-wheeled engines. In 1814 Mr. Stephenson introduced two cylinders, or two complete steam engines in one locomotive. From this time, up to 1829, the powerful opposition of the owners of other modes of conveyance greatly retarded the progress of locomotive engines ; and so strong was the feeling that they were not economical, that both Mr. Walker and Mr. Rostrick reported against them in 1829. These reports, and one of a doubtful character by Telford, led to the offer of a prize of £500, in 1829, by the directors of the Liverpool and Manchester Railway, for the best locomotive engine, the weight of which was not to exceed six tons. This proceeding gave an important impulse to locomotives, and ended in establishing the superiority of railways over all other existing systems of travelling. Three competitors appeared, namely, Messrs. Stephenson, Erickson, and Hackworth ; their locomotives were respectively named the *Rocket*, the *Novelty*, and the *Sanspareil*. They were all tried, and the prize was won by the *Rocket*, which, after the trials were over, reached a speed of thirty-five miles per hour. The other two engines reached the required speed per hour, as shown by their trials, but broke down before the required distance was completed.

The *Rocket* embraced the tubes and blast-pipe of the modern locomotive; the former (twenty-five in number) were suggested by Mr. Booth, of Liverpool, and the latter was first introduced by Mr. Hackworth, in his locomotives constructed previous to the *Sanspareil*.

The *Novelty* embraced a principle of generating a high heat by means of bellows, not since that time adopted in practice. She broke down after the trial commenced.

The *Sanspareil* embraced the blast-pipe (first introduced by her owner, Mr. Hackworth, as already stated), with the single return tube of the old locomotives. She was fully expected to accomplish the required distance greatly within the given time; but she unfortunately broke down, as already noticed, before the distance was fully completed.

It will hence be seen that Mr. G. Stephenson's *Rocket* won, chiefly through the adoption of the important suggestions of others, rather than through his own inventive genius. He can, therefore, *only* be considered a *fortunate* man, and Mr. Hackworth, a particularly *unfortunate* man, as his opponent, Mr. Stephenson, beat him by the help of the blast-pipe, which was Mr. Hackworth's own invention.

From 1830, up to the introduction of the seven-foot gauge on the Great Western Railway in 1838, no marked improvement took place in the locomotive. The rivalry, however, which sprung up between the gauges tended greatly to develop their capabilities.

A great number of patents have been enrolled for improving the locomotive engine, but only a few of these have been adopted in practice; among the most conspicuous of them is Mr. Crampton's arrangement of wheels, Mr. M'Connell's tank engine, Mr. Samuel's express engine, and Mr. Adam's steam carriage. The improvements in the mechanism of the slide-valve motion by Mr. Gray have been widely adopted. This great improvement is usually called Stephenson and Gray's, because the patent was so enrolled. Mr. Crampton has engines of his plan at work, both in England and on the Continent, which enable high driving wheels to be used on the narrow gauge without raising the centre of gravity. For illustrations of these, and other examples, see the new edition of "Tredgold on the Steam Engine."

The tank engine carries on the same frame water and fuel, *its tank for water being placed on the top of the boiler.*

This is the plan adopted on the Great Western Railway; but on the narrow gauge lines the tank is usually placed below the boiler and framing, which is a better arrangement where the machinery permits it to be done.

Mr. Samuel's express engine weighs only 25 cwt., and Mr. Adams' steam carriage is on this plan, with a very handsome carriage for passengers, all on one frame, and has been tried on some of the branch railways of both gauges.

Having thus briefly glanced at the progress of the locomotive engine, it only remains as briefly to notice some important discussions which have agitated the mechanical world concerning them.

From the earliest introduction of locomotives, four, six, or eight wheels appear to have been used, according to the designs of the makers; but about 1840-42 an animated discussion of the respective merits of the four and six-wheeled engines was carried on in the railway press. Both classes have their merits, and both had able advocates; but public opinion evidently tended in favour of the six-wheeled engine as the safer of the two under all contingencies; hence the greater portion of the present locomotives have six wheels.

The gauge controversy of 1845-48 led to the re-introduction of eight-wheeled engines on both gauges, weighing about 36 tons each, which realised speeds of about sixty and seventy miles per hour. The weight of these monster engines, it will be observed, was more than eight times the weight of the *Rocket* ($4\frac{1}{4}$ tons), which won the prize in 1829; whilst the speed is only twice that of the *Rocket* (thirty-five miles per hour) at that time. It is worthy to remark that the existing engines in 1829 were from 10 to $16\frac{1}{2}$ tons, and were considered as far too heavy; hence the directors of the Liverpool and Manchester Railway bound competitors not to exceed 6 tons weight. In 1849 the same feeling prevailed, and the injury done to the railways by these 36-ton engines was much complained of, and tank engines and steam carriages, till their weight was reduced, were equally objectionable; so that, generally, the weight of all locomotives is now reduced to what may be considered as proper and practicable in this important respect.

ON MOVING A TRAIN ON A LEVEL RAILWAY.

When the train of a locomotive engine commences its motion on a railway, the power of the engine exceeds the resistance, and therefore the speed increases until the resistance becomes equal to the power of the engine; the speed of the train will then be uniform, which is commonly called a steady speed, or the greatest or maximum speed; the work or motion destroyed by the resistance being now exactly equal to the power exerted by the engine. See formula (v), p. 32; see also "Statics and Dynamics," Weale's Series.

It has been found by experiment that the friction on a horizontal or inclined railway is invariably $= \frac{w}{n}$, or the n th part of the weight w of the train, $\frac{1}{n}$ being the co-efficient of friction; therefore the whole resistance to motion on the railway is also $= \frac{w}{n}$. Let P = power required to move the train, s = space in feet moved over in the time t in minutes, and H = number of horse-powers in P ; then, since 33000 are the estimated number of units of work which one horse can perform in a minute, $P = 33000 H$ = units of work or pounds moved one foot in one minute, and $\frac{s}{t}$ = feet moved in one minute by the weight $\frac{w}{n}$; whence $\frac{w}{n} \times \frac{s}{t}$ = units of work required in moving the carriages or train on a level railway.

$$\therefore P = 33000 H = \frac{w}{n} \times \frac{s}{t},$$

$$\text{whence} \quad H = \frac{w s}{33000 n t} \dots\dots\dots (A)$$

In railway calculations w is usually given in tons, and s in miles, which are to be reduced to pounds and feet by multiplying them respectively by 2240 and 5280; also n is most commonly = 280; if, therefore, we substitute 2240 W for w , 5280 S for s , and 280 for n , in formula (A), there will *result after reduction*,

$$H = \frac{128 W . S}{100 t} \dots\dots\dots (1)$$

whence $W = \frac{100 H . t}{128 S} \dots\dots\dots (2)$

$$S = \frac{100 H . t}{128 W} \dots\dots\dots (3)$$

and $t = \frac{128 W . S}{100 H} \dots\dots\dots (4)$

Example 1.—Required the horse-powers (H) of a locomotive engine, which moves with a steady speed of 50 miles per hour on a level railway, the weight of the train being 45 tons, and the friction $\frac{1}{280}$ of the weight of the train, the resistance of the air not being considered.

By formula (1),

$$H = \frac{128 W . S}{100 t} = \frac{128 \times 45 \times 50}{100 \times 60} = 48 \text{ horse-powers.}$$

Example 2.—An engine of 40 horse-powers moves with a steady speed of 35 miles per hour on a level railway; required the weight of the train, the friction being as usual.

By formula (2),

$$W = \frac{100 H . t}{128 S} = \frac{100 \times 40 \times 60}{128 \times 35} = 53\frac{1}{4} \text{ tons.}$$

Example 3.—In what time will an engine of 50 horse-powers, moving a train of 60 tons, complete a distance of 80 miles?

By formula (4),

$$t = \frac{128 W . S}{100 H} = \frac{128 \times 60 \times 80}{100 \times 50} = 122\frac{2}{3} \text{ min.} = 2 \text{ h. } 22\frac{2}{3} \text{ min.}$$

Example 4.—How many miles per hour will a train of 40 tons be drawn by an engine of 35 horse-powers?

By formula (3),

$$S = \frac{100 \times H . t}{128 W} = \frac{100 \times 35 \times 60}{128 \times 40} = 41\frac{1}{4} \text{ miles per hour.}$$

Example 5.—At what rate per hour will a train of 100 tons be drawn on a level railway by an engine of 50 horse-powers?

Example 6.—How many pounds per ton does the friction amount to, in Example 1, the engine being of 48 horse-powers?

By transposing formula (A),

$$\frac{1}{n} = \frac{33000 \cdot t \cdot H}{w \cdot s} = \frac{33000 \times 60 \times 48}{2240 \times 45 \times 5280 \times 50} = \frac{1}{280} \text{ of}$$

the weight of the train, or 8 lbs. per ton, the values of w and s being reduced to pounds and feet respectively.

ON MOVING A TRAIN AGAINST THE JOINT RESISTANCES OF FRICTION AND GRAVITY ON AN INCLINED PLANE.

Let P = power, and w = weight in pounds of a train, and h = rise of the inclined railway in every 100 feet of its length; then by Art. (66), Form. (2), Baker's "Statics and Dynamics," Weale's Series, $P = \frac{100 + hn}{100n} \cdot w$; and let H , s , and t respectively represent the horse-powers, space in feet, and time required in moving the weight $\frac{100 + hn}{100n} \cdot w$, as in the last articles; then $P = 33000 H =$ units of work in pounds, $\frac{s}{t} =$ feet moved in one minute by the weight $\frac{100 + hn}{100n} \cdot w$; whence $\frac{100 + hn}{100n} \cdot w \times \frac{s}{t} =$ units of work required in moving the weight w , which must be equal to the units of work in the power;

$$\therefore P = 33000 = \frac{100 + hn}{100n} \cdot w \times \frac{s}{t};$$

$$\text{whence} \quad H = \frac{(100 + hn) s w}{33000 \times 100 n t} \dots\dots\dots (B)$$

Now, let W = weight moved in tons, and S the space or distance moved in miles, as usually given in railway calculations; then $w = 2240 W$, and $s = 5280 S$; these values

being substituted in formula (B,) and n being taken = 280, as in the last article, there will result after reduction,

$$H = \frac{256 (5 + 14 h) W . S}{1000 t} \dots\dots (1)$$

$$\text{whence } W = \frac{1000 t . H}{256 (5 + 14 h) S} \dots\dots\dots (2)$$

$$S = \frac{1000 t . H}{256 (5 + 14 h) W} \dots\dots\dots (3)$$

$$t = \frac{256 (5 + 14 h) W . S}{1000 H} \dots\dots\dots (4)$$

$$\text{and } h = \frac{1000 t . H - 1280 W . S}{3584 W . S} \dots\dots (5)$$

In all these formulæ h must be taken negatively when the train moves on a descending gradient of a railway, in which case gravity assists the moving power. It also appears that when h is negative and equal to $\frac{5}{14}$ of a foot, then no power is required to move the train, for the value of H vanishes, since in this case $5 + 14 h = 0$.

Example 1.—A train of 40 tons ascends a railway gradient, rising 2 feet in 100, with a uniform speed of 15 miles per hour; required the horse-powers of the locomotive engine, the friction being as usual.

By formula (1),

$$H = \frac{256 (5 + 14 h) W . S}{1000 t} = \frac{256 (5 + 28) \times 40 \times 15}{1000 \times 60} \\ = 84\frac{1}{2} \text{ horse-powers.}$$

Example 2.—Required the horse-powers, as in the last example, when the weight of the train is 60 tons, the rise $\frac{1}{2}$ foot in 100, and the rate of motion 30 miles per hour.

Answer.—92 horse-powers.

Example 3.—An engine of 75 horse-powers ascends a gradient, rising $\frac{3}{4}$ of a foot in 100, with a uniform speed of 20 miles per hour; required the weight of the train.

By formula (2),

$$W = \frac{1000 t . H}{256 (5 + 14 h) S} = \frac{1000 \times 60 \times 75}{256 (5 + 2\frac{1}{2}) \times 20} = 56.7 \text{ tons.}$$

Example 4.—A train of 120 tons descends a gradient, falling $\frac{1}{4}$ of a foot in 100, with a uniform speed of 50 miles per hour; what are the horse-powers exerted by the engine?

Here the h must be negative, because the train descends the gradient; hence, by formula (1),

$$H = \frac{256 (5 - 14 h) S \cdot W}{1000 t} = \frac{256 (5 - \frac{1}{4}) \times 50 \times 120}{1000 \times 60} \\ = 38\frac{2}{3} \text{ horse-powers.}$$

Example 5.—A train of 50 tons ascends a gradient, having a rise of $\frac{1}{4}$ of a foot in 100; required the speed of the engine when its horse-powers are 40.

SAFETY VALVES.

In locomotive engines there are two safety valves placed on the boiler for the escape of steam when it exceeds the pressure limited by the load on these valves. One of them is placed beyond the control of the engine-man, and is commonly called the *lock-up valve*. The other valve is regulated by a lever and spring, at a somewhat lower pressure than that on the lock-up valve. The apertures for safety valves require no nice calculations. It is only necessary to have the aperture sufficiently large to let the steam off from the boiler as fast as it is generated, when the engine is not at work.

The safety valve of a locomotive engine is sometimes loaded by putting a heavy weight upon it in the case of the lock-up valve, and sometimes the other valve is secured by means of a lever with a weight to move along it to suit the required pressure, as in the stationary engine, which has already been explained, and the formula for graduating the lever given.

ON THE VARIABLE RESISTANCES TO LOCOMOTIVE ENGINES.

This engine (besides the friction of the rims of the wheels on the rails, which has been already the subject of investigation) has to overcome other variable resistances, viz., that

of the atmosphere, which varies according to the direction of the wind, which, sometimes, when very high, and in the same direction as the motion of the engine, assists its speed. The direct reverse takes place when a high wind is a-head of the direction of the motion of the engine. All other directions of the winds assist or retard its motion more or less, except direct cross-winds, which may be said to be nearly neutral in their effects. There is also a somewhat variable resistance from the friction of the axles, from the moving parts of the engine, and from the passage of the steam through the blast-pipe.

The resistance of the atmosphere is difficult to determine ; it is considered to vary as the square of the velocity. The result of the experiments of Pambour on these subjects shall here be given, and also examples to illustrate the theory.

The power of the locomotive engine cannot be exactly estimated by the pressure of steam in the boiler, and the diameter and length of the stroke of the piston, since the elastic force of the steam is diminished, in passing from the boiler to the cylinders, by the smallness of the apertures of the steam-pipes through which it has to pass. This diminution is also frequently produced by the evaporating power of the boiler not being capable of keeping up a supply of steam to the cylinders of the same elasticity as that in the boiler ; hence the pressure upon the piston is less than that upon the safety valve of the boiler. This diminution of the steam in the cylinders, compared with that in the boiler, will frequently be in the ratio of the increase of the velocity of the engine. Thus, supposing an engine can evaporate a certain quantity of water per hour, of the elasticity shown by the valve on the boiler ; if this production of steam is sufficient to supply as many cylinders-full of steam, of the same density as that in the boiler, as shall be equal to the number of strokes per minute of the piston required to produce the given velocity, the elasticity of the steam in the cylinders will be very nearly equal to that in the boiler, and, consequently, the pressure on the piston will also be very nearly equal to that in the boiler. But if the velocity of the engine is such that the number of cylinders-full of steam required is greater than the evaporation of the boiler can supply at the elasticity shown by the safety valve, then the elasticity in the cylinders is proportionally diminished.

Example.—A railway train moves at the rate of 30 miles per hour upon a level rail, the resistance from friction is 8 lbs. per ton, the resistance of the atmosphere 30 lbs. on the train when the rate is 10 miles per hour, the diameter of the driving wheels 6 feet, the area of the piston 100 square inches, the length of the stroke 18 inches, the resistance due to the blast-pipe is $1\frac{3}{4}$ lbs. per square inch of the piston when the rate is 10 miles per hour; required the pressure of the steam, the evaporation of the boiler, the number of bushels of coals for a journey of 150 miles, supposing that one bushel of coals can evaporate 11 cubic feet of water, the weight of the train being 90 tons.

$$8 \times 90 = 720 = \text{resistance from the friction,}$$

$$\left(\frac{30}{10}\right)^2 \times 30 = 270 = \text{resistance of the atmosphere against the train.}$$

$$720 + 270 = 990 \text{ lbs.} = \text{whole resistance to the motion of the train,}$$

$$6 \times 3.1416 = 18.8496 \text{ feet moved over by the driving wheels in one revolution,}$$

$$18.8496 \times 990 = 18661.104 = \text{work of resistance in one revolution.}$$

Since the engine has two cylinders, and each piston makes two strokes in one revolution of the driving wheels, the work done in one stroke must be multiplied by 4; hence,

$$1 \times 100 \times \frac{3}{2} \times 4 = 600 = \text{the work of 1 lb. pressure per square inch on the pistons in one revolution of the driving wheels.}$$

The effective pressure of one square inch of the piston, multiplied by the work of 1 lb. per square inch pressure in one revolution, must be equal to the resistances in one revolution; hence,

$$\frac{18661.104}{600} = 31.102 \text{ lbs.} = \text{pressure on one square inch.}$$

From the experiments of Pambour, it has been found that the resistance of the blast-pipe, or steam-jet, increases

directly as the velocity, and the co-efficient he gives is $\cdot 175$; and hence, at any given velocity it is $\cdot 175$ multiplied by that velocity, that is, for a velocity of 30 miles per hour.

$$\cdot 175 \times 30 = 5\cdot 25 \text{ lbs.} = \text{resistance of the blast-pipe,}$$

$$\therefore 31\cdot 102 + \frac{1}{7} \times 31\cdot 102 + 5\cdot 25 + 15 + 1 = 56\cdot 795 \text{ lbs.} =$$

pressure per square inch.

$$\frac{30 \times 5280}{6 \times 3\cdot 1416 \times 60} = 140 = \text{number of revolutions of the driving wheels per minute.}$$

$$4 \times 140 = 560 = \text{number of strokes of the piston per minute.}$$

$$\frac{100}{144} \times \frac{3}{2} \times 560 = 583 \text{ cubic feet} = \text{volume of steam}$$

discharged per minute; but by the table one cubic foot of water produces 498 cubic feet of steam at 56 lbs. pressure (the decimal $\cdot 795$ being neglected); hence the number of

$$\text{cubic feet evaporated per minute is } \frac{583}{498} = 1\cdot 17; \text{ and since}$$

one bushel of coals evaporates 11 cubic feet of water, the

$$\text{number of bushels of coals used in one minute is } = \frac{1\cdot 17}{11},$$

and for 5 hours, which it requires to go over 150 miles,

$$\text{there results } \frac{1\cdot 17}{11} \times 60 \times 5 = 32 \text{ bushels of coals, nearly,}$$

to convey 90 tons 150 miles. For further information on these important subjects, see the new edition of "Tredgold on the Steam Engine."

Note.—In concluding the subject of the motion of locomotive engines on railways, it will be here proper to remark that the methods of laying out railway-curves on the ground, of cutting, embanking, &c., were first prepared by the author of this work at the commencement of the railway era (1824); and have since that time been fully adopted in practice, not only in this kingdom and its numerous colonies, but also in India, the United States, and other foreign countries; more than thirty thousand copies of his works, embodying these methods in a practical form, have been sold. He also gave a greatly improved method of calculating the contents of railway cuttings, and remodelled the several methods of dividing lands and commons of variable

value among the several claimants, in proportion to the value of their claims, thus giving these important parts of applied mathematics a more scientific and comprehensive form than they previously possessed. See Baker's "Land and Engineering Surveying," Weale's Series, and Baker's "Engineering and Earthwork," and Nugent's edition of Railway Construction, Weale's Series, No. 62.

ON THE STEAM-BLAST, OR STEAM-JET, IN LOCOMOTIVES, ETC.

The steam-jet in locomotive engines leads from the exhaust passages of the cylinders into the chimney, and causes the draught through the fire-tubes necessary for the enormous consumption of fuel which is required in the locomotive, since each jet of steam emitted creates a partial vacuum in the chimney, which is immediately filled by a current of air rushing through the fire-grate.

"This mode of draught, which is at the same time economical and of extreme simplicity, is preferable to all others, inasmuch as, by using it, the draught may be varied more easily than by making use of machines, the effect of which cannot increase the draught, except by an augmentation of the velocity, which is frequently found inconvenient and very limited. It would be important to bring the steam to the exhausting ports by a pipe of larger diameter, in order that in its passage the steam should experience but little friction, and also that the exhausting ports should have the proper dimensions, so that the steam at its issue might nearly acquire the velocity which corresponds to the pressure in the boiler. It has been asserted that, in the steam-jet, all the effect produced by the *vis viva* of the steam was not obtained unless the air was at a temperature sufficiently high for no condensation of the steam to take place; but it appears that this circumstance bears no very sensible influence. However, it would be useful to try some experiments on that subject."

"It has also been asserted, from experiments made on locomotives, that by the use of an intermittent jet a greater useful effect was produced than by a continuous one. Supposing this to be true, it should be seen if, in the experiments that have been made, the tension of the steam was not greater with the intermittent jet than by the continuous one." See M. Peclet's "Treatise on Heat," Art. 577

ON CHIMNEYS.

From numerous experiments, the following laws are deduced in reference to the production of the motion of air or gases, in pipes or close galleries :—

1st. All other things being the same, the pressure required to generate velocity only is proportional to the square of such velocity.

2nd. All other things being the same, the pressure required to overcome the resistance offered by pipes, walls, or sides of galleries is also proportional to the square of the velocity with which the air moves.

Whence it follows that, all other things being equal, whatever may be the pressure and velocity causing ventilation, a certain fixed proportion or percentage is expended in generating the velocity, and the remaining constant proportion is expended in overcoming the frictional resistance by the wall of the chimney.

From the experiments of Regnault, it appears that air expands 0.3665 of its volume at 32° of Fahrenheit, by being heated from that temperature to 212° on the same scale; hence the friction

$$\frac{0.3665}{212^\circ - 32} = \frac{1}{491}$$

has been adopted as the correct measure of the expansion of air for each degree of Fahrenheit between the limits just stated.

Let v = the volume of any given weight of air at the temperature of 32°, v' = the volume it assumes on being heated to any higher temperature t , and v'' = the volume at the temperature t' ; then

$$v : v'' :: v \left(1 + \frac{t - 32}{491} \right) : v \left(1 + \frac{t' - 32}{491} \right),$$

$$\text{whence } v'' \left(1 + \frac{t - 32}{491} \right) = v' \left(1 + \frac{t' - 32}{491} \right),$$

from which

$$v'' = \left(\frac{t' + 491 - 32}{t + 491 - 32} \right) v' = \left(\frac{t' + 459}{t + 459} \right) v' \dots (1)$$

an equation from which the volume of air at any given temperature can readily be found from its volume at any other temperature.

It is known that if h = height of a chimney in which air is allowed to expand freely by heat, under a constant pressure (barometrical); by heating the air in such a chimney from a temperature t to a higher temperature t' , its contents will be expanded in the ratio of

$$h \text{ to } h \left(\frac{t' + 459}{t + 459} \right);$$

and hence the difference,

$$h \left(\frac{t' + 459}{t + 459} \right) - h, \text{ or } h \left(\frac{t' + 459}{t + 459} - 1 \right) = \frac{h(t' - t)}{t + 459} \dots (2)$$

would represent the length of a column of air at t' , having the same area as the chimney, which would be expelled from it by such an increase of temperature. The height of such expelled column, reduced to air of the temperature t , would be

$$\frac{h(t' - t)}{t + 459} \div \frac{t' + 459}{t + 459} = \frac{h(t' - t)}{t' + 459} \dots\dots (3)$$

This may be called the *motive height*; whence

$$v = 8 \sqrt{\text{motive height}} = 8 \sqrt{h \left(\frac{t' - t}{t' + 459} \right)} \dots (4)$$

which is the same theorem as that given by Tredgold, excepting the constant, which is a little less than that given by Regnault.

MISCELLANEOUS EXAMPLES.

1. Given the area of the piston of a high-pressure stationary engine 400 square inches, the length of the stroke 6 feet, the evaporation of the boiler $1\frac{1}{2}$ cubic feet of water per minute, and the pressure of steam in the cylinder 60 lbs. per square inch; required the useful load and the horse-powers.

2. In a condensing engine the area of the cylinder is 1000 square inches, the length of the stroke including clearance 5 feet, the steam is cut off at 1 foot of the stroke, the clearance is $\frac{1}{2}$ of a foot, the pressure of steam is 30 lbs., the elasticity of vapour in the condenser is 4 lbs., the effective evaporation of the boiler is $\frac{1}{2}$ of a cubic foot per minute, and the resistance as usual; required the useful load and horse-powers. See solution to question 3, page 33.

3. Let the area of the piston be 1800 square inches, the length of the stroke including clearance $10\frac{1}{2}$ feet, the clearance being $\frac{1}{2}$ of a foot, the steam is cut off at 2 feet of the stroke, the pressure of steam in the cylinder is 48 lbs. per square inch, the elasticity of vapour in the condenser is 4 lbs., the total resistance from friction is $1\frac{3}{4}$ lbs. per square inch of the piston, the effective evaporation of the boiler is $\frac{2}{15}$ of a cubic foot per minute; required the useful work per minute, the effective horse-powers, the number of strokes per minute, and the duty of the engine, allowing one bushel to evaporate 10 cubic feet of water.

4. The area of the piston is 1500 square inches, length of the stroke including clearance of 6 inches is 9 feet, the steam is cut off at 3 feet of the stroke, the pressure of steam in the cylinder is 45 lbs. per square inch, the elasticity of the vapour in the condenser is 3 lbs., and the resistance is $1\frac{1}{2}$ lbs., and the number of strokes per minute is 20; required the quantity of water evaporated per minute, the horse-powers, and the useful load on the piston.

5. The area of the piston is 1800 square inches, $\frac{1}{3}$ of a cubic foot of water is evaporated per minute, the number of strokes per minute is 18, the length of the stroke including clearance of 6 inches is $10\frac{1}{2}$ feet, the steam is cut off at 2 feet of the stroke, and the total resistance of vapour in the condenser and of friction are together $5\frac{1}{2}$ lbs.; required the horse-powers.

6. The horse-powers of an engine are 200, the length of stroke with clearance of 6 inches is 10 feet, the steam is cut off at 20 inches of the stroke, the pressure of the steam is 45 lbs., the elasticity of vapour in the condenser is 4 lbs., the resistance from friction 2 lbs. per square inch, and the number of strokes 20; required the area of the piston, and the useful load on each square inch thereof.

7. The area of the piston is 4000 square inches, the length of the stroke including clearance of $\frac{1}{2}$ a foot is $10\frac{1}{2}$ feet, the pressure of the steam 40 lbs. per square inch, the pressure of vapour in the condenser and the resistance from friction are together 5 lbs. per square inch; required at what part of the stroke the steam must be cut off so as to yield all its work, the horse-powers of the engine, the useful load on the piston, and the quantity of water evaporated.

8. Let the area of the piston = 3600 square inches, the length of the stroke = 10 feet, the number of strokes per minute = 18, the elasticity of the steam = 36 lbs., that of the vapour in the condenser including the resistance of friction 5 lbs., and the steam is cut off at $\frac{1}{3}$ of the stroke; required the horse-powers of the engine, the load, and the point at which the velocity of the piston is a maximum.

9. The length of the stroke is 12 feet, the pressure of steam in the cylinder is 50 lbs.; at what point of the stroke must the steam be cut off so as to yield all its work, when the resistance of the vapour in the condenser together with the friction of the engine is 5 lbs. per square inch on the piston?

10. The length of the stroke is 10 feet, the steam is cut off at $\frac{1}{4}$ of the stroke, the area of the piston is 3600 square inches, the number of strokes per minute is 18, the clearance is $\frac{1}{2}$ a foot, the pressure of vapour in the condenser is 3 lbs., and the water evaporated per minute is $\frac{3}{4}$ of a cubic foot; required the useful load, supposing the friction of the unloaded piston to be 5 lbs. per square inch, and the additional friction to be $\frac{1}{3}$ of the useful load.

11. The area of the piston is 2000 square inches, the length of the stroke including the clearance of 6 inches is 12 feet, the effective evaporation is $\frac{1}{3}\frac{2}{3}$ of a cubic foot per minute, the pressure of the steam in the cylinder is 50 lbs., and the elasticity of the vapour in the condenser together with the resistance of friction is $6\frac{1}{2}$ lbs.; required the point at which the steam must be cut off, so that all its work may be

expended, the number of strokes per minute, the useful work, the effective horse-powers, and the duty of the engine, allowing that one bushel of coals can evaporate 12 cubic feet of water.

12. The diameter of the cylinder is 40 inches, the length of the stroke 10 feet, the clearance $\frac{1}{10}$ of the stroke, the pressure in the boiler 21·5 lbs. per square inch, the effective evaporation $\frac{9}{10}$ of a cubic foot of water per minute, and the consumption of coals in the same time $8\frac{1}{2}$ lbs.; required the useful horse-powers, when the piston moves with the velocity of 250 feet per minute; also find the useful effects of one pound of coals and one cubic foot of water.

Note.—The solution to all these questions may be obtained by means of the formulæ, commencing at page 26.

APPENDIX.

ON THE STRENGTH, FRICTION, ETC., OF SEVERAL IMPORTANT PARTS OF THE STEAM ENGINE.

ON GUDGEONS.

In gudgeons, one-fifth of the diameter is usually allowed for wear, and Mr. Tredgold, on this principle, gives the following

RULE.—Multiply the stress in pounds by the length of the gudgeon in inches, and the cube root of the product, divided by 9, is the diameter of the gudgeon in inches.

Example.—If the stress on a gudgeon be 12 tons, and its length 8 inches ; required its diameter.

$$2240 \times 12 \times 8 = 215040$$

$$\sqrt[3]{215040} = 60 \text{ nearly,}$$

$$\text{and } \frac{60}{9} = 6\frac{2}{3} \text{ inches, the diameter of the gudgeon.}$$

CRANKS.

The force or weight acting on a crank being given, to find its breadth and depth.

RULE.—Multiply the weight in pounds, acting at the end of a crank, by the cube of its length in feet, and this product being divided by 2662 times the deflection, will give the product of the cube of the depth and the breadth in inches.

Example.—If the force acting upon a crank be 6000 lbs., and its length 3 feet ; required its breadth and depth, so that the deflection may not exceed $\frac{1}{8}$ of an inch.

By the rule, $\frac{6000 \times 3^3}{2662 \times .1} = 609$ nearly = cube of the depth multiplied by the breadth.

If the breadth be assumed = 3 inches, then

$$\sqrt[3]{\frac{609}{3}} = 6 \text{ inches nearly} = \text{the depth.}$$

If the depth at the end where the force acts be half the depth at the axis, divide by 1628 instead of 2662; then

$\frac{6000 \times 3^3}{1628 \times .1} = 995$ = cube of the depth multiplied by the breadth; and if the breadth be taken = 3 inches, as before, then

$$\sqrt[3]{\frac{995}{3}} = 6.93 \text{ inches, the greater depth;}$$

$$\text{and } \frac{6.93}{2} = 3.465 \text{ inches, the lesser depth.}$$

FRICTION OF AN AXLE.

Let P = pressure on the bearings,

r = radius of the axle,

n = number of revolutions per second,

f = ratio of the friction to the pressure corresponding to the bodies in contact,

and $\pi = 3.1416$; then

$$2\pi \cdot P \cdot f \cdot r \cdot n = \text{work of friction per second.}$$

Example.—Given the radius of the axle = 6 inches, the weight of the shaft and other parts pressing on it = 1500 lbs., the shaft making 10 revolutions per minute; required the work expended on friction.

Let the co-efficient of friction $f = .07$, and since 6 inches = .5 of a foot, there results from the preceding formula

$$\frac{2 \times 3.1416 \times 1500 \times .07 \times .5 \times 10}{60} = 54.978 \text{ lbs.,}$$

the quantity of work expended on friction per second.

FRICTION ON A PIVOT.

The symbols P , r , n , f , representing the same things as in the last article, there will result the following formula for the friction on a pivot,

$$4 \cdot 2 \times P \cdot f \cdot r \cdot n$$

= the work expended on friction per second.

Example.—Given the radius of the base of the pivot = 3 inches, the weight pressing upon it 2000 lbs.; the pivot makes 10 revolutions per minute; required the work expended on friction.

Let the co-efficient of friction $f = \cdot 07$, and since 3 inches = $\cdot 25$ of a foot, there results from the formula

$$\frac{4 \cdot 2 \times 2000 \times \cdot 07 \times \cdot 25 \times 10}{60} = 24\frac{1}{2} \text{ lbs. nearly.}$$

FRICTION OF CYLINDERS.

The proportion which the friction of a large cylinder bears to the friction of any number of cylinders, the sum of the areas of which is equal to the area of the large cylinder, may be shown in the following manner:—

Let d = diameter of one of the small cylinders,
and n = the number of them; then

$$\frac{\pi}{4} n d^2 = \text{area of the large cylinder;}$$

$$\therefore d \sqrt{n} = \text{diameter of the large cylinder.}$$

But the friction is proportional to the circumference of the cylinder; therefore the friction of the small cylinders is

$$\pi d n,$$

and the friction of the large cylinder is

$$\pi d \sqrt{n}.$$

Hence, the friction of the large cylinder : the friction of all the small cylinders :: $\pi d \sqrt{n}$: $\pi d n$,

$$:: 1 : \sqrt{n};$$

which proportion, in the case of four small cylinders, becomes as 1 : 2, that is, the friction of four cylinders is double the friction of one cylinder, the area of which is equal to the areas of all the four.

ON WINDING MACHINES,

MOVED BY THE STEAM ENGINE, FOR DRAWING COALS OUT
OF A SHAFT.

In winding machines of this kind the steam engine is intended to produce a given number of strokes in drawing up a corf; hence, the diameter of the roll must be ascertained at the first lift. In this case it is supposed that the machine has flat ropes, such as are now generally used, and which coil upon each other.

To find the diameter of the roll at the first lift, it will be necessary to know the thickness of the rope, the depth of the shaft or pit, and the number of strokes which the steam engine is intended to make in drawing up a corf or corves.

Then the number of strokes of the engine, and the thickness of the rope being both known, the thickness of the rope upon the roll can be determined, let the diameter of the rope be what it may. Thus, suppose the thickness of the rope be 1 inch, and the number of strokes 12; the radius of the roll is increased 12 inches, or the diameter is increased 24 inches, whatever that diameter may be.

Put d = the depth of the shaft or pit,
and t = the thickness of the rope, both in inches;
also n = the number of strokes of the engine,
 $\pi = 3.1416$,
and x = the diameter of roll.

$$\text{Then} \quad n = \frac{d - \pi n^2 t}{\pi n}.$$

Example.—If an engine makes 20 strokes in drawing a corf up a shaft, the depth of which is 100 fathoms, and the thickness of the rope 1 inch; required the diameter of the roll at the first lift.

By the formula,

$$x = \frac{d - \pi n^2 t}{\pi n};$$

that is,
$$x = \frac{100 \times 72 - 3.1416 \times 20^2 \times 1}{3.1416 \times 20} =$$

$$\frac{7200 - 1256.64}{62.832} = 94.59 \text{ inches} =$$

7 feet 10.6 inches nearly, the required diameter of the roll.

It is proper here to remark that if an engine be drawing coals out of a pit where round ropes have been used, and if it be required to take the round ones off, and supply their place with flat ones, the formula just given will determine the diameter of the roll at the first lift, so that the engine may go the same number of strokes as when the round ropes were on.

Example.—If an engine goes 10 strokes in drawing a corf up a shaft, the depth of which is 60 fathoms, with round ropes, where these round ropes do not coil upon each other, what must be the diameter of the flat rope roll, so that the engine may go the same number of strokes as before, the thickness of the rope being $\frac{1}{2}$ an inch?

By the formula,

$$x = \frac{d - \pi n^2 t}{\pi n},$$

that is,
$$x = \frac{60 \times 72 - 3.1416 \times 10^2 \times \frac{1}{2}}{3.1416 \times 10} =$$

$$\frac{4320 - 157.08}{31.416} = 132.5 \text{ inches} =$$

11 feet $0\frac{1}{2}$ inch = the diameter of the rope roll.

To find the Position of the Meetings in a Coal Shaft.

When an engine draws coals out of a shaft with flat ropes, the curves will not pass each other at mid-shaft, that is, half way between the top and bottom of the shaft; for the corf which descends from the top of the shaft will pass

through a greater space in the same time than the corf which ascends from the bottom, owing to the circumference of the roll being always greater until the engine has performed half its number of strokes; therefore the meetings will always be below mid-shaft. At the meetings the number of coils of the ropes on the roll are equal, and after this the roll on which the ascending corf hangs continues to increase until the corf arrives at the top of the shaft.

*To find where the Ascending and Descending Corves will meet.**

Let the depth of the shaft and the thickness of the rope be represented as in the last formula, and let r = radius of the roll, and let the distance of the meeting from the bottom of the shaft = y ; then we may use either of the following formulæ:—

$$y = \frac{1}{4} \pi n^2 t + \pi r n.$$

$$y = d - \frac{3}{4} \pi n^2 t - \pi n r. \quad y = \frac{1}{4} d - \frac{1}{4} \pi n^2 t.$$

Example.—At what distance from the bottom of a shaft will the corves meet, the following being given?

$d = 600$ feet, $t = \frac{1}{16}$ foot, $n = 20$, $r = 8.9418$ feet, as in last problem.

Calculation by the first Formula.

$$y = 8.1416 \times 100 \times \frac{1}{16} + 81.416 \times 8.9418 \times 2 = 26.18 + 247.68976 = 273.82.$$

Hence, the distance of the place of meeting from the bottom of the pit is 274 feet, within about two inches.

Calculation by the second Formula.

$$y = 600 - \frac{1}{16} \times 400 - 81.416 \times 8.9418 \times 2 = 600 - 78.54 - 247.64 = 273.82.$$

Calculation by the third Formula.

$$y = 300 - 8.1416 \times 100 \times \frac{1}{16} = 300 - 81.416 \times \frac{1}{16} = 300 - 26.18 = 273.82.$$

Hence, as before, the place of meeting is at the distance 273.82 feet, or 274 feet *nearly*, from the bottom of the pit.

* The formulæ and investigations following have been kindly supplied by Professor J. R. Young.

Demonstrations of the Formulæ in the last Problem.

In investigating formulæ for the foregoing problem, it must be remembered that when the curves meet, the number of coils on the roll for the ascending curve is the same as the number for the descending curve, the engine having then performed half its number of strokes. Hence, putting y for the distance of the place of meeting from the bottom of the pit, and regarding y , for the moment, as the entire depth, the number of strokes for this depth being $\frac{1}{2} n$, we have

$$2r = \frac{y - \frac{1}{2} \pi n^2 t}{\frac{1}{2} \pi n}$$

$\therefore r \pi n = y - \frac{1}{2} \pi n^2 t$, and therefore $y = \frac{1}{2} \pi n^2 t + \pi r n$;

which is the first of the formulæ employed.

Again: the diameter of the coil at the first lift is $2r$; and when the corf is drawn up the distance y from the bottom of the pit, the engine having performed $\frac{1}{2} n$ strokes, $\frac{1}{2} n t$ expresses the thickness added to the coil, or the amount by which the radius r is increased; in other words, when the corf is at the distance y from the bottom, the *diameter* of the coil is $2r + n t$, which, of course, is the same as the diameter of the coil for the other corf, when this is at the distance $d - y$ from the top. Hence,

$$\frac{d - y - \frac{1}{2} \pi n^2 t}{\frac{1}{2} \pi n} = 2r + n t$$

$$\therefore d - y - \frac{1}{2} \pi n^2 t = \pi n r + \frac{1}{2} \pi n^2 t$$

$$\therefore y = d - \frac{1}{2} \pi n^2 t - \frac{1}{2} \pi n^2 t - \pi n r = d - \pi n^2 t - \pi n r;$$

which is the second formula employed; and the third is half the sum of these two. A *fourth* formula is $y = \frac{1}{2} d + \frac{1}{2} \pi r n$.

NOTE TO THE TABLE OF HYPERBOLIC LOGARITHMS.—The common log. of any number multiplied by 2.80258505 gives the hyperbolic log.; and the hyperbolic log. multiplied by .48429448 gives the common log.—EDITOR.

TABLE OF HYPERBOLIC LOGARITHMS.

Nos.	Logarithm.	Nos.	Logarithm.	Nos.	Logarithm.
1.01	·0099503	1.34	·2926696	1.67	·5128236
1.02	·0198026	1.35	·3001045	1.68	·5187937
1.03	·0295588	1.36	·3074846	1.69	·5247285
1.04	·0392207	1.37	·3148107	1.70	·5306282
1.05	·0487902	1.38	·3220834	1.71	·5364933
1.06	·0582689	1.39	·3293037	1.72	·5423242
1.07	·0676586	1.40	·3364722	1.73	·5481214
1.08	·0769610	1.41	·3435897	1.74	·5538851
1.09	·0861777	1.42	·3506568	1.75	·5596157
1.10	·0953102	1.43	·3576744	1.76	·5653138
1.11	·1043600	1.44	·3646431	1.77	·5709795
1.12	·1133287	1.45	·3715635	1.78	·5766133
1.13	·1222176	1.46	·3784364	1.79	·5822156
1.14	·1310283	1.47	·3852624	1.80	·5877866
1.15	·1397619	1.48	·3920420	1.81	·5933268
1.16	·1484200	1.49	·3987761	1.82	·5988365
1.17	·1570037	1.50	·4054651	1.83	·6043159
1.18	·1655144	1.51	·4121097	1.84	·6097655
1.19	·1739533	1.52	·4187103	1.85	·6151856
1.20	·1823215	1.53	·4252677	1.86	·6205764
1.21	·1906203	1.54	·4317824	1.87	·6259384
1.22	·1988508	1.55	·4382549	1.88	·6312717
1.23	·2070141	1.56	·4446858	1.89	·6365768
1.24	·2151113	1.57	·4510756	1.90	·6418538
1.25	·2231435	1.58	·4574248	1.91	·6471032
1.26	·2311117	1.59	·4637340	1.92	·6523251
1.27	·2390169	1.60	·4700036	1.93	·6575200
1.28	·2468600	1.61	·4762341	1.94	·6626879
1.29	·2546422	1.62	·4824261	1.95	·6678293
1.30	·2623642	1.63	·4885800	1.96	·6729444
1.31	·2700271	1.64	·4946962	1.97	·6780335
1.32	·2776317	1.65	·5007752	1.98	·6830968
1.33	·2851789	1.66	·5068174	1.99	·6881346
1.34	·2926696	1.67	·5128236	2.00	·6931472

No.	Logarithm.	No.	Logarithm.	No.	Logarithm.
2-01	·6961347	2-34	·8501509	2-67	·9820784
2-02	·7030974	2-35	·8544153	2-68	·9858167
2-03	·7080357	2-36	·8586616	2-69	·9895411
2-04	·7129497	2-37	·8628899	2-70	·9932517
2-05	·7178397	2-38	·8671004	2-71	·9969486
2-06	·7227059	2-39	·8712933	2-72	1-0006318
2-07	·7275485	2-40	·8754687	2-73	1-0043015
2-08	·7323678	2-41	·8796267	2-74	1-0079579
2-09	·7371640	2-42	·8837675	2-75	1-0116008
2-10	·7419373	2-43	·8878912	2-76	1-0152306
2-11	·7466879	2-44	·8919980	2-77	1-0188473
2-12	·7514160	2-45	·8960880	2-78	1-0224509
2-13	·7561219	2-46	·9001613	2-79	1-0260415
2-14	·7608058	2-47	·9042181	2-80	1-0296194
2-15	·7654678	2-48	·9082585	2-81	1-0331846
2-16	·7701082	2-49	·9122826	2-82	1-0367368
2-17	·7747271	2-50	·9162907	2-83	1-0402766
2-18	·7793248	2-51	·9202827	2-84	1-0438040
2-19	·7839015	2-52	·9242589	2-85	1-0473189
2-20	·7884573	2-53	·9282193	2-86	1-0508216
2-21	·7929925	2-54	·9321640	2-87	1-0543120
2-22	·7975071	2-55	·9360933	2-88	1-0577902
2-23	·8020015	2-56	·9400072	2-89	1-0612564
2-24	·8064758	2-57	·9439058	2-90	1-0647107
2-25	·8109302	2-58	·9477893	2-91	1-0681530
2-26	·8153648	2-59	·9516578	2-92	1-0715836
2-27	·8197798	2-60	·9555114	2-93	1-0750024
2-28	·8241754	2-61	·9593502	2-94	1-0784095
2-29	·8285518	2-62	·9631743	2-95	1-0818051
2-30	·8329091	2-63	·9669838	2-96	1-0851892
2-31	·8372475	2-64	·9707789	2-97	1-0885619
2-32	·8415671	2-65	·9745596	2-98	1-0919233
2-33	·8458682	2-66	·9783261	2-99	1-0952733
2-34	·8501509	2-67	·9820784	3-00	1-0986123

Nos.	Logarithm.	Nos.	Logarithm.	Nos.	Logarithm.
3·01	1·1019400	3·34	1·2059707	3·67	1·3001916
3·02	1·1052568	3·35	1·2089603	3·68	1·3029127
3·03	1·1085626	3·36	1·2119409	3·69	1·3056264
3·04	1·1118575	3·37	1·2149127	3·70	1·3083328
3·05	1·1151415	3·38	1·2178757	3·71	1·3110318
3·06	1·1184149	3·39	1·2208299	3·72	1·3137236
3·07	1·1216775	3·40	1·2237754	3·73	1·3164082
3·08	1·1249295	3·41	1·2267122	3·74	1·3190856
3·09	1·1281710	3·42	1·2296405	3·75	1·3217558
3·10	1·1314021	3·43	1·2325605	3·76	1·3244189
3·11	1·1346227	3·44	1·2354714	3·77	1·3270749
3·12	1·1378330	3·45	1·2383742	3·78	1·3297240
3·13	1·1410330	3·46	1·2412685	3·79	1·3323660
3·14	1·1442227	3·47	1·2441545	3·80	1·3350010
3·15	1·1474024	3·48	1·2470322	3·81	1·3376291
3·16	1·1505720	3·49	1·2499017	3·82	1·3402504
3·17	1·1537315	3·50	1·2527629	3·83	1·3428648
3·18	1·1568811	3·51	1·2556160	3·84	1·3454723
3·19	1·1600209	3·52	1·2584609	3·85	1·3480731
3·20	1·1631508	3·53	1·2612978	3·86	1·3506671
3·21	1·1662709	3·54	1·2641266	3·87	1·3532544
3·22	1·1693813	3·55	1·2669475	3·88	1·3558351
3·23	1·1724821	3·56	1·2697605	3·89	1·3584091
3·24	1·1755733	3·57	1·2725655	3·90	1·3609765
3·25	1·1786549	3·58	1·2753627	3·91	1·3635373
3·26	1·1817271	3·59	1·2781521	3·92	1·3660916
3·27	1·1847899	3·60	1·2809338	3·93	1·3686394
3·28	1·1878434	3·61	1·2837077	3·94	1·3711807
3·29	1·1908875	3·62	1·2864740	3·95	1·3737156
3·30	1·1939224	3·63	1·2892326	3·96	1·3762440
3·31	1·1969482	3·64	1·2919836	3·97	1·3787661
3·32	1·1999647	3·65	1·2947271	3·98	1·3812818
3·33	1·2029722	3·66	1·2974631	3·99	1·3837912
3·34	1·2059707	3·67	1·3001916	4·00	1·3862943

Nos.	Logarithm.	Nos.	Logarithm.	Nos.	Logarithm.
4·01	1·3887912	4·34	1·4678743	4·67	1·5411590
4·02	1·3912818	4·35	1·4701758	4·68	1·5432981
4·03	1·3937663	4·36	1·4724720	4·69	1·5454325
4·04	1·3962446	4·37	1·4747630	4·70	1·5475625
4·05	1·3987168	4·38	1·4770487	4·71	1·5496879
4·06	1·4011829	4·39	1·4793292	4·72	1·5518087
4·07	1·4036429	4·40	1·4816045	4·73	1·5539252
4·08	1·4060969	4·41	1·4838746	4·74	1·5560371
4·09	1·4085449	4·42	1·4861396	4·75	1·5581446
4·10	1·4109869	4·43	1·4883995	4·76	1·5602476
4·11	1·4134230	4·44	1·4906543	4·77	1·5623462
4·12	1·4158531	4·45	1·4929040	4·78	1·5644405
4·13	1·4182774	4·46	1·4951487	4·79	1·5665304
4·14	1·4206957	4·47	1·4973883	4·80	1·5686159
4·15	1·4231085	4·48	1·4996230	4·81	1·5706971
4·16	1·4255150	4·49	1·5018527	4·82	1·5727739
4·17	1·4279160	4·50	1·5040774	4·83	1·5748464
4·18	1·4303112	4·51	1·5062971	4·84	1·5769147
4·19	1·4327007	4·52	1·5085119	4·85	1·5789787
4·20	1·4350845	4·53	1·5107219	4·86	1·5810384
4·21	1·4374626	4·54	1·5129269	4·87	1·5830939
4·22	1·4398351	4·55	1·5151272	4·88	1·5851452
4·23	1·4422020	4·56	1·5173226	4·89	1·5871923
4·24	1·4445632	4·57	1·5195132	4·90	1·5892352
4·25	1·4469189	4·58	1·5216990	4·91	1·5912739
4·26	1·4492691	4·59	1·5238800	4·92	1·5933085
4·27	1·4516138	4·60	1·5260563	4·93	1·5953389
4·28	1·4539530	4·61	1·5282278	4·94	1·5973653
4·29	1·4562867	4·62	1·5303947	4·95	1·5993875
4·30	1·4586149	4·63	1·5325568	4·96	1·6014057
4·31	1·4609379	4·64	1·5347143	4·97	1·6034198
4·32	1·4632553	4·65	1·5368672	4·98	1·6054298
4·33	1·4655675	4·66	1·5390154	4·99	1·6074358
4·34	1·4678743	4·67	1·5411590	5·00	1·6094379

Nos.	Logarithm.	Nos.	Logarithm.	Nos.	Logarithm.
5·01	1·6114359	5·34	1·6752256	5·67	1·7351891
5·02	1·6134300	5·35	1·6770956	5·68	1·7369512
5·03	1·6154200	5·36	1·6789639	5·69	1·7387102
5·04	1·6174060	5·37	1·6808278	5·70	1·7404661
5·05	1·6193882	5·38	1·6826882	5·71	1·7422189
5·06	1·6213664	5·39	1·6845453	5·72	1·7439687
5·07	1·6233408	5·40	1·6863989	5·73	1·7457155
5·08	1·6253112	5·41	1·6882491	5·74	1·7474951
5·09	1·6272778	5·42	1·6900958	5·75	1·7491998
5·10	1·6292405	5·43	1·6919395	5·76	1·7509374
5·11	1·6311994	5·44	1·6937790	5·77	1·7526720
5·12	1·6331544	5·45	1·6956155	5·78	1·7544036
5·13	1·6351056	5·46	1·6974487	5·79	1·7561323
5·14	1·6370530	5·47	1·6992786	5·80	1·7578579
5·15	1·6389967	5·48	1·7011051	5·81	1·7595805
5·16	1·6409365	5·49	1·7029282	5·82	1·7613002
5·17	1·6428726	5·50	1·7047481	5·83	1·7630170
5·18	1·6448050	5·51	1·7065646	5·84	1·7647308
5·19	1·6467336	5·52	1·7083778	5·85	1·7664416
5·20	1·6486586	5·53	1·7101878	5·86	1·7681496
5·21	1·6505798	5·54	1·7119944	5·87	1·7698546
5·22	1·6524974	5·55	1·7137979	5·88	1·7715567
5·23	1·6544112	5·56	1·7155981	5·89	1·7732559
5·24	1·6563214	5·57	1·7173950	5·90	1·7749523
5·25	1·6582280	5·58	1·7191887	5·91	1·7766458
5·26	1·6601310	5·59	1·7209792	5·92	1·7783364
5·27	1·6620303	5·60	1·7227666	5·93	1·7800242
5·28	1·6639260	5·61	1·7245507	5·94	1·7817091
5·29	1·6658182	5·62	1·7263316	5·95	1·7833912
5·30	1·6677068	5·63	1·7281094	5·96	1·7850704
5·31	1·6695918	5·64	1·7298840	5·97	1·7867469
5·32	1·6714733	5·65	1·7316555	5·98	1·7884205
5·33	1·6733512	5·66	1·7334238	5·99	1·7900914
5·34	1·6752256	5·67	1·7351891	6·00	1·7917594

Nos.	Logarithm.	Nos.	Logarithm.	Nos.	Logarithm.
6·01	1·7934247	6·34	1·8468787	6·67	1·8976198
6·02	1·7950872	6·35	1·8484547	6·68	1·8991179
6·03	1·7967470	6·36	1·8500283	6·69	1·9006138
6·04	1·7984040	6·37	1·8515994	6·70	1·9021075
6·05	1·8000582	6·38	1·8531680	6·71	1·9035989
6·06	1·8017098	6·39	1·8547342	6·72	1·9050881
6·07	1·8033586	6·40	1·8562979	6·73	1·9065751
6·08	1·8050047	6·41	1·8578592	6·74	1·9080600
6·09	1·8066481	6·42	1·8594181	6·75	1·9095425
6·10	1·8082887	6·43	1·8609745	6·76	1·9110228
6·11	1·8099267	6·44	1·8625285	6·77	1·9125011
6·12	1·8115621	6·45	1·8640801	6·78	1·9139771
6·13	1·8131947	6·46	1·8656293	6·79	1·9154509
6·14	1·8148247	6·47	1·8671761	6·80	1·9169226
6·15	1·8164520	6·48	1·8687205	6·81	1·9183921
6·16	1·8180767	6·49	1·8702625	6·82	1·9198594
6·17	1·8196988	6·50	1·8718021	6·83	1·9213247
6·18	1·8213182	6·51	1·8733394	6·84	1·9227877
6·19	1·8229351	6·52	1·8748743	6·85	1·9242486
6·20	1·8245493	6·53	1·8764069	6·86	1·9257074
6·21	1·8261608	6·54	1·8779371	6·87	1·9271641
6·22	1·8277699	6·55	1·8794650	6·88	1·9286186
6·23	1·8293763	6·56	1·8809906	6·89	1·9300710
6·24	1·8309801	6·57	1·8825138	6·90	1·9315214
6·25	1·8325814	6·58	1·8840347	6·91	1·9329696
6·26	1·8341801	6·59	1·8855533	6·92	1·9344157
6·27	1·8357763	6·60	1·8870696	6·93	1·9358598
6·28	1·8373699	6·61	1·8885837	6·94	1·9373017
6·29	1·8389610	6·62	1·8900954	6·95	1·9387416
6·30	1·8405496	6·63	1·8916048	6·96	1·9401794
6·31	1·8421356	6·64	1·8931119	6·97	1·9416152
6·32	1·8437191	6·65	1·8946168	6·98	1·9430489
6·33	1·8453002	6·66	1·8961194	6·99	1·9444805
6·34	1·8468787	6·67	1·8976198	7·00	1·9459101

Nos.	Logarithm.	Nos.	Logarithm.	Nos.	Logarithm.
7·01	1·9473376	7·34	1·9933387	7·67	2·0373166
7·02	1·9487632	7·35	1·9947002	7·68	2·0386195
7·03	1·9501866	7·36	1·9960599	7·69	2·0399207
7·04	1·9516080	7·37	1·9974177	7·70	2·0412203
7·05	1·9530275	7·38	1·9987736	7·71	2·0425181
7·06	1·9544449	7·39	2·0001278	7·72	2·0438143
7·07	1·9558604	7·40	2·0014800	7·73	2·0451088
7·08	1·9572739	7·41	2·0028305	7·74	2·0464016
7·09	1·9586853	7·42	2·0041790	7·75	2·0476928
7·10	1·9600947	7·43	2·0055258	7·76	2·0489823
7·11	1·9615022	7·44	2·0068708	7·77	2·0502701
7·12	1·9629077	7·45	2·0082140	7·78	2·0515563
7·13	1·9643112	7·46	2·0095553	7·79	2·0528408
7·14	1·9657127	7·47	2·0108949	7·80	2·0541237
7·15	1·9671123	7·48	2·0122327	7·81	2·0554049
7·16	1·9685099	7·49	2·0135687	7·82	2·0566845
7·17	1·9699056	7·50	2·0149030	7·83	2·0579624
7·18	1·9712993	7·51	2·0162354	7·84	2·0592388
7·19	1·9726911	7·52	2·0175661	7·85	2·0605135
7·20	1·9740810	7·53	2·0188950	7·86	2·0617866
7·21	1·9754689	7·54	2·0202221	7·87	2·0630580
7·22	1·9768549	7·55	2·0215475	7·88	2·0643278
7·23	1·9782390	7·56	2·0228711	7·89	2·0655961
7·24	1·9796212	7·57	2·0241929	7·90	2·0668627
7·25	1·9810014	7·58	2·0255131	7·91	2·0681277
7·26	1·9823798	7·59	2·0268315	7·92	2·0693911
7·27	1·9837562	7·60	2·0281482	7·93	2·0706530
7·28	1·9851308	7·61	2·0294631	7·94	2·0719132
7·29	1·9865035	7·62	2·0307763	7·95	2·0731719
7·30	1·9878743	7·63	2·0320878	7·96	2·0744290
7·31	1·9892432	7·64	2·0333976	7·97	2·0756845
7·32	1·9906103	7·65	2·0347056	7·98	2·0769384
7·33	1·9919754	7·66	2·0360119	7·99	2·0781907
7·34	1·9933387	7·67	2·0373166	8·00	2·0794415

Nos.	Logarithm.	Nos.	Logarithm.	Nos.	Logarithm.
8·01	2·0806907	8·34	2·1210632	8·67	2·1598687
8·02	2·0819384	8·35	2·1222615	8·68	2·1610215
8·03	2·0831845	8·36	2·1234584	8·69	2·1621729
8·04	2·0844290	8·37	2·1246539	8·70	2·1633230
8·05	2·0856720	8·38	2·1258479	8·71	2·1644718
8·06	2·0869135	8·39	2·1270405	8·72	2·1656192
8·07	2·0881534	8·40	2·1282312	8·73	2·1667653
8·08	2·0893918	8·41	2·1294214	8·74	2·1679101
8·09	2·0906287	8·42	2·1306098	8·75	2·1690536
8·10	2·0918640	8·43	2·1317967	8·76	2·1701959
8·11	2·0930984	8·44	2·1329822	8·77	2·1713367
8·12	2·0943306	8·45	2·1341664	8·78	2·1724763
8·13	2·0955613	8·46	2·1353491	8·79	2·1736146
8·14	2·0967905	8·47	2·1365304	8·80	2·1747517
8·15	2·0980182	8·48	2·1377104	8·81	2·1758874
8·16	2·0992444	8·49	2·1388889	8·82	2·1770218
8·17	2·1004691	8·50	2·1400661	8·83	2·1781550
8·18	2·1016923	8·51	2·1412419	8·84	2·1792868
8·19	2·1029140	8·52	2·1424163	8·85	2·1804172
8·20	2·1041341	8·53	2·1435893	8·86	2·1815467
8·21	2·1053529	8·54	2·1447609	8·87	2·1826747
8·22	2·1065702	8·55	2·1459312	8·88	2·1838015
8·23	2·1077861	8·56	2·1471001	8·89	2·1849207
8·24	2·1089998	8·57	2·1482681	8·90	2·1860512
8·25	2·1102128	8·58	2·1494339	8·91	2·1871742
8·26	2·1114243	8·59	2·1505987	8·92	2·1882959
8·27	2·1126343	8·60	2·1517622	8·93	2·1894163
8·28	2·1138428	8·61	2·1529243	8·94	2·1905355
8·29	2·1150499	8·62	2·1540851	8·95	2·1916535
8·30	2·1162555	8·63	2·1552445	8·96	2·1927702
8·31	2·1174596	8·64	2·1564026	8·97	2·1938856
8·32	2·1186622	8·65	2·1575593	8·98	2·1949998
8·33	2·1198634	8·66	2·1587147	8·99	2·1961128
8·34	2·1210632	8·67	2·1598687	9·00	2·1972245

Nos.	Logarithm.	Nos.	Logarithm.	Nos.	Logarithm.
9·01	2·1983350	9·34	2·2343062	9·67	2·2690282
9·02	2·1994443	9·35	2·2353763	9·68	2·2700618
9·03	2·2005523	9·36	2·2364452	9·69	2·2710944
9·04	2·2016591	9·37	2·2375130	9·70	2·2721258
9·05	2·2027647	9·38	2·2385797	9·71	2·2731562
9·06	2·2038691	9·39	2·2396452	9·72	2·2741856
9·07	2·2049722	9·40	2·2407096	9·73	2·2752142
9·08	2·2060741	9·41	2·2417729	9·74	2·2762411
9·09	2·2071748	9·42	2·2428350	9·75	2·2772673
9·10	2·2082744	9·43	2·2438960	9·76	2·2782924
9·11	2·2093727	9·44	2·2449559	9·77	2·2793165
9·12	2·2104697	9·45	2·2460147	9·78	2·2803395
9·13	2·2115656	9·46	2·2470723	9·79	2·2813614
9·14	2·2126603	9·47	2·2481288	9·80	2·2823823
9·15	2·2137538	9·48	2·2491843	9·81	2·2834022
9·16	2·2148461	9·49	2·2502386	9·82	2·2844211
9·17	2·2159372	9·50	2·2512917	9·83	2·2854389
9·18	2·2170272	9·51	2·2523438	9·84	2·2864556
9·19	2·2181160	9·52	2·2533948	9·85	2·2874714
9·20	2·2192034	9·53	2·2544446	9·86	2·2884861
9·21	2·2202898	9·54	2·2554934	9·87	2·2894998
9·22	2·2213750	9·55	2·2565411	9·88	2·2905124
9·23	2·2224590	9·56	2·2575877	9·89	2·2915241
9·24	2·2235418	9·57	2·2586332	9·90	2·2925347
9·25	2·2246235	9·58	2·2596776	9·91	2·2935443
9·26	2·2257040	9·59	2·2607209	9·92	2·2945529
9·27	2·2267833	9·60	2·2617631	9·93	2·2955604
9·28	2·2278615	9·61	2·2628042	9·94	2·2965670
9·29	2·2289385	9·62	2·2638442	9·95	2·2975725
9·30	2·2300144	9·63	2·2648832	9·96	2·2985770
9·31	2·2310890	9·64	2·2659211	9·97	2·2995806
9·32	2·2321626	9·65	2·2669579	9·98	2·3005831
9·33	2·2332350	9·66	2·2679936	9·99	2·3015846
9·34	2·2343062	9·67	2·2690282	10·00	2·3025851

TABLE OF FRICTION OF GUDGEONS OR AXLE ENDS IN MOTION ON THEIR BEARINGS.

(From the experiments of M. Morin.)

Surfaces in Contact.	State of the Surface.	Co-efficients of Friction.	
		In the usual way.	Continuously.
Cast-iron axes in cast-iron bearings	greased with oil of olives, hog's lard, tallow, or soft gom	0.07 to 0.08	0.054
	with the same and water coated with asphaltum .	0.075	0.28
	greasy	0.054	0.19
	greasy and wetted . . .	0.14	
Cast-iron axes in wrought-iron bearings	greased with oil of olives, hog's lard, tallow, or soft gom	0.18	
	greasy	0.07 to 0.08	0.056
	greasy and damped . . .	0.16	
	scarcely greasy	0.16	
Cast-iron axes in lignum-vitæ bearings	without unguent	0.19	
	with oil or hog's lard . .	0.18	
	greasy with ditto	—	0.09
	greasy with a mixture of hog's lard and molybdena	0.10	
Wrought-iron axes in cast-iron bearings		0.14	
Iron axes in brass bearings	greased with oil of olives, hog's lard, tallow, or soft gom	0.07 to 0.08	0.054
	greased with oil of olives, hog's lard, or tallow .	0.07 to 0.08	0.054
Iron axes in lignum-vitæ bearings	coated with hard gom . .	0.09	
	greasy and wetted	0.19	
Brass axes in brass bearings	scarcely greasy	0.25	
	greased with oil, or hog's lard	0.11	
Brass axes in cast-iron bearings	greasy	0.19	
	greased with oil	0.10	
Lignum-vitæ axes in ditto	with hog's lard	0.09	
	greased with oil, or tallow	—	0.045 to 0.052
Lignum-vitæ axes in lignum-vitæ bearings	greased with hog's lard .	0.12	
	greasy	0.15	
	greased with hog's lard .	—	0.07

**TABLE OF FRICTION OF PLANE SURFACES IN MOTION
ONE UPON THE OTHER.**

(From the experiments of M. Morin.)

Surfaces in Contact.	Disposition of the Fibres.	State of the Surfaces.	Co-effi- cient of Friction.
Oak upon oak	parallel	without unguent	0.48
	ditto	rubbed with dry soap	0.16
	perpendicular	without unguent	0.34
	ditto	steeped in water	0.25
	wood endways on wood length- ways	without unguent	0.19
Elm upon oak	parallel	ditto	0.43
Ash, fir, beech, wild pear-tree, and service-tree upon oak .	perpendicular	ditto	0.45
	ditto	ditto	0.36 to 0.40
		ditto	0.62
Iron upon oak	ditto	with water	0.26
		rubbed with dry soap	0.21
		without unguent	0.49
Cast-iron upon oak	ditto	with water	0.26
		rubbed with dry soap	0.19
Copper upon oak	ditto	without unguent	0.62
Iron upon elm	ditto	ditto	0.25
Cast-iron upon elm	ditto	ditto	0.20
Black dressed leather upon oak	ditto	ditto	0.27
Tanned leather upon oak . .	lengthways	ditto	0.32
		with water	0.29
		without unguent	0.56
Tanned leather upon cast-iron and brass	ditto	steeped in water	0.36
		greased and steeped in	0.23
		water with oil	0.15

Surfaces in Contact.	Disposition of the Fibres.	State of the Surfaces.	Co-effi- cient of Friction.
Hemp, in threads or in cord, upon oak	parallel { perpendicular	{ without unguent } { with water	0.52 0.88
Oak and elm upon cast-iron .	parallel {	{ without unguent }	0.88
Wild pear-tree ditto	ditto	ditto	0.44
Iron upon iron	ditto	ditto	0.44
Iron upon cast-iron and brass	ditto	ditto	0.18
Cast-iron ditto	ditto	ditto	0.15
Brass { upon brass	ditto	ditto	0.20
{ upon cast-iron	ditto	ditto	0.22
{ upon iron	ditto	ditto	0.16
Oak, elm, yoke elm, wild pear, cast-iron, wrought-iron, steel, moving one upon another, or on themselves .	ditto	{ greased in the usual way, with tallow, hog's lard, oil, or soft gom slightly greasy to the touch } { without unguent }	0.07 to 0.08 0.15 0.64
Calcareous oölite stone upon calcareous oölite	ditto	ditto	0.67
Calcareous stone, called mus- chelkalk, upon calcareous oölite	ditto	ditto	0.65
Common brick upon calcareous oölite	ditto	ditto	0.88
Oak upon calcareous oölite .	wood endways	ditto	0.69
Wrought-iron ditto	parallel	ditto	0.88
Calcareous stone, called mus- chelkalk, upon muschelkalk	ditto	ditto	0.65
Calcareous oölite stone upon muschelkalk	ditto	ditto	0.60
Common brick ditto	ditto	ditto	0.88
Oak upon muschelkalk . . .	wood endways	ditto	0.24
Iron upon muschelkalk . . .	parallel {	{ saturated with water }	0.20

INDEX.

Air pump, 73

Arago's experiments to ascertain the relation between pressure and temperature, 22

Archimedes' screw, the, 63

Atmosphere, resistance of, to the progress of the locomotive engine, 89

Axle, friction of an, 99

Blackett's improvements on the locomotive engine, 81

Boilers, 70

Height of steam dome, 70

Inside diameter of steam dome, 70

On the evaporating power of the, 13

Value of the evaporating power, 13

Inside diameter, 70

Length for locomotive engines, 70

Chimney, action of the, 93

Coal shaft, to find where the ascending and descending curves will meet, 103
To find the position of meetings in a, 102

Condenser, 72

Cranks, 98

Principles of the, 45

Cylinders, friction of, 100

Dulong's experiments to ascertain the relation between pressure and temperature, 22

Eccentric, the, 53

Wheel, to construct an, 54

Expansion, to find the work done by, without the use of logarithms, 6

Feathering screw, advantages of, 65

Field's paddle wheels described, 58

Fire-grate, area of, 70

Fluids, elastic, increased volume of, with increase of temperature, 23

Fly-wheel, purpose of, 37

To find the limits within which the angular velocity varies, the force being in one direction, 37

To find the units of work in the, and the number of revolutions before it stops, 38

Of the single-acting engine, rules and examples for, 41

Of the double-acting engine, rules and examples for, 39

Frederick's steam locomotive, 81

Gauge controversy, 83

Gay-Lussac's law for elastic fluids, 28

Governor, action of, 42

Rules and examples on the, 44

To find the distance in which the balls revolve from their point of suspension, 44

To find the radius of the circle described by the balls, 44

Griffith's screw propeller, 64

Gudgeons, 98

Table of friction of, 114

Horse power described, 3

To find the, 3

Lever of the safety valve, 34

Calculation for graduating the, 34

To graduate the, the weight of the lever being considered, 35

Load, term defined, 3

To find the, 3

Locomotive engine, 77

Action of, described, 79

Blast pipe considered, 78

Boiler described, 77

Chimney, description of, 78

Connecting rods, 78

Forcing pumps, use of, 78

Hand gear described, 78

Pistons described, 78

Side valves, use of, 77

Wheels described, 79

Number of wheels considered, 83

Weight of, 83

Patents for improvements on the, 80

Power of, considered, 89

Variable resistances to, 88

Logarithms, table of hyperbolic, 105

Mariotte's law, 1

Maudslay's feathering screw, 65

Morgan's paddle wheel with feathering floats, 59

Motion, parallel, 55

Navier's formulæ, 25

Novelty, the, described, 89

Paddle wheels, description of, 57

With oblique floats, 59

Pambour's theory of the steam engine, 20

Patents for improving the locomotive engine, 80, 82

Pipes, steam, 71

- Piston, to find the units of work done on the, in one stroke, 2
 To determine the velocity of the, when any part of the stroke is described, 17
 To find when the velocity of the, is a maximum, 19
 Work done on the, in a given time, 26
 Pivot, friction on a, 100
 Plane surfaces, table of friction of, in motion one upon another, 115
 Pole's formula on the relation between pressure and volume, 24
 Pressure, to find the, at which steam is admitted, 3
 To find the centre of, in Morgan's paddle board, 60
 Pressure and temperature, relation between, 22
- Railway, moving a train on a level, 84
 Robinson's idea of the propelling properties of steam, 80
 Rocket, the, described, 82
- Safety valves, 33, 88
 Lever of the, 34
 " calculation for graduating the, 34
 To find the pressure on the, 34
 Samuel's express engine, 83
 Sanspareil, 82
 Screw propellers, marine, 62
 Action of the, 63
 First experiments with the, 63
 Griffith's, 64
 Area of the, 65
 Diameter of the, 67
 Theory of the, 67
 Steam, discovery of the expansive power of, 1
 To find the advantage derived from working it expansively, 10
 Elastic force of, 1
 First record of its power, 80
 First use of, 80
 High pressure, advantages of using, 30
- Steam, point at which it must be cut off to obtain the greatest quantity of work, 81
 Resistances to the pressure of, in non-condensing and condensing engines, 13
 Theoretical investigation of the properties of, 17
 Volume of evaporation per minute, 15
 Steam blast, object of, 92
 Value of the, 92
 Steam dome, height and diameter of the, 70
 Steam engine, duty of the, 30
 Geometrical construction, 73
 Miscellaneous examples, 95
 Side valves of the, 72
 Stephenson's improvements on the locomotive, 81
 Rocket, 81
- Table of friction of gudgeons or axle ends in motion on their bearings, 114
 Table of the volume produced by a cubic foot of water in the form of steam at different pressures, with the corresponding temperatures, 13
 Table of hyperbolic logarithms, 105
 Tank engine described, 82
 Train moving on a level railway, 84
 Moving a, against the joint resistances of friction and gravity on an inclined plane, 86
 Tredgold's formula for pressures, 22
 Trevithick, application of steam carriages, 81
- Unit of work, 2
 In reference to the unit of time, 2
 To find the, done on the piston in one stroke, 2
 Measuring by, 2
 Useful load, to find, 12
- Watt's steam patent, 80
 Wind, the resistance of, 89
 Winding machines, 101
 Work, unit of, 2

THE PRIZE MEDAL, INTERNATIONAL EXHIBITION, 1862,
was awarded to the Publishers of
"Weale's Series."



A NEW LIST
OF
WEALE'S
**RUDIMENTARY SCIENTIFIC, EDUCATIONAL,
AND CLASSICAL SERIES.**

These popular and cheap Series of Books, now comprising nearly Three Hundred distinct works in almost every department of Science, Art, and Education, are recommended to the notice of Engineers, Architects, Builders, Artisans, and Students generally, as well as to those interested in Workmen's Libraries, Free Libraries, Literary and Scientific Institutions, Colleges, Schools, Science Classes, &c., &c.

N.B.—In ordering from this List it is recommended, as a means of facilitating business and obviating error, to quote the numbers affixed to the volumes, as well as the titles and prices.

*** The books are bound in limp cloth, unless otherwise stated.

RUDIMENTARY SCIENTIFIC SERIES.

ARCHITECTURE, BUILDING, ETC.

No.

16. **ARCHITECTURE—ORDERS**—The Orders and their Æsthetic Principles. By W. H. LEEDS. Illustrated. 1s. 6d.
17. **ARCHITECTURE—STYLES**—The History and Description of the Styles of Architecture of Various Countries, from the Earliest to the Present Period. By T. TALBOT BURY, F.R.I.B.A., &c. Illustrated. 2s.
*** **ORDERS AND STYLES OF ARCHITECTURE**, in One Vol., 3s. 6d.

18. **ARCHITECTURE—DESIGN**—The Principles of Design in Architecture, as deducible from Nature and exemplified in the Works of the Greek and Gothic Architects. By E. L. GARBETT, Architect. Illustrated. 2s.

*** *The three preceding Works, in One handsome Vol., half bound, entitled "MODERN ARCHITECTURE," Price 6s.*

22. **THE ART OF BUILDING**, Rudiments of. General Principles of Construction, Materials used in Building, Strength and Use of Materials, Working Drawings, Specifications, and Estimates. By EDWARD DOBSON, M.R.I.B.A., &c. Illustrated. 1s. 6d.

23. **BRICKS AND TILES**, Rudimentary Treatise on the Manufacture of; containing an Outline of the Principles of Brickmaking. By EDW. DOBSON, M.R.I.B.A. With Additions by C. TOMLINSON, F.R.S. Illustrated, 3s.

25. **MASONRY AND STONECUTTING**, Rudimentary Treatise on; in which the Principles of Masonic Projection and their application to the Construction of Curved Wing-Walls, Domes, Oblique Bridges, and Roman and Gothic Vaulting, are concisely explained. By EDWARD DOBSON, M.R.I.B.A., &c. Illustrated with Plates and Diagrams. 2s. 6d.

44. **FOUNDATIONS AND CONCRETE WORKS**, a Rudimentary Treatise on; containing a Synopsis of the principal cases of Foundation Works, with the usual Modes of Treatment, and Practical Remarks on Footings, Planking, Sand, Concrete, Béton, Pile-driving, Caissons, and Cofferdams. By E. DOBSON, M.R.I.B.A., &c. Fourth Edition, revised by GEORGE DODD, C.E. Illustrated. 1s. 6d.

CROSBY LOCKWOOD AND CO., 7, STATIONERS' HALL COURT, E.C.

Architecture, Building, etc., continued.

42. **COTTAGE BUILDING.** By C. BRUCE ALLEN, Architect. Eleventh Edition, revised and enlarged. Numerous Illustrations. 1s. 6d.
45. **LIMES, CEMENTS, MORTARS, CONCRETES, MASTICS PLASTERING, &c.,** Rudimentary Treatise on. By G. R. BURNELL, C.E. Ninth Edition, with Appendices. 1s. 6d.
57. **WARMING AND VENTILATION,** a Rudimentary Treatise on; being a concise Exposition of the General Principles of the Art of Warming and Ventilating Domestic and Public Buildings, Mines, Lighthouses, Ships, &c. By CHARLES TOMLINSON, F.R.S., &c. Illustrated. 3s.
- 83**. **CONSTRUCTION OF DOOR LOCKS.** Compiled from the Papers of A. C. HOBBS, Esq., of New York, and Edited by CHARLES TOMLINSON, F.R.S. To which is added, a Description of Fenby's Patent Lock and a Note upon IRON SAFES by ROBERT MALLETT, M.I.C.E. Illus. 2s. 6d.
111. **ARCHES, PIERS, BUTTRESSES, &c.:** Experimental Essay on the Principles of Construction in; made with a view to their being useful to the Practical Builder. By WILLIAM BLAND. Illustrated. 1s. 6d.
116. **THE ACOUSTICS OF PUBLIC BUILDINGS;** or, The Principles of the Science of Sound applied to the purposes of the Architect and Builder. By T. ROGER SMITH, M.R.I.B.A., Architect. Illustrated. 1s. 6d.
124. **CONSTRUCTION OF ROOFS,** Treatise on the, as regards Carpentry and Joinery. Deduced from the Works of ROBISON, PRICE, and TREDGOLD. Illustrated. 1s. 6d.
127. **ARCHITECTURAL MODELLING IN PAPER,** the Art of By T. A. RICHARDSON, Architect. With Illustrations, designed by the Author, and engraved by O. JEWITT. 1s. 6d.
128. **VITRUVIUS—THE ARCHITECTURE OF MARCUS VITRUVIUS POLLO.** In Ten Books. Translated from the Latin by JOSEPH GWILT, F.S.A., F.R.A.S. With 23 Plates. 5s.
130. **GRECIAN ARCHITECTURE,** An Inquiry into the Principles of Beauty in; with a Historical View of the Rise and Progress of the Art in Greece. By the EARL OF ABERDEEN. 1s.
- *. * *The two Preceding Works in One handsome Vol., half bound, entitled "ANCIENT ARCHITECTURE." Price 6s.*
132. **DWELLING-HOUSES,** a Rudimentary Treatise on the Erection of. By S. H. BROOKS, Architect. New Edition, with Plates. 2s. 6d.
156. **QUANTITIES AND MEASUREMENTS,** How to Calculate and Take them in Bricklayers', Masons', Plasterers', Plumbers', Painters', Paperhangers', Gilders', Smiths', Carpenters', and Joiners' Work. By A. C. BEATON, Architect and Surveyor. New and Enlarged Edition. Illus. 1s. 6d.
175. **LOCKWOOD & CO.'S BUILDER'S AND CONTRACTOR'S PRICE BOOK,** with which is incorporated ATCHLEY's and portions of the late G. R. BURNELL's "BUILDER'S PRICE BOOKS," for 1876, containing the latest Prices of all kinds of Builders' Materials and Labour, and of a Trades connected with Building: with many useful and important Memoranda and Tables; Lists of the Members of the Metropolitan Board of Works, of Districts, District Officers, and District Surveyors, and the Metropolitan Bye-laws. The whole Revised and Edited by FRANCIS J. W. MILLER, Architect and Surveyor. 3s. 6d.
182. **CARPENTRY AND JOINERY—THE ELEMENTARY PRINCIPLES OF CARPENTRY.** Chiefly composed from the Standard Work of THOMAS TREDGOLD, C.E. With Additions from the Works of the most Recent Authorities, and a TREATISE ON JOINERY by E. WYNDHAM TARN, M.A. Numerous Illustrations. 3s. 6d.
- 182*. **CARPENTRY AND JOINERY. ATLAS** of 35 Plates to accompany the foregoing book. With Descriptive Letterpress. 4to. 6s.
187. **HINTS TO YOUNG ARCHITECTS.** By GEORGE WIGHTWICK. Author of "The Palace of Architecture," &c. &c. New, Revised and enlarged Edition. By G. HUSKISSON GUILLAUME, Architect. With numerous Woodcuts. 3s. 6d. *[Just published.]*

Architecture, Building, etc., continued.**188. HOUSE PAINTING, GRAINING, MARBLING, AND SIGN**

WRITING: A Practical Manual of, containing full information on the Processes of House Painting in Oil and Distemper, the Formation of Letters and Practice of Sign Writing, the Principles of Decorative Art, a Course of Elementary Drawing for House Painters, Writers, &c., and a Collection of Useful Receipts. With 9 Coloured Plates of Woods and Marbles, and nearly 150 Wood Engravings. By ELLIS A. DAVIDSON, Author of "Building Construction," "Drawing for Carpenters," &c. 5s.

[Just published.]

189. THE RUDIMENTS OF PRACTICAL BRICKLAYING.

In Six Sections: General Principles of Bricklaying; Arch Drawing, Cutting, and Setting; different kinds of Pointing; Paving, Tiling, Materials; Slating and Plastering; Practical Geometry, Mensuration, &c. By ADAM HAMMOND. Illustrated with 68 Woodcuts. 1s. 6d.

[Just published.]

191. PLUMBING. A Text-Book to the Practice of the Art or Craft of

the Plumber. With Supplementary Chapters upon House Drainage, embodying the latest Improvements. Containing about 300 Illustrations. By WILLIAM PATON BUCHAN, Practical and Consulting Sanitary Plumber; Mem. of Coun. San. and Soc. Econ. Sec. of the Philosophical Society of Glasgow. [Nearly ready.]

192. THE TIMBER IMPORTER'S, TIMBER MERCHANT'S,

and BUILDER'S STANDARD GUIDE; comprising copious and valuable Memoranda for the Retailer and Builder. By RICHARD E. GRANDY. Second Edition, Revised. 3s.

CIVIL ENGINEERING, ETC.**13. CIVIL ENGINEERING,** the Rudiments of; for the Use of

Beginners, for Practical Engineers, and for the Army and Navy. By HENRY LAW, C.E. Including a Section on Hydraulic Engineering, by GEORGE R. BURNELL, C.E. 5th Edition, with Notes and Illustrations by ROBERT MALLETT, A.M., F.R.S. Illustrated with Plates and Diagrams. 5s.

29. THE DRAINAGE OF DISTRICTS AND LANDS. By G.

DRYSDALE DEMPSEY, C.E. New Edition, revised and enlarged. Illustrated. 1s. 6d.

30. THE DRAINAGE OF TOWNS AND BUILDINGS. By

G. DRYSDALE DEMPSEY, C.E. New Edition. Illustrated. 2s. 6d.
* * With "Drainage of Districts and Lands," in One Vol., 3s. 6d.

31. WELL-DIGGING, BORING, AND PUMP-WORK. By

JOHN GEORGE SWINDELL, Assoc. R.I.B.A. New Edition, revised by G. R. BURNELL, C.E. Illustrated. 1s. 6d.

35. THE BLASTING AND QUARRYING OF STONE, for

Building and other Purposes. With Remarks on the Blowing up of Bridges. By Gen. Sir JOHN BURGOYNE, Bart., K.C.B. Illustrated. 1s. 6d.

43. TUBULAR AND OTHER IRON GIRDER BRIDGES.

Particularly describing the BRITANNIA and CONWAY TUBULAR BRIDGES. With a Sketch of Iron Bridges, and Illustrations of the Application of Malleable Iron to the Art of Bridge Building. By G. D. DEMPSEY, C.E., New Edition, with Illustrations. 1s. 6d.

62. RAILWAY CONSTRUCTION, Elementary and Practical In-

struction on the Science of. By Sir MACDONALD STEPHENSON, C.E. New Edition, revised and enlarged by EDWARD NUGENT, C.E. Plates and numerous Woodcuts. 3s.

80*. EMBANKING LANDS FROM THE SEA, the Practice of.

Treated as a Means of Profitable Employment for Capital. With Examples and Particulars of actual Embankments, and also Practical Remarks on the Repair of old Sea Walls. By JOHN WIGGINS, F.G.S. New Edition, with Notes by ROBERT MALLETT, F.R.S. 2s.

81. WATER WORKS, for the Supply of Cities and Towns. With

a Description of the Principal Geological Formations of England as influencing Supplies of Water; and Details of Engines and Pumping Machinery for raising Water. By SAMUEL HUGHES, F.G.S., C.E. New Edition, revised and enlarged, with numerous Illustrations. 4s.

82. GAS WORKS,** and the Practice of Manufacturing and Distributing

Coal Gas. By SAMUEL HUGHES, C.E. New Edition, revised by W. RICHARDS, C.E. Illustrated. 3s. 6d.

Civil Engineering, etc., continued.

117. **SUBTERRANEAN SURVEYING**; an Elementary and Practical Treatise on. By THOMAS FENWICK. Also the Method of Conducting Subterranean Surveys without the Use of the Magnetic Needle, and other modern Improvements. By THOMAS BAKER, C.E. Illustrated. 2s. 6d.
118. **CIVIL ENGINEERING IN NORTH AMERICA**, a Sketch of. By DAVID STEVENSON, F.R.S.E., &c. Plates and Diagrams. 3s.
121. **RIVERS AND TORRENTS**. With the Method of Regulating their Courses and Channels. By Professor PAUL FRISI, F.R.S., of Milan. To which is added, AN ESSAY ON NAVIGABLE CANALS. Translated by Major-General JOHN GARSTIN, of the Bengal Engineers. Plates. 2s. 6d.

MECHANICAL ENGINEERING, ETC.

33. **CRANES**, the Construction of, and other Machinery for Raising Heavy Bodies for the Erection of Buildings, and for Hoisting Goods. By JOSEPH GLYNN, F.R.S., &c. Illustrated. 1s. 6d.
34. **THE STEAM ENGINE**, a Rudimentary Treatise on. By Dr. LARDNER. Illustrated. 7s. 6d.
59. **STEAM BOILERS**: their Construction and Management. By R. ARMSTRONG, C.E. Illustrated. 1s. 6d.
63. **AGRICULTURAL ENGINEERING**: Farm Buildings, Motive Power, Field Machines, Machinery, and Implements. By G. H. ANDREWS, C.E. Illustrated. 3s.
67. **CLOCKS, WATCHES, AND BELLS**, a Rudimentary Treatise on. By Sir EDMUND BECKETT (late EDMUND BECKETT DENISON, LL.D., Q.C.) A new, Revised, and considerably Enlarged Edition (the 6th), with very numerous Illustrations. 4s. 6d. [Just published.]
- 77*. **THE ECONOMY OF FUEL**, particularly with Reference to Reverberatory Furnaces for the Manufacture of Iron, and to Steam Boilers. By T. SYMES PRIDEAUX. 1s. 6d.
82. **THE POWER OF WATER**, as applied to drive Flour Mills, and to give motion to Turbines and other Hydrostatic Engines. By JOSEPH GLYNN, F.R.S., &c. New Edition, Illustrated. 2s.
98. **PRACTICAL MECHANISM**, the Elements of; and Machine Tools. By T. BAKER, C.E. With Remarks on Tools and Machinery, by J. NASMYTH, C.E. Plates. 2s. 6d.
114. **MACHINERY**, Elementary Principles of, in its Construction and Working. Illustrated by numerous Examples of Modern Machinery for different Branches of Manufacture. By C. D. ABEL, C.E. 1s. 6d.
115. **ATLAS OF PLATES**. Illustrating the above Treatise. By C. D. ABEL, C.E. 7s. 6d.
125. **THE COMBUSTION OF COAL AND THE PREVENTION OF SMOKE**, Chemically and Practically Considered. With an Appendix. By C. WYE WILLIAMS, A.I.C.E. Plates. 3s.
139. **THE STEAM ENGINE**, a Treatise on the Mathematical Theory of, with Rules at length, and Examples for the Use of Practical Men. By T. BAKER, C.E. Illustrated. 1s. 6d.
162. **THE BRASS FOUNDER'S MANUAL**; Instructions for Modelling, Pattern-Making, Moulding, Turning, Filing, Burnishing, Bronzing, &c. With copious Receipts, numerous Tables, and Notes on Prime Costs and Estimates. By WALTER GRAHAM. Illustrated. 2s. 6d.
164. **MODERN WORKSHOP PRACTICE**, as applied to Marine, Land, and Locomotive Engines, Floating Docks, Dredging Machines, Bridges, Cranes, Ship-building, &c., &c. By J. G. WINTON. Illustrated. 3s.
165. **IRON AND HEAT**, exhibiting the Principles concerned in the Construction of Iron Beams, Pillars, and Bridge Girders, and the Action of Heat in the Smelting Furnace. By J. ARMOUR, C.E. 2s. 6d.

Mechanical Engineering, etc., continued.

166. *POWER IN MOTION: Horse-Power, Motion, Toothed-Wheel Gearing, Long and Short Driving Bands, Angular Forces.* By JAMES ARMOUR, C.E. With 73 Diagrams. 2s. 6d.
167. *THE APPLICATION OF IRON TO THE CONSTRUCTION OF BRIDGES, GIRDERS, ROOFS, AND OTHER WORKS.* Showing the Principles upon which such Structures are designed, and their Practical Application. By FRANCIS CAMPIN, C.E. Numerous Woodcuts. 2s.
171. *THE WORKMAN'S MANUAL OF ENGINEERING DRAWING.* By JOHN MAXTON, Engineer, Instructor in Engineering Drawing, Royal Naval College, Greenwich, formerly of R.S.N.A., South Kensington. Third Edition. Illustrated with 7 Plates and nearly 350 Woodcuts. 3s. 6d.
190. *STEAM AND THE STEAM ENGINE, Stationary and Portable.* An elementary treatise on. Being an extension of Mr. John Sewell's "Treatise on Steam." By D. KINNAR CLARK, C.E., M.I.C.E. Author of "Railway Machinery," "Railway Locomotives," &c., &c. With numerous Illustrations. 3s. 6d. [Just ready.]

SHIPBUILDING, NAVIGATION, MARINE ENGINEERING, ETC.

51. *NAVAL ARCHITECTURE, the Rudiments of; or, an Exposition of the Elementary Principles of the Science, and their Practical Application to Naval Construction.* Compiled for the Use of Beginners. By JAMES PRAKE, School of Naval Architecture, H.M. Dockyard, Portsmouth. Fourth Edition, corrected, with Plates and Diagrams. 3s. 6d.
- 53*. *SHIPS FOR OCEAN AND RIVER SERVICE, Elementary and Practical Principles of the Construction of.* By HAKON A. SOMMERFELDT, Surveyor of the Royal Norwegian Navy. With an Appendix. 1s.
- 53**. *AN ATLAS OF ENGRAVINGS to Illustrate the above.* Twelve large folding plates. Royal 4to, cloth. 7s. 6d.
54. *MASTING, MAST-MAKING, AND RIGGING OF SHIPS, Rudimentary Treatise on.* Also Tables of Spars, Rigging, Blocks; Chain, Wire, and Hemp Ropes, &c., relative to every class of vessels. Together with an Appendix of Dimensions of Masts and Yards of the Royal Navy of Great Britain and Ireland. By ROBERT KIPPING, N.A. Thirteenth Edition. Illustrated. 1s. 6d.
- 54*. *IRON SHIP-BUILDING.* With Practical Examples and Details for the Use of Ship Owners and Ship Builders. By JOHN GRANTHAM, Consulting Engineer and Naval Architect. Fifth Edition, with important Additions. 4s.
- 54**. *AN ATLAS OF FORTY PLATES to Illustrate the above.* Fifth Edition. Including the latest Examples, such as H.M. Steam Frigates "Warrior," "Hercules," "Bellerophon;" H.M. Troop Ship "Serapis," Iron Floating Dock, &c., &c. 4to, boards. 38s.
55. *THE SAILOR'S SEA BOOK: a Rudimentary Treatise on Navigation.* I. How to Keep the Log and Work it off. II. On Finding the Latitude and Longitude. By JAMES GREENWOOD, B.A., of Jesus College, Cambridge. To which are added, Directions for Great Circle Sailing; an Essay on the Law of Storms and Variable Winds; and Explanations of Terms used in Ship-building. Ninth Edition, with several Engravings and Coloured Illustrations of the Flags of Maritime Nations. 2s.
80. *MARINE ENGINES, AND STEAM VESSELS, a Treatise on.* Together with Practical Remarks on the Screw and Propelling Power, as used in the Royal and Merchant Navy. By ROBERT MURRAY, C.E., Engineer-Surveyor to the Board of Trade. With a Glossary of Technical Terms, and their Equivalents in French, German, and Spanish. Fifth Edition, revised and enlarged. Illustrated. 3s.

Shipbuilding, Navigation, etc., continued.

- 83bis. **THE FORMS OF SHIPS AND BOATS**: Hints, Experimentally Derived, on some of the Principles regulating Ship-building. By W. BLAND. Sixth Edition, revised, with numerous Illustrations and Models. 1s. 6d.
99. **NAVIGATION AND NAUTICAL ASTRONOMY**, in Theory and Practice. With Attempts to facilitate the Finding of the Time and the Longitude at Sea. By J. R. YOUNG, formerly Professor of Mathematics in Belfast College. Illustrated. 2s. 6d.
- 100*. **TABLES** intended to facilitate the Operations of Navigation and Nautical Astronomy, as an Accompaniment to the above Book. By J. R. YOUNG. 1s. 6d.
106. **SHIPS' ANCHORS**, a Treatise on. By GEORGE COTSELL, N.A. Illustrated. 1s. 6d.
149. **SAILS AND SAIL-MAKING**, an Elementary Treatise on. With Draughting, and the Centre of Effort of the Sails. Also, Weights and Sizes of Ropes; Mastng, Riggng, and Sails of Steam Vessels, &c., &c. Tenth Edition, enlarged, with an Appendix. By ROBERT KIPPING, N.A., Sailmaker, Quayside, Newcastle. Illustrated. 2s. 6d.
155. **THE ENGINEER'S GUIDE TO THE ROYAL AND MERCANTILE NAVIES**. By a PRACTICAL ENGINEER. Revised by D. F. M'CARTHY, late of the Ordnance Survey Office, Southampton. 3s.

PHYSICAL SCIENCE, NATURAL PHILOSOPHY, ETC.

1. **CHEMISTRY**, for the Use of Beginners. By Professor GEORGE FOWNES, F.R.S. With an Appendix, on the Application of Chemistry to Agriculture. 1s.
2. **NATURAL PHILOSOPHY**, Introduction to the Study of; for the Use of Beginners. By C. TOMLINSON, Lecturer on Natural Science in King's College School, London. Woodcuts. 1s. 6d.
4. **MINERALOGY**, Rudiments of; a concise View of the Properties of Minerals. By A. RAMSAY, Jun. Woodcuts and Steel Plates. 3s.
6. **MECHANICS**, Rudimentary Treatise on; being a concise Exposition of the General Principles of Mechanical Science, and their Applications. By CHARLES TOMLINSON, Lecturer on Natural Science in King's College School, London. Illustrated. 1s. 6d.
7. **ELECTRICITY**; showing the General Principles of Electrical Science, and the purposes to which it has been applied. By Sir W. SNOW HARRIS, F.R.S., &c. With considerable Additions by R. SABINE, C.E., F.S.A. Woodcuts. 1s. 6d.
- 7*. **GALVANISM**, Rudimentary Treatise on, and the General Principles of Animal and Voltaic Electricity. By Sir W. SNOW HARRIS. New Edition, revised, with considerable Additions, by ROBERT SABINE, C.E., F.S.A. Woodcuts. 1s. 6d.
8. **MAGNETISM**; being a concise Exposition of the General Principles of Magnetical Science, and the Purposes to which it has been applied. By Sir W. SNOW HARRIS. New Edition, revised and enlarged by H. M. NOAD, Ph.D., Vice-President of the Chemical Society, Author of "A Manual of Electricity," &c., &c. With 165 Woodcuts. 3s. 6d.
11. **THE ELECTRIC TELEGRAPH**; its History and Progress; with Descriptions of some of the Apparatus. By R. SABINE, C.E., F.S.A., &c. Woodcuts. 3s.
12. **PNEUMATICS**, for the Use of Beginners. By CHARLES TOMLINSON. Illustrated. 1s. 6d.
72. **MANUAL OF THE MOLLUSCA**; a Treatise on Recent and Fossil Shells. By Dr. S. P. WOODWARD, A.L.S. With Appendix by RALPH TATE, A.L.S., F.G.S. With numerous Plates and 300 Woodcuts, 6s. 6d. Cloth boards, 7s. 6d.

Physical Science, Natural Philosophy, etc., continued.

- 79**. **PHOTOGRAPHY**, Popular Treatise on; with a Description of the Stereoscope, &c. Translated from the French of D. VAN MONCKHOVEN, by W. H. THORNTWHAITE, Ph.D. Woodcuts. 1s. 6d.
96. **ASTRONOMY**. By the Rev. R. MAIN, M.A., F.R.S., &c. New and enlarged Edition, with an Appendix on "Spectrum Analysis." Woodcuts. 1s. 6d.
97. **STATICS AND DYNAMICS**, the Principles and Practice of; embracing also a clear development of Hydrostatics, Hydrodynamics, and Central Forces. By T. BAKER, C.E. 1s. 6d.
138. **TELEGRAPH**, Handbook of the; a Manual of Telegraphy, Telegraph Clerks' Remembrancer, and Guide to Candidates for Employment in the Telegraph Service. By R. BOND. Fourth Edition, revised and enlarged: to which is appended, QUESTIONS on MAGNETISM, ELECTRICITY, and PRACTICAL TELEGRAPHY, for the Use of Students, by W. MCGREGOR, First Assistant Superintendent, Indian Gov. Telegraphs. Woodcuts. 3s.
143. **EXPERIMENTAL ESSAYS**. By CHARLES TOMLINSON. I. On the Motions of Camphor on Water. II. On the Motion of Camphor towards the Light. III. History of the Modern Theory of Dew. Woodcuts. 1s.
173. **PHYSICAL GEOLOGY**, partly based on Major-General PORTLOCK's "Rudiments of Geology." By RALPH TATE, A.L.S., &c. Numerous Woodcuts. 2s.
174. **HISTORICAL GEOLOGY**, partly based on Major-General PORTLOCK's "Rudiments." By RALPH TATE, A.L.S., &c. Woodcuts. 2s. 6d.
173. **RUDIMENTARY TREATISE ON GEOLOGY**, Physical and & Historical. Partly based on Major-General PORTLOCK's "Rudiments of Geology." By RALPH TATE, A.L.S., F.G.S., &c., &c. Numerous Illustrations. In One Volume. 4s. 6d.
174. **ANIMAL PHYSICS**, Handbook of. By DIONYSIUS LARDNER, & D.C.L., formerly Professor of Natural Philosophy and Astronomy in University College, London. With 520 Illustrations. In One Volume, cloth boards. 7s. 6d.

* * Sold also in Two Parts, as follows :—

183. **ANIMAL PHYSICS**. By Dr. LARDNER. Part I., Chapter I—VII. 4s.
184. **ANIMAL PHYSICS**. By Dr. LARDNER. Part II. Chapter VIII—XVIII. 3s.

MINING, METALLURGY, ETC.

117. **SUBTERRANEAN SURVEYING**, Elementary and Practical Treatise on, with and without the Magnetic Needle. By THOMAS FENWICK, Surveyor of Mines, and THOMAS BAKER, C.E. Illustrated. 2s. 6d.
133. **METALLURGY OF COPPER**; an Introduction to the Methods of Seeking, Mining, and Assaying Copper, and Manufacturing its Alloys. By ROBERT H. LAMBORN, Ph.D. Woodcuts. 2s. 6d.
134. **METALLURGY OF SILVER AND LEAD**. A Description of the Ores; their Assay and Treatment, and valuable Constituents. By Dr. R. H. LAMBORN. Woodcuts. 2s.
135. **ELECTRO-METALLURGY**; Practically Treated. By ALEXANDER WATT, F.R.S.S.A. New Edition. Woodcuts. 2s.
172. **MINING TOOLS**, Manual of. For the Use of Mine Managers, Agents, Students, &c. Comprising Observations on the Materials from, and Processes by which they are manufactured; their Special Uses, Applications, Qualities, and Efficiency. By WILLIAM MORGANS, Lecturer on Mining at the Bristol School of Mines. 2s. 6d.
- 172*. **MINING TOOLS, ATLAS** of Engravings to Illustrate the above, containing 235 Illustrations of Mining Tools, drawn to Scale. 4to. 4s. 6d.

Mining, Metallurgy, etc., continued.

176. **METALLURGY OF IRON**, a Treatise on the. Containing Outlines of the History of Iron Manufacture, Methods of Assay, and Analyses of Iron Ores, Processes of Manufacture of Iron and Steel, &c. By H. BAUERMAN, F.G.S., Associate of the Royal School of Mines. Fourth Edition, revised and enlarged, with numerous Illustrations. 4s. 6d.
180. **COAL AND COAL MINING: A Rudimentary Treatise on.** By WARINGTON W. SMYTH, M.A., F.R.S., &c., Chief Inspector of the Mines of the Crown and of the Duchy of Cornwall. New Edition, revised and corrected. With numerous Illustrations. 3s. 6d.

EMIGRATION.

154. **GENERAL HINTS TO EMIGRANTS.** Containing Notices of the various Fields for Emigration. With Hints on Preparation for Emigrating, Outfits, &c., &c. With Directions and Recipes useful to the Emigrant. With a Map of the World. 2s.
157. **THE EMIGRANT'S GUIDE TO NATAL.** By ROBERT JAMES MANN, F.R.A.S., F.M.S. Second Edition, carefully corrected to the present Date. Map. 2s.
159. **THE EMIGRANT'S GUIDE TO AUSTRALIA**, *New South Wales, Western Australia, South Australia, Victoria, and Queensland.* By the Rev. JAMES BAIRD, B.A. Map. 2s. 6d.
160. **THE EMIGRANT'S GUIDE TO TASMANIA and NEW ZEALAND.** By the Rev. JAMES BAIRD, B.A. With a Map. 2s.
- 159 & 160. **THE EMIGRANT'S GUIDE TO AUSTRALASIA.** By the Rev. J. BAIRD, B.A. Comprising the above two volumes, 12mo, cloth boards. With Maps of Australia and New Zealand. 5s.

AGRICULTURE.

29. **THE DRAINAGE OF DISTRICTS AND LANDS.** By G. DRYSDALE DEMPSEY, C.E. Illustrated. 1s. 6d.
. With "*Drainage of Towns and Buildings*," in One Vol., 3s. 6d.
63. **AGRICULTURAL ENGINEERING: Farm Buildings, Motive Powers and Machinery of the Steading, Field Machines, and Implements.** By G. H. ANDREWS, C.E. Illustrated. 3s.
66. **CLAY LANDS AND LOAMY SOILS.** By Professor DONALDSON. 1s.
131. **MILLER'S, MERCHANT'S, AND FARMER'S READY RECKONER**, for ascertaining at sight the value of any quantity of Corn, from One Bushel to One Hundred Quarters, at any given price, from £1 to £5 per quarter. Together with the approximate values of Millstones and Millwork, &c. 1s.
140. **SOILS, MANURES, AND CROPS.** (Vol. 1. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. Woodcuts. 2s.
141. **FARMING AND FARMING ECONOMY**, Notes, Historical and Practical, on. (Vol. 2. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. Woodcuts. 3s.
142. **STOCK; CATTLE, SHEEP, AND HORSES.** (Vol. 3. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. Woodcuts. 2s. 6d.
145. **DAIRY, PIGS, AND POULTRY**, Management of the. By R. SCOTT BURN. With Notes on the Diseases of Stock. (Vol. 4. OUTLINES OF MODERN FARMING.) Woodcuts. 2s.
146. **UTILIZATION OF SEWAGE, IRRIGATION, AND RECLAMATION OF WASTE LAND.** (Vol. 5. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. Woodcuts. 2s. 6d.
- *.* Nos. 140-1-2-5-6, in One Vol., handsomely half-bound, entitled "**OUTLINES OF MODERN FARMING.**" By ROBERT SCOTT BURN. Price 12s.
177. **FRUIT TREES**, The Scientific and Profitable Culture of. From the French of DU BREUIL, Revised by GEO. GLENNY. 187 Woodcuts. 3s. 6d.

LONDON: CROSBY LOCKWOOD AND CO.,

FINE ARTS.

20. **PERSPECTIVE FOR BEGINNERS.** Adapted to Young Students and Amateurs in Architecture, Painting, &c. By GEORGE PYNE, Artist. Woodcuts. 2s.
40. **GLASS STAINING;** or, Painting on Glass, The Art of. Comprising Directions for Preparing the Pigments and Fluxes, laying them upon the Glass, and Firing or Burning in the Colours. From the German of Dr. GESSERT. To which is added, an Appendix on THE ART OF ENAMELLING, &c. 1s.
41. **PAINTING ON GLASS,** the Art of. From the German of EMANUEL OTTO FROMBERG. 1s.
69. **MUSIC,** A Rudimentary and Practical Treatise on. With numerous Examples. By CHARLES CHILD SPENCER. 2s. 6d.
71. **PIANOFORTE,** The Art of Playing the. With numerous Exercises and Lessons. Written and Selected from the Best Masters, by CHARLES CHILD SPENCER. 1s. 6d.
181. **PAINTING POPULARLY EXPLAINED,** including Fresco, Oil, Mosaic, Water Colour, Water-Glass, Tempera, Encaustic, Miniature, Painting on Ivory, Vellum, Pottery, Enamel, Glass, &c. With Historical Sketches of the Progress of the Art by THOMAS JOHN GULLICK, assisted by JOHN TIMBS, F.S.A. Third Edition, revised and enlarged, with Frontispiece and Vignette. 5s.
186. **A GRAMMAR OF COLOURING,** applied to Decorative Painting and the Arts. By GEORGE FIELD. New Edition, enlarged and adapted to the Use of the Ornamental Painter and Designer. By ELLIS A. DAVIDSON, Author of "Drawing for Carpenters," &c. With two new Coloured Diagrams and numerous Engravings on Wood. 2s. 6d.

ARITHMETIC, GEOMETRY, MATHEMATICS, ETC.

32. **MATHEMATICAL INSTRUMENTS,** a Treatise on; in which their Construction and the Methods of Testing, Adjusting, and Using them are concisely Explained. By J. F. HEATHER, M.A., of the Royal Military Academy, Woolwich. Original Edition, in 1 vol., Illustrated. 1s. 6d.
- In ordering the above, be careful to say, "Original Edition," or give the number in the Series (32) to distinguish it from the Enlarged Edition in 3 vols. (Nos. 168-9-70.)
60. **LAND AND ENGINEERING SURVEYING,** a Treatise on; with all the Modern Improvements. Arranged for the Use of Schools and Private Students; also for Practical Land Surveyors and Engineers. By T. BAKER, C.E. New Edition, revised by EDWARD NUGENT, C.E. Illustrated with Plates and Diagrams. 2s.
- 61*. **READY RECKONER FOR THE ADMEASUREMENT OF LAND.** By ABRAHAM ARMAN, Schoolmaster, Thurleigh, Beds. To which is added a Table, showing the Price of Work, from 2s. 6d. to £1 per acre, and Tables for the Valuation of Land, from 1s. to £1,000 per acre, and from one pole to two thousand acres in extent, &c., &c. 1s. 6d.
76. **DESCRIPTIVE GEOMETRY,** an Elementary Treatise on; with a Theory of Shadows and of Perspective, extracted from the French of G. MONGE. To which is added, a description of the Principles and Practice of Isometrical Projection; the whole being intended as an introduction to the Application of Descriptive Geometry to various branches of the Arts. By J. F. HEATHER, M.A. Illustrated with 14 Plates. 2s.
178. **PRACTICAL PLANE GEOMETRY:** giving the Simplest Modes of Constructing Figures contained in one Plane and Geometrical Construction of the Ground. By J. F. HEATHER, M.A. With 215 Woodcuts. 2s.
179. **PROJECTION:** Orthographic, Topographic, and Perspective: giving the various Modes of Delineating Solid Forms by Constructions on a Single Plane Surface. By J. F. HEATHER, M.A. [In preparation.]
- The above three volumes will form a COMPLETE ELEMENTARY COURSE OF MATHEMATICAL DRAWING.

Arithmetic, Geometry, Mathematics, etc., continued.

83. **COMMERCIAL BOOK-KEEPING.** With Commercial Phrases and Forms in English, French, Italian, and German. By JAMES HADDON, M.A., Arithmetical Master of King's College School, London. 1s.
 84. **ARITHMETIC,** a Rudimentary Treatise on: with full Explanations of its Theoretical Principles, and numerous Examples for Practice. For the Use of Schools and for Self-Instruction. By J. R. YOUNG, late Professor of Mathematics in Belfast College. New Edition, with Index. 1s. 6d.
 - 84* A KEY to the above, containing Solutions in full to the Exercises, together with Comments, Explanations, and Improved Processes, for the Use of Teachers and Unassisted Learners. By J. R. YOUNG. 1s. 6d.
 85. **EQUATIONAL ARITHMETIC,** applied to Questions of Interest,
 - 85*. Annuities, Life Assurance, and General Commerce; with various Tables by which all Calculations may be greatly facilitated. By W. HIPSLEY. 2s.
 86. **ALGEBRA,** the Elements of. By JAMES HADDON, M.A., Second Mathematical Master of King's College School. With Appendix, containing miscellaneous Investigations, and a Collection of Problems in various parts of Algebra. 2s.
 - 86* A KEY AND COMPANION to the above Book, forming an extensive repository of Solved Examples and Problems in Illustration of the various Expedients necessary in Algebraical Operations. Especially adapted for Self-Instruction. By J. R. YOUNG. 1s. 6d.
 88. **EUCLID, THE ELEMENTS OF:** with many additional Propositions
 89. and Explanatory Notes: to which is prefixed, an Introductory Essay on Logic. By HENRY LAW, C.E. 2s. 6d.
 - *.* Sold also separately, viz. :—
 88. EUCLID, The First Three Books. By HENRY LAW, C.E. 1s.
 89. EUCLID, Books 4, 5, 6, 11, 12. By HENRY LAW, C.E. 1s. 6d.
 90. **ANALYTICAL GEOMETRY AND CONIC SECTIONS,** a Rudimentary Treatise on. By JAMES HANN, late Mathematical Master of King's College School, London. A New Edition, re-written and enlarged by J. R. YOUNG, formerly Professor of Mathematics at Belfast College. 2s.
 91. **PLANE TRIGONOMETRY,** the Elements of. By JAMES HANN, formerly Mathematical Master of King's College, London. 1s.
 92. **SPHERICAL TRIGONOMETRY,** the Elements of. By JAMES HANN. Revised by CHARLES H. DOWLING, C.E. 1s.
 - *.* Or with "The Elements of Plane Trigonometry," in One Volume, 2s.
 93. **MENSURATION AND MEASURING,** for Students and Practical Use. With the Mensuration and Levelling of Land for the Purposes of Modern Engineering. By T. BAKER, C.E. New Edition, with Corrections and Additions by E. NUGENT, C.E. Illustrated. 1s. 6d.
 94. **LOGARITHMS,** a Treatise on; with Mathematical Tables for facilitating Astronomical, Nautical, Trigonometrical, and Logarithmic Calculations; Tables of Natural Sines and Tangents and Natural Cosines. By HENRY LAW, C.E. Illustrated. 2s. 6d.
 - 101*. **MEASURES, WEIGHTS, AND MONEYS OF ALL NATIONS,** and an Analysis of the Christian, Hebrew, and Mahometan Calendars. By W. S. B. WOOLHOUSE, F.R.A.S., &c. 1s. 6d.
 102. **INTEGRAL CALCULUS,** Rudimentary Treatise on the. By HOMERSHAM COX, B.A. Illustrated. 1s.
 103. **INTEGRAL CALCULUS,** Examples on the. By JAMES HANN, late of King's College, London. Illustrated. 1s.
 101. **DIFFERENTIAL CALCULUS,** Examples of the. By W. S. B. WOOLHOUSE, F.R.A.S., &c. 1s. 6d.
 104. **DIFFERENTIAL CALCULUS,** Examples and Solutions of the. By JAMES HADDON, M.A. 1s.
-

Arithmetic, Geometry, Mathematics, etc., continued.

105. **MNEMONICAL LESSONS.**—GEOMETRY, ALGEBRA, AND TRIGONOMETRY, in Easy Mnemonical Lessons. By the Rev. THOMAS PENYNGTON KIRKMAN, M.A. 1s. 6d.
136. **ARITHMETIC**, Rudimentary, for the Use of Schools and Self-Instruction. By JAMES HADDON, M.A. Revised by ABRAHAM ARMAN. 1s. 6d.
137. A KEY TO HADDON'S RUDIMENTARY ARITHMETIC. By A. ARMAN. 1s. 6d.
147. **ARITHMETIC**, STEPPING-STONE TO; being a Complete Course of Exercises in the First Four Rules (Simple and Compound), on an entirely new principle. For the Use of Elementary Schools of every Grade. Intended as an Introduction to the more extended works on Arithmetic. By ABRAHAM ARMAN. 1s.
148. A KEY TO STEPPING-STONE TO ARITHMETIC. By A. ARMAN. 1s.
158. **THE SLIDE RULE, AND HOW TO USE IT**; containing full, easy, and simple Instructions to perform all Business Calculations with unexampled rapidity and accuracy. By CHARLES HOARE, C.E. With a Slide Rule in tuck of cover. 3s.
168. **DRAWING AND MEASURING INSTRUMENTS.** Including—I. Instruments employed in Geometrical and Mechanical Drawing, and in the Construction, Copying, and Measurement of Maps and Plans. II. Instruments used for the purposes of Accurate Measurement, and for Arithmetical Computations. By J. F. HEATHER, M.A., late of the Royal Military Academy, Woolwich, Author of "Descriptive Geometry," &c., &c. Illustrated. 1s. 6d.
169. **OPTICAL INSTRUMENTS.** Including (more especially) Telescopes, Microscopes, and Apparatus for producing copies of Maps and Plans by Photography. By J. F. HEATHER, M.A. Illustrated. 1s. 6d.
170. **SURVEYING AND ASTRONOMICAL INSTRUMENTS.** Including—I. Instruments Used for Determining the Geometrical Features of a portion of Ground. II. Instruments Employed in Astronomical Observations. By J. F. HEATHER, M.A. Illustrated. 1s. 6d.
- * The above three volumes form an enlargement of the Author's original work, "Mathematical Instruments: their Construction, Adjustment, Testing, and Use," the Eleventh Edition of which is on sale, price 1s. 6d. (See No. 32 in the Series.)
168. } **MATHEMATICAL INSTRUMENTS.** By J. F. HEATHER,
169. } M.A. Enlarged Edition, for the most part entirely re-written. The 3 Parts as
170. } above, in One thick Volume. With numerous Illustrations. Cloth boards. 5s.
185. **THE COMPLETE MEASURER**; setting forth the Measurement of Boards, Glass, &c., &c.; Unequal-sided, Square-sided, Octagonal-sided, Round Timber and Stone, and Standing Timber. With just Allowances for the Bark in the respective species of Trees, and proper deductions for the waste in hewing the trees, &c.; also a Table showing the solidity of hewn or eight-sided timber, or of any octagonal-sided column. Compiled for the accommodation of Timber-growers, Merchants, and Surveyors, Stonemasons, Architects, and others. By RICHARD HORTON. Third Edition, with considerable and valuable additions. 4s. [*Just published.*]

LEGAL TREATISES.

50. **THE LAW OF CONTRACTS FOR WORKS AND SERVICES.** By DAVID GIBBONS. Third Edition, revised and considerably enlarged. 3s. [*Just published.*]
151. **A HANDY BOOK ON THE LAW OF FRIENDLY, INDUSTRIAL & PROVIDENT BUILDING & LOAN SOCIETIES.** With copious Notes. By NATHANIEL WHITE, of H.M. Civil Service. 1s.
163. **THE LAW OF PATENTS FOR INVENTIONS**; and on the Protection of Designs and Trade Marks. By F. W. CAMPIN, Barrister-at-Law. 2s.

MISCELLANEOUS VOLUMES.

36. *A DICTIONARY OF TERMS used in ARCHITECTURE, BUILDING, ENGINEERING, MINING, METALLURGY, ARCHÆOLOGY, the FINE ARTS, &c.* With Explanatory Observations on various Subjects connected with Applied Science and Art. By JOHN WEALE. Fourth Edition, with numerous Additions. Edited by ROBERT HUNT, F.R.S., Keeper of Mining Records, Editor of Ure's "Dictionary of Arts, Manufactures, and Mines." Numerous Illustrations. 5s.
112. *MANUAL OF DOMESTIC MEDICINE.* By R. GOODING, B.A., M.B. Intended as a Family Guide in all Cases of Accident and Emergency. 2s.
- 112*. *MANAGEMENT OF HEALTH.* A Manual of Home and Personal Hygiene. By the Rev. JAMES BAIRD, B.A. 1s.
113. *FIELD ARTILLERY ON SERVICE,* on the Use of. With especial Reference to that of an Army Corps. For Officers of all Arms. By TAUBERT, Captain, Prussian Artillery. Translated from the German by Lieut.-Col. HENRY HAMILTON MAXWELL, Bengal Artillery. 1s. 6d.
- 113*. *SWORDS, AND OTHER ARMS* used for Cutting and Thrusting, Memoir on. By Colonel MAREY. Translated from the French by Colonel H. H. MAXWELL. With Notes and Plates. 1s.
150. *LOGIC,* Pure and Applied. By S. H. EMMENS. Third Edition. 1s. 6d.
152. *PRACTICAL HINTS FOR INVESTING MONEY.* With an Explanation of the Mode of Transacting Business on the Stock Exchange. By FRANCIS PLAYFORD, Sworn Broker. 1s. 6d.
153. *SELECTIONS FROM LOCKE'S ESSAYS ON THE HUMAN UNDERSTANDING.* With Notes by S. H. EMMENS. 2s.
193. *HANDBOOK OF FIELD FORTIFICATION,* intended for the Guidance of Officers Preparing for Promotion, and especially adapted to the requirements of Beginners. By Major W. W. KNOLLYS, F.R.G.S., 93rd Sutherland Highlanders, &c. With 163 Woodcuts. 3s.

EDUCATIONAL AND CLASSICAL SERIES.

HISTORY.

1. *England, Outlines of the History of;* more especially with reference to the Origin and Progress of the English Constitution. A Text Book for Schools and Colleges. By WILLIAM DOUGLAS HAMILTON, F.S.A., of Her Majesty's Public Record Office. Fourth Edition, revised and brought down to 1872. Maps and Woodcuts. 5s.; cloth boards, 6s.
5. *Greece, Outlines of the History of;* in connection with the Rise of the Arts and Civilization in Europe. By W. DOUGLAS HAMILTON, of University College, London, and EDWARD LEVIEN, M.A., of Balliol College, Oxford. 2s. 6d.; cloth boards, 3s. 6d.
7. *Rome, Outlines of the History of;* from the Earliest Period to the Christian Era and the Commencement of the Decline of the Empire. By EDWARD LEVIEN, of Balliol College, Oxford. Map, 2s. 6d.; cl. bds. 3s. 6d.
9. *Chronology of History, Art, Literature, and Progress,* from the Creation of the World to the Conclusion of the Franco-German War. The Continuation by W. D. HAMILTON, F.S.A., of Her Majesty's Record Office. 3s.; cloth boards, 3s. 6d.
50. *Dates and Events in English History,* for the use of Candidates in Public and Private Examinations. By the Rev. EDGAR RAND, B.A. 1s.

ENGLISH LANGUAGE AND MISCELLANEOUS.

11. **Grammar of the English Tongue, Spoken and Written.** With an Introduction to the Study of Comparative Philology. By HYDE CLARKE, D.C.L. Third Edition. 1s.
- 11*. **Philology: Handbook of the Comparative Philology of English, Anglo-Saxon, Frisian, Flemish or Dutch, Low or Platt Dutch, High Dutch or German, Danish, Swedish, Icelandic, Latin, Italian, French, Spanish, and Portuguese Tongues.** By HYDE CLARKE, D.C.L. 1s.
12. **Dictionary of the English Language, as Spoken and Written.** Containing above 100,000 Words. By HYDE CLARKE, D.C.L. 3s. 6d.; cloth boards, 4s. 6d.; complete with the GRAMMAR, cloth bds., 5s. 6d.
48. **Composition and Punctuation, familiarly Explained for those who have neglected the Study of Grammar.** By JUSTIN BRENNAN. 16th Edition. 1s.
49. **Derivative Spelling-Book: Giving the Origin of Every Word from the Greek, Latin, Saxon, German, Teutonic, Dutch, French, Spanish, and other Languages; with their present Acception and Pronunciation.** By J. ROWBOTHAM, F.R.A.S. Improved Edition. 1s. 6d.
51. **The Art of Extempore Speaking: Hints for the Pulpit, the Senate, and the Bar.** By M. BAUTAIN, Vicar-General and Professor at the Sorbonne. Translated from the French. Fifth Edition, carefully corrected. 2s. 6d.
52. **Mining and Quarrying, with the Sciences connected therewith.** First Book of, for Schools. By J. H. COLLINS, F.G.S., Lecturer to the Miners' Association of Cornwall and Devon. 1s. 6d.
53. **Places and Facts in Political and Physical Geography, for Candidates in Public and Private Examinations.** By the Rev. EDGAR RAND, B.A. 1s.
54. **Analytical Chemistry, Qualitative and Quantitative, a Course of.** To which is prefixed, a Brief Treatise upon Modern Chemical Nomenclature and Notation. By WM. W. PINK, Practical Chemist, &c., and GEORGE E. WEBSTER, Lecturer on Metallurgy and the Applied Sciences, Nottingham. 2s.

THE SCHOOL MANAGERS' SERIES OF READING BOOKS,

Adapted to the Requirements of the New Code. Edited by the Rev. A. R. GRANT, Rector of Hitcham, and Honorary Canon of Ely; formerly H.M. Inspector of Schools.

INTRODUCTORY PRIMER, 3d.

	s.	d.		s.	d.
FIRST STANDARD . . .	0	6	FOURTH STANDARD . . .	1	2
SECOND " . . .	0	10	FIFTH " . . .	1	6
THIRD " . . .	1	0	SIXTH " . . .	1	6

LESSONS FROM THE BIBLE. Part I. Old Testament. 1s.

LESSONS FROM THE BIBLE. Part II. New Testament, to which is added

THE GEOGRAPHY OF THE BIBLE, for very young Children. By Rev. C. THORNTON FORSTER. 1s. 2d. ** Or the Two Parts in One Volume. 2s.

FRENCH.

24. **French Grammar.** With Complete and Concise Rules on the Genders of French Nouns. By G. L. STRAUSS, Ph.D. 1s.
25. **French-English Dictionary.** Comprising a large number of New Terms used in Engineering, Mining, on Railways, &c. By ALFRED ELWES. 1s. 6d.
26. **English-French Dictionary.** By ALFRED ELWES. 2s.
- 25, 26. **French Dictionary (as above).** Complete, in One Vol., 3s. 6d. cloth boards, 3s. 6d. ** Or with the GRAMMAR, cloth boards, 4s. 6d.

French, continued.

47. **French and English Phrase Book** : containing Introductory Lessons, with Translations, for the convenience of Students ; several Vocabularies of Words, a Collection of suitable Phrases, and Easy Familiar Dialogues. 1s.

GERMAN.

39. **German Grammar.** Adapted for English Students, from Heyse's Theoretical and Practical Grammar, by Dr. G. L. STRAUSS. 1s.
40. **German Reader** : A Series of Extracts, carefully culled from the most approved Authors of Germany ; with Notes, Philological and Explanatory. By G. L. STRAUSS, Ph.D. 1s.
41. **German Triglote Dictionary.** By NICHOLAS ESTERHAZY, S. A. HAMILTON. Part I. English-German-French. 1s.
42. **German Triglote Dictionary.** Part II. German-French-English. 1s.
43. **German Triglote Dictionary.** Part III. French-German-English. 1s.
- 41-43. **German Triglote Dictionary** (as above), in One Vol., 3s. ; cloth boards, 4s. ** Or with the GERMAN GRAMMAR, cloth boards, 5s.

ITALIAN.

27. **Italian Grammar**, arranged in Twenty Lessons, with 2 Course of Exercises. By ALFRED ELWES. 1s.
28. **Italian Triglote Dictionary**, wherein the Genders of all the Italian and French Nouns are carefully noted down. By ALFRED ELWES. Vol. 1. Italian-English-French. 2s.
30. **Italian Triglote Dictionary.** By A. ELWES. Vol. 2. English-French-Italian. 2s.
32. **Italian Triglote Dictionary.** By ALFRED ELWES. Vol. 3. French-Italian-English. 2s.
- 28,30,32. **Italian Triglote Dictionary** (as above). In One Vol., 6s. ; cloth boards, 7s. 6d. ** Or with the ITALIAN GRAMMAR, cloth bds., 8s. 6d.

SPANISH AND PORTUGUESE.

34. **Spanish Grammar**, in a Simple and Practical Form. With a Course of Exercises. By ALFRED ELWES. 1s. 6d.
35. **Spanish-English and English-Spanish Dictionary.** Including a large number of Technical Terms used in Mining, Engineering, &c., with the proper Accents and the Gender of every Noun. By ALFRED ELWES. 4s. ; cloth boards, 5s. ** Or with the GRAMMAR, cloth boards, 6s.
55. **Portuguese Grammar**, in a Simple and Practical Form. With a Course of Exercises. By ALFRED ELWES, Author of "A Spanish Grammar," &c. 1s. 6d. *[Just published.]*

HEBREW.

- 46*. **Hebrew Grammar.** By Dr. BRESSLAU. 1s. 6d.
44. **Hebrew and English Dictionary**, Biblical and Rabbinical ; containing the Hebrew and Chaldee Roots of the Old Testament Post-Rabbinical Writings. By Dr. BRESSLAU. 6s. ** Or with the GRAMMAR, 7s.
46. **English and Hebrew Dictionary.** By Dr. BRESSLAU. 3s.
- 44,46. **Hebrew Dictionary** (as above), in Two Vols., complete, with 46*. the GRAMMAR, cloth boards, 12s.

LATIN.

19. **Latin Grammar.** Containing the Inflections and Elementary Principles of Translation and Construction. By the Rev. THOMAS GOODWIN, M.A., Head Master of the Greenwich Proprietary School. 1s.
20. **Latin-English Dictionary.** Compiled from the best Authorities. By the Rev. THOMAS GOODWIN, M.A. 2s.
22. **English-Latin Dictionary;** together with an Appendix of French and Italian Words which have their origin from the Latin. By the Rev. THOMAS GOODWIN, M.A. 1s. 6d.
- 20, 22. **Latin Dictionary** (as above). Complete in One Vol., 3s. 6d.; cloth boards, 4s. 6d. * * Or with the GRAMMAR, cloth boards, 5s. 6d.

LATIN CLASSICS. With Explanatory Notes in English.

1. **Latin Delectus.** Containing Extracts from Classical Authors, with Genealogical Vocabularies and Explanatory Notes, by HENRY YOUNG, lately Second Master of the Royal Grammar School, Guildford. 1s.
2. **Cæsar's Commentarii de Bello Gallico.** Notes, and a Geographical Register for the Use of Schools, by H. YOUNG. 2s.
12. **Ciceronis Oratio pro Sexto Roscio Amerino.** Edited, with an Introduction, Analysis, and Notes Explanatory and Critical, by the Rev. JAMES DAVIES, M.A. 1s.
14. **Ciceronis Cato Major, Lælius, Brutus, sive de Senectute, de Amicitia, de Claris Oratoribus Dialogi.** With Notes by W. BROWNRIGG SMITH, M.A., F.R.G.S. 2s.
3. **Cornelius Nepos.** With Notes. Intended for the Use of Schools. By H. YOUNG. 1s.
6. **Horace; Odes, Epode, and Carmen Sæculare.** Notes by H. YOUNG. 1s. 6d.
7. **Horace; Satires, Epistles, and Ars Poetica.** Notes by W. BROWNRIGG SMITH, M.A., F.R.G.S. 1s. 6d.
21. **Juvenalis Satiræ.** With Prolegomena and Notes by T. H. S. ESCOTT, B.A., Lecturer on Logic at King's College, London. 1s. 6d.
16. **Livy: History of Rome.** Notes by H. YOUNG and W. B. SMITH, M.A. Part 1. Books i., ii., 1s. 6d.
- 16*. ——— Part 2. Books iii., iv., v., 1s. 6d.
17. ——— Part 3. Books xxi., xxii., 1s. 6d.
8. **Sallustii Crispi Catalina et Bellum Jugurthinum.** Notes Critical and Explanatory, by W. M. DONNE, B.A., Trinity College, Cambridge. 1s. 6d.
10. **Terentii Adelphi Hecyra, Phormio.** Edited, with Notes, Critical and Explanatory, by the Rev. JAMES DAVIES, M.A. 2s.
9. **Terentii Andria et Heautontimorumenos.** With Notes, Critical and Explanatory, by the Rev. JAMES DAVIES, M.A. 1s. 6d.
11. **Terentii Eunuchus, Comoedia.** Edited, with Notes, by the Rev. JAMES DAVIES, M.A. 1s. 6d. Or the Adelphi, Andria, and Eunuchus, 3 vols. in 1, cloth boards, 6s.
4. **Virgilii Maronis Bucolica et Georgica.** With Notes on the Bucolics by W. RUSHTON, M.A., and on the Georgics by H. YOUNG. 1s. 6d.
5. **Virgilii Maronis Æneis.** Notes, Critical and Explanatory, by H. YOUNG. 2s.
19. **Latin Verse Selections,** from Catullus, Tibullus, Propertius, and Ovid. Notes by W. B. DONNE, M.A., Trinity College, Cambridge. 2s.
20. **Latin Prose Selections,** from Varro, Columella, Vitruvius, Seneca, Quintilian, Florus, Velleius Paterculus, Valerius Maximus Suetonius, Apuleius, &c. Notes by W. B. DONNE, M.A. 2s.

GREEK.

14. **Greek Grammar**, in accordance with the Principles and Philological Researches of the most eminent Scholars of our own day. By HANS CLAUDE HAMILTON. 1s.
- 15, 17. **Greek Lexicon**. Containing all the Words in General Use, with their Significations, Inflections, and Doubtful Quantities. By HENRY R. HAMILTON. Vol. 1. Greek-English, 2s.; Vol. 2. English-Greek, 2s. Or the Two Vols. in One, 4s.: cloth boards, 5s.
- 14, 15. **Greek Lexicon** (as above). Complete, with the GRAMMAR, in 17. One Vol., cloth boards, 6s.

GREEK CLASSICS. With Explanatory Notes in English.

1. **Greek Delectus**. Containing Extracts from Classical Authors, with Genealogical Vocabularies and Explanatory Notes, by H. YOUNG. New Edition, with an improved and enlarged Supplementary Vocabulary, by JOHN HUTCHISON, M.A., of the High School, Glasgow. 1s.
30. **Æschylus: Prometheus Vincit: The Prometheus Bound**. From the Text of DINDORF. Edited, with English Notes, Critical and Explanatory, by the Rev. JAMES DAVIES, M.A. 1s.
32. **Æschylus: Septem Contra Thebes: The Seven against Thebes**. From the Text of DINDORF. Edited, with English Notes, Critical and Explanatory, by the Rev. JAMES DAVIES, M.A. 1s.
40. **Aristophanes: Acharnians**. Chiefly from the Text of C. H. WEISE. With Notes, by C. S. T. TOWNSHEND, M.A. 1s. 6d.
26. **Euripides: Alcestitis**. Chiefly from the Text of DINDORF. With Notes, Critical and Explanatory, by JOHN MILNER, B.A. 1s.
23. **Euripides: Hecuba and Medea**. Chiefly from the Text of DINDORF. With Notes, Critical and Explanatory, by W. BROWNRIGG SMITH, M.A., F.R.G.S. 1s. 6d.
- 14-17. **Herodotus, The History of**, chiefly after the Text of GAISFORD. With Preliminary Observations and Appendices, and Notes, Critical and Explanatory, by T. H. L. LEARY, M.A., D.C.L.
 Part 1. Books i., ii. (The Clio and Euterpe), 2s.
 Part 2. Books iii., iv. (The Thalia and Melpomene), 2s.
 Part 3. Books v.-vii. (The Terpsichore, Erato, and Polymnia), 2s.
 Part 4. Books viii., ix. (The Urania and Calliope) and Index, 1s. 6d.
- 5-12. **Homer, The Works of**. According to the Text of BAUMLEIN. With Notes, Critical and Explanatory, drawn from the best and latest Authorities, with Preliminary Observations and Appendices, by T. H. L. LEARY, M.A., D.C.L.
 THE ILIAD: Part 1. Books i. to vi., 1s. 6d. | Part 3. Books xiii. to xviii., 1s. 6d.
 Part 2. Books vii. to xii., 1s. 6d. | Part 4. Books xix. to xxiv., 1s. 6d.
 THE ODYSSEY: Part 1. Books i. to vi., 1s. 6d. | Part 3. Books xiii. to xviii., 1s. 6d.
 Part 2. Books vii. to xii., 1s. 6d. | Part 4. Books xix. to xxiv., and Hymns, 2s.
4. **Lucian's Select Dialogues**. The Text carefully revised, with Grammatical and Explanatory Notes, by H. YOUNG. 1s.
13. **Plato's Dialogues: The Apology of Socrates, the Crito, and the Phædo**. From the Text of C. F. HERMANN. Edited with Notes, Critical and Explanatory, by the Rev. JAMES DAVIES, M.A. 2s.
18. **Sophocles: Œdipus Tyrannus**. Notes by H. YOUNG. 1s.
20. **Sophocles: Antigone**. From the Text of DINDORF. Notes, Critical and Explanatory, by the Rev. JOHN MILNER, B.A. 2s.
41. **Thucydides: History of the Peloponnesian War**. Notes by H. YOUNG. Book 1. 1s.
- 2, 3. **Xenophon's Anabasis; or, The Retreat of the Ten Thousand**. Notes and a Geographical Register, by H. YOUNG. Part 1. Books i. to iii., 1s. Part 2. Books iv. to vii., 1s.
42. **Xenophon's Panegyric on Agesilaus**. Notes and Introduction by LL. F. W. JEWITT. 1s. 6d.

LONDON, November, 1875.

A Catalogue of Books

INCLUDING MANY

NEW & STANDARD WORKS

IN

ENGINEERING, ARCHITECTURE,
AGRICULTURE, MATHEMATICS, MECHANICS,
SCIENCE, &c. &c.

PUBLISHED BY

LOCKWOOD & CO.,

7, STATIONERS'-HALL COURT, LUDGATE HILL, E.C.

ENGINEERING, SURVEYING, &c.

Humber's New Work on Water-Supply.

A COMPREHENSIVE TREATISE on the WATER-SUPPLY of CITIES and TOWNS. By WILLIAM HUMBER, Assoc. Inst. C.E., and M. Inst. M.E. Author of "Cast and Wrought Iron Bridge Construction," &c. &c. This work, it is expected, will contain about 50 Double Plates, and upwards of 300 pages of Text. Imp. 4to, half bound in morocco. [In the press.]

* * *In accumulating information for this volume, the Author has been very liberally assisted by several professional friends, who have made this department of engineering their special study. He has thus been in a position to prepare a work which, within the limits of a single volume, will supply the reader with the most complete and reliable information upon all subjects, theoretical and practical, connected with water supply. Through the kindness of Messrs. Anderson, Bateman, Hawksley, Homersham, Baldwin Latham, Lawson, Milne, Quick, Rawlinson, Simpson, and others, several works, constructed and in course of construction, from the designs of these gentlemen, will be fully illustrated and described.*

AMONGST OTHER IMPORTANT SUBJECTS THE FOLLOWING WILL BE TREATED IN THE TEXT:—

Historical Sketch of the means that have been proposed and adopted for the Supply of Water.—Water and the Foreign Matter usually associated with it.—Rainfall and Evaporation.—Springs and Subterranean Lakes.—Hydraulics.—The Selection of Sites for Water Works.—Wells.—Reservoirs.—Filtration and Filter Beds.—Reservoir and Filter Bed Appendages.—Pumps and Appendages.—Pumping Machinery.—Culverts and Conduits, Aqueducts, Syphons, &c.—Distribution of Water.—Water Meters and general House Fittings.—Cost of Works for the Supply of Water.—Constant and Intermittent Supply.—Suggestions for preparing Plans, &c. &c., together with a Description of the numerous Works illustrated, viz:—Aberdeen, Bideford, Cockermouth, Dublin, Glasgow, Loch Katrine, Liverpool, Manchester, Rotherham, Sunderland, and several others; with copies of the Contract, Drawings and Specification in each case.

Humber's Modern Engineering. First Series.

A RECORD of the PROGRESS of MODERN ENGINEERING, 1863. Comprising Civil, Mechanical, Marine, Hydraulic, Railway, Bridge, and other Engineering Works, &c. By WILLIAM HUMBER, Assoc. Inst. C.E., &c. Imp. 4to, with 36 Double Plates, drawn to a large scale, and Photographic Portrait of John Hawkshaw, C.E., F.R.S., &c. Price 3*l.* 3*s.* half morocco.

List of the Plates.

NAME AND DESCRIPTION.	PLATES.	NAME OF ENGINEER.
Victoria Station and Roof—L. B. & S. C. Rail.	1 to 8	Mr. R. Jacob Hood, C.E.
Southport Pier	9 and 10	Mr. James Brunlees, C.E.
Victoria Station and Roof—L. C. & D. & G. W. Railways	11 to 15A	Mr. John Fowler, C.E.
Roof of Cremorne Music Hall	16	Mr. William Humber, C.E.
Bridge over G. N. Railway	17	Mr. Joseph Cubitt, C.E.
Roof of Station—Dutch Rhenish Railway ..	18 and 19	Mr. Euschedi, C.E.
Bridge over the Thames—West London Extension Railway	20 to 24	Mr. William Baker, C.E.
Armour Plates	25	Mr. James Chalmers, C.E.
Suspension Bridge, Thames	26 to 29	Mr. Peter W. Barlow, C.E.
The Allen Engine	30	Mr. G. T. Porter, M.E.
Suspension Bridge, Avon	31 to 33	Mr. John Hawkshaw, C.E. and W. H. Barlow, C.E.
Underground Railway	34 to 36	Mr. John Fowler, C.E.

With copious Descriptive Letterpress, Specifications, &c.

"Handsomely lithographed and printed. It will find favour with many who desire to preserve in a permanent form copies of the plans and specifications prepared for the guidance of the contractors for many important engineering works."—*Engineer*.

Humber's Modern Engineering. Second Series.

A RECORD of the PROGRESS of MODERN ENGINEERING, 1864; with Photographic Portrait of Robert Stephenson, C.E., M.P., F.R.S., &c. Price 3*l.* 3*s.* half morocco.

List of the Plates.

NAME AND DESCRIPTION.	PLATES.	NAME OF ENGINEER.
Birkenhead Docks, Low Water Basin	1 to 15	Mr. G. F. Lyster, C.E.
Charing Cross Station Roof—C. C. Railway.	16 to 18	Mr. Hawkshaw, C.E.
Digswell Viaduct—Great Northern Railway.	19	Mr. J. Cubitt, C.E.
Robbery Wood Viaduct—Great N. Railway.	20	Mr. J. Cubitt, C.E.
Iron Permanent Way	20A	—
Clydach Viaduct—Merthyr, Tredegar, and Abergavenny Railway	21	Mr. Gardner, C.E.
Ebbw Viaduct ditto ditto ditto	22	Mr. Gardner, C.E.
College Wood Viaduct—Cornwall Railway ..	23	Mr. Brunel.
Dublin Winter Palace Roof	24 to 26	Messrs. Ordish & Le Feuvre.
Bridge over the Thames—L. C. & D. Railw.	27 to 32	Mr. J. Cubitt, C.E.
Albert Harbour, Greenock	33 to 36	Messrs. Bell & Miller.

With copious Descriptive Letterpress, Specifications, &c.

"A *resumé* of all the more interesting and important works lately completed in Great Britain; and containing, as it does, carefully executed drawings, with full working details, it will be found a valuable accessory to the profession at large."—*Engineer*.

"Mr. Humber has done the profession good and true service, by the fine collection of examples he has here brought before the profession and the public."—*Practical Mechanics' Journal*.

Humber's Modern Engineering. Third Series.

A RECORD of the PROGRESS of MODERN ENGINEERING, 1865. Imp. 4to, with 40 Double Plates, drawn to a large scale, and Photographic Portrait of J. R. M'Clean, Esq., late President of the Institution of Civil Engineers. Price 3*l*. 3*s*. half morocco.

List of Plates and Diagrams.

MAIN DRAINAGE, METROPOLIS.

NORTH SIDE.

Map showing Interception of Sewers.
Middle Level Sewer. Sewer under Regent's Canal.
Middle Level Sewer. Junction with Fleet Ditch.
Outfall Sewer. Bridge over River Lea. Elevation.
Outfall Sewer. Bridge over River Lea. Details.
Outfall Sewer. Bridge over River Lea. Details.
Outfall Sewer. Bridge over Marsh Lane, North Woolwich Railway, and Bow and Barking Railway Junction.
Outfall Sewer. Bridge over Bow and Barking Railway. Elevation.
Outfall Sewer. Bridge over Bow and Barking Railway. Details.
Outfall Sewer. Bridge over Bow and Barking Railway. Details.
Outfall Sewer. Bridge over East London Waterworks' Feeder. Elevation.
Outfall Sewer. Bridge over East London Waterworks' Feeder. Details.
Outfall Sewer. Reservoir. Plan.
Outfall Sewer. Reservoir. Section.
Outfall Sewer. Tumbling Bay and Outlet.
Outfall Sewer. Penstocks.

SOUTH SIDE.

Outfall Sewer. Bermondsey Branch.
Outfall Sewer. Bermondsey Branch.
Outfall Sewer. Reservoir and Outlet. Plan.

MAIN DRAINAGE, METROPOLIS, *continued—*

Outfall Sewer. Reservoir and Outlet. Details.
Outfall Sewer. Reservoir and Outlet. Details.
Outfall Sewer. Reservoir and Outlet. Details.
Outfall Sewer. Filth Hoist.
Sections of Sewers (North and South Sides).

THAMES EMBANKMENT.

Section of River Wall.
Steam-boat Pier, Westminster. Elevation.
Steam-boat Pier, Westminster. Details.
Landing Stairs between Charing Cross and Waterloo Bridges.
York Gate. Front Elevation.
York Gate. Side Elevation and Details.
Overflow and Outlet at Savoy Street Sewer. Details.
Overflow and Outlet at Savoy Street Sewer. Penstock.
Overflow and Outlet at Savoy Street Sewer. Penstock.
Steam-boat Pier, Waterloo Bridge. Elevation.
Steam-boat Pier, Waterloo Bridge. Details.
Steam-boat Pier, Waterloo Bridge. Details.
Junction of Sewers. Plans and Sections.
Gullies. Plans and Sections.
Rolling Stock.
Granite and Iron Forts.

With copious Descriptive Letterpress, Specifications, &c.

Opinions of the Press.

"Mr. Humber's works—especially his annual 'Record,' with which so many of our readers are now familiar—fill a void occupied by no other branch of literature. . . . The drawings have a constantly increasing value, and whoever desires to possess clear representations of the two great works carried out by our Metropolitan Board will obtain Mr. Humber's last volume."—*Engineering*.

"No engineer, architect, or contractor should fail to preserve these records of works which, for magnitude, have not their parallel in the present day, no student in the profession but should carefully study the details of these great works, which he may be one day called upon to imitate."—*Mechanics' Magazine*.

"A work highly creditable to the industry of its author. . . . The volume is quite an encyclopædia for the study of the student who desires to master the subject of municipal drainage on its scale of greatest development."—*Practical Mechanics Journal*.

Humber's Modern Engineering. Fourth Series.

A RECORD of the PROGRESS of MODERN ENGINEERING, 1866. Imp. 4to, with 36 Double Plates, drawn to a large scale, and Photographic Portrait of John Fowler, Esq., President of the Institution of Civil Engineers. Price 3*l*. 3*s*. half-morocco.

List of the Plates and Diagrams.

NAME AND DESCRIPTION.	PLATES.	NAME OF ENGINEER.
Abbey Mills Pumping Station, Main Drainage, Metropolis.....	1 to 4	Mr. Bazalgette, C.E.
Barrow Docks	5 to 9	Messrs. M'Clean & Stillman, [C. E.]
Manquis Viaduct, Santiago and Valparaiso Railway	10, 11	Mr. W. Loyd, C.E.
Adams' Locomotive, St. Helen's Canal Railw. Cannon Street Station Roof, Charing Cross Railway	12, 13	Mr. H. Cross, C.E.
Read Bridge over the River Moka.....	14 to 16	Mr. J. Hawkshaw, C.E.
Telegraphic Apparatus for Mesopotamia	17, 18	Mr. H. Wakefield, C.E.
Viaduct over the River Wye, Midland Railw.	19	Mr. Siemens, C.E.
St. Germans Viaduct, Cornwall Railway	20 to 22	Mr. W. H. Barlow, C.E.
Wrought-Iron Cylinder for Diving Bell.....	23, 24	Mr. Brunel, C.E.
Millwall Docks.....	25	Mr. J. Coode, C.E.
	26 to 31	Messrs. J. Fowler, C.E., and William Wilson, C.E.
Milroy's Patent Excavator	32	Mr. Milroy, C.E.
Metropolitan District Railway.....	33 to 38	Mr. J. Fowler, Engineer-in-Chief, and Mr. T. M. Johnson, C.E.
Harbours, Ports, and Breakwaters.....	A to C	

The Letterpress comprises—

A concluding article on Harbours, Ports, and Breakwaters, with Illustrations and detailed descriptions of the Breakwater at Cherbourg, and other important modern works; an article on the Telegraph Lines of Mesopotamia; a full description of the Wrought-iron Diving Cylinder for Ceylon, the circumstances under which it was used, and the means of working it; full description of the Millwall Docks; &c., &c., &c.

Opinions of the Press.

"Mr. Humber's 'Record of Modern Engineering' is a work of peculiar value, as well to those who design as to those who study the art of engineering construction. It embodies a vast amount of practical information in the form of full descriptions and working drawings of all the most recent and noteworthy engineering works. The plates are excellently lithographed, and the present volume of the 'Record' is not a whit behind its predecessors."—*Mechanics Magazine*.

"We gladly welcome another year's issue of this valuable publication from the able pen of Mr. Humber. The accuracy and general excellence of this work are well known, while its usefulness in giving the measurements and details of some of the latest examples of engineering, as carried out by the most eminent men in the profession, cannot be too highly prized."—*Artisan*.

"The volume forms a valuable companion to those which have preceded it, and cannot fail to prove a most important addition to every engineering library."—*Mining Journal*.

"No one of Mr. Humber's volumes was bad; all were worth their cost, from the mass of plates from well-executed drawings which they contained. In this respect, perhaps, this last volume is the most valuable that the author has produced."—*Practical Mechanics Journal*.

Humber's Great Work on Bridge Construction.

A COMPLETE and PRACTICAL TREATISE on CAST and WROUGHT-IRON BRIDGE CONSTRUCTION, including Iron Foundations. In Three Parts—Theoretical, Practical, and Descriptive. By WILLIAM HUMBER, Assoc. Inst. C.E., and M. Inst. M.E. Third Edition, revised and much improved, with 115 Double Plates (20 of which now first appear in this edition), and numerous additions to the Text. In 2 vols. imp. 4to., price 6l. 16s. 6d. half bound in morocco.

"A very valuable contribution to the standard literature of civil engineering. In addition to elevations, plans, and sections, large scale details are given, which very much enhance the instructive worth of these illustrations. No engineer would willingly be without so valuable a fund of information."—*Civil Engineer and Architect's Journal*.

"Mr. Humber's stately volumes lately issued—in which the most important bridges erected during the last five years, under the direction of the late Mr. Brunel, Sir W. Cubitt, Mr. Hawkshaw, Mr. Page, Mr. Fowler, Mr. Hemans, and others among our most eminent engineers, are drawn and specified in great detail."—*Engineer*.

Weale's Engineers' Pocket-Book.

THE ENGINEERS', ARCHITECTS', and CONTRACTORS' POCKET-BOOK (LOCKWOOD & Co.'s; formerly WEALE'S). Published Annually. In roan tuck, gilt edges, with 10 Copper Plates and numerous Woodcuts. Price 6s.

"A vast amount of really valuable matter condensed into the small dimensions of a book which is, in reality, what it professes to be—a pocket-book. We cordially recommend the book to the notice of the managers of coal and other mines; to them it will prove a handy book of reference on a variety of subjects more or less intimately connected with their profession."—*Colliery Guardian*.

"Every branch of engineering is treated of, and facts, figures, and data of every kind abound."—*Mechanics' Mag.*

"It contains a large amount of information peculiarly valuable to those for whose use it is compiled. We cordially commend it to the engineering and architectural professions generally."—*Mining Journal*.

Iron Bridges, Girders, Roofs, &c.

A TREATISE on the APPLICATION of IRON to the CONSTRUCTION of BRIDGES, GIRDERS, ROOFS, and OTHER WORKS; showing the Principles upon which such Structures are Designed, and their Practical Application. Especially arranged for the use of Students and Practical Mechanics, all Mathematical Formulæ and Symbols being excluded. By FRANCIS CAMPIN, C.E. With numerous Diagrams. 12mo., cloth boards, 3s.

"For numbers of young engineers the book is just the cheap, handy, first guide they want."—*Middlesborough Weekly News*.

"Invaluable to those who have not been educated in mathematics."—*Colliery Guardian*.

"Remarkably accurate and well written."—*Artisan*.

Iron and Steel.

'IRON AND STEEL': a Work for the Forge, Foundry, Factory, and Office. Containing Ready, Useful, and Trustworthy Information for Ironmasters and their Stocktakers; Managers of Bar, Rail, Plate, and Sheet Rolling Mills; Iron and Metal Founders; Iron Ship and Bridge Builders; Mechanical, Mining, and Consulting Engineers; Architects, Contractors, Builders, and Professional Draughtsmen. By CHARLES HOARE, Author of 'The Slide Rule,' &c. Oblong, 18mo., 5s. cloth.

Barlow on the Strength of Materials, enlarged.

A TREATISE ON THE STRENGTH OF MATERIALS, with Rules for application in Architecture, the Construction of Suspension Bridges, Railways, &c.; and an Appendix on the Power of Locomotive Engines, and the effect of Inclined Planes and Gradients. By PETER BARLOW, F.R.S. A New Edition, revised by his Sons, P. W. BARLOW, F.R.S., and W. H. BARLOW, F.R.S., to which are added Experiments by HODGKINSON, FAIRBAIRN, and KIRKALDY; an Essay (with Illustrations) on the effect produced by passing Weights over Elastic Bars, by the Rev. ROBERT WILLIS, M.A., F.R.S. And Formulæ for Calculating Girders, &c. The whole arranged and edited by W. HUMBER, Assoc. Inst. C.E., Author of "A Complete and Practical Treatise on Cast and Wrought-Iron Bridge Construction," &c. &c. Demy 8vo, 400 pp., with 19 large Plates, and numerous woodcuts, price 18s. cloth.

"The book is undoubtedly worthy of the highest commendation."—*Mining Journal*.

"The best book on the subject which has yet appeared. . . . We know of no work that so completely fulfils its mission."—*English Mechanic*.

"The standard treatise upon this particular subject."—*Engineer*.

Strains, Formulæ & Diagrams for Calculation of.

A HANDY BOOK for the CALCULATION of STRAINS in GIRDERS and SIMILAR STRUCTURES, and their STRENGTH; consisting of Formulæ and Corresponding Diagrams, with numerous Details for Practical Application, &c. By WILLIAM HUMBER, Assoc. Inst. C.E., &c. Fcap. 8vo, with nearly 100 Woodcuts and 3 Plates, price 7s. 6d. cloth.

"The arrangement of the matter in this little volume is as convenient as it well could be. . . . The system of employing diagrams as a substitute for complex computations is one justly coming into great favour, and in that respect Mr. Humber's volume is fully up to the times."—*Engineering*.

"The formulæ are neatly expressed, and the diagrams good."—*Athenæum*.

"We heartily commend this really handy book to our engineer and architect readers."—*English Mechanic*.

Mechanical Engineering.

A PRACTICAL TREATISE ON MECHANICAL ENGINEERING: comprising Metallurgy, Moulding, Casting, Forging, Tools, Workshop Machinery, Mechanical Manipulation, Manufacture of the Steam Engine, &c. &c. With an Appendix on the Analysis of Iron and Iron Ore, and Glossary of Terms. By FRANCIS CAMPIN, C.E. Illustrated with 91 Woodcuts and 28 Plates of Slotting, Shaping, Drilling, Punching, Shearing, and Riveting Machines—Blast, Refining, and Reverberatory Furnaces—Steam Engines, Governors, Boilers, Locomotives, &c. 8vo, cloth, 12s.

Steam Engine.

STEAM AND THE STEAM ENGINE, Stationary and Portable, an Elementary Treatise on. Being an Extension of Mr. John Sewell's Treatise on Steam. By D. KINNEN CLARK, C.E., M.I.C.E., Author of 'Railway Machinery,' 'Railway Locomotives,' &c., &c. With numerous Illustrations. 12mo, cloth boards, 4s.

"Every essential part of the subject is treated of competently, and in a popular style."—*Iron*.

Strains.

THE STRAINS ON STRUCTURES OF IRONWORK ;
with Practical Remarks on Iron Construction. By F. W. SHENLDS,
M. Inst. C.E. Second Edition, with 5 plates. Royal 8vo, 5s. cloth.

CONTENTS.—Introductory Remarks ; Beams Loaded at Centre ; Beams Loaded at unequal distances between supports ; Beams uniformly Loaded ; Girders with triangular bracing Loaded at centre ; Ditto, Loaded at unequal distances between supports ; Ditto, uniformly Loaded ; Calculation of the Strains on Girders with triangular Basings ; Cantilevers ; Continuous Girders ; Lattice Girders ; Girders with Vertical Struts and Diagonal Ties ; Calculation of the Strains on Ditto ; Bow and String Girders ; Girders of a form not belonging to any regular figure ; Plate Girders ; Apportionments of Material to Strain ; Comparison of different Girders ; Proportion of Length to Depth of Girders ; Character of the Work ; Iron Roofs.

Construction of Iron Beams, Pillars, &c.

IRON AND HEAT, Exhibiting the Principles concerned in the
Construction of Iron Beams, Pillars, and Bridge Girders, and the
Action of Heat in the Smelting Furnace. By JAMES ARMOUR,
C.E. Woodcuts, 12mo, cloth boards, 3s. 6d. ; cloth limp, 2s. 6d.

"A very useful and thoroughly practical little volume, in every way deserving of circulation amongst working men."—*Mining Journal*.

"No ironworker who wishes to acquaint himself with the principles of his own trade can afford to be without it."—*South Durham Mercury*.

Power in Motion.

POWER IN MOTION : Horse Power, Motion, Toothed Wheel
Gearing, Long and Short Driving Bands, Angular Forces, &c.
By JAMES ARMOUR, C.E. With 73 Diagrams. 12mo, cloth
boards, 3s. 6d. [Recently published.]

"Numerous illustrations enable the author to convey his meaning as explicitly as it is perhaps possible to be conveyed. The value of the theoretic and practical knowledge imparted cannot well be over estimated."—*Newcastle Weekly Chronicle*.

Metallurgy of Iron.

A TREATISE ON THE METALLURGY OF IRON : con-
taining Outlines of the History of Iron Manufacture, Methods of
Assay, and Analyses of Iron Ores, Processes of Manufacture of
Iron and Steel, &c. By H. BAUERMAN, F.G.S., Associate of the
Royal School of Mines. With numerous Illustrations. Fourth
Edition, revised and much enlarged. 12mo., cloth boards, 5s. 6d.

[Just published.]

"Carefully written, it has the merit of brevity and conciseness, as to less important points, while all material matters are very fully and thoroughly entered into."—*Standard*.

Trigonometrical Surveying.

AN OUTLINE OF THE METHOD OF CONDUCTING A
TRIGONOMETRICAL SURVEY, for the Formation of Geo-
graphical and Topographical Maps and Plans, Military Recon-
naissance, Levelling, &c., with the most useful Problems in Geodesy
and Practical Astronomy, and Formulæ and Tables for Facilitating
their Calculation. By LIEUT-GENERAL FROME, R.E., late In-
spector-General of Fortifications, &c. Fourth Edition, Enlarged,
thoroughly Revised, and partly Re-written. By CAPTAIN CHARLES
WARREN, R.E., F.G.S. With 19 Plates and 115 Woodcuts,
royal 8vo, price 16s. cloth.

Hydraulics.

HYDRAULIC TABLES, CO-EFFICIENTS, and FORMULÆ for finding the Discharge of Water from Orifices, Notches, Weirs, Pipes, and Rivers. With New Formulæ, Tables, and General Information on Rain-fall, Catchment-Basins, Drainage, Sewerage, Water Supply for Towns and Mill Power. By JOHN NEVILLE, Civil Engineer, M.R.I.A. Third Edition, carefully revised, with considerable Additions. Numerous Illustrations. Crown 8vo, 14s. cloth. [Now ready.]

Drawing for Engineers, &c.

THE WORKMAN'S MANUAL OF ENGINEERING DRAWING. By JOHN MAXTON, Instructor in Engineering Drawing, South Kensington. Second Edition, carefully revised. With upwards of 300 Plates and Diagrams. 12mo, cloth, strongly bound, 4s. 6d.

"Even accomplished draughtsmen will find in it much that will be of use to them. A copy of it should be kept for reference in every drawing office."—*Engineering.*

"An indispensable book for teachers of engineering drawing."—*Mechanics' Magazine.*

Levelling.

A TREATISE on the PRINCIPLES and PRACTICE of LEVELLING; showing its Application to Purposes of Railway and Civil Engineering, in the Construction of Roads; with Mr. TELFORD'S Rules for the same. By FREDERICK W. SIMMS, F.G.S., M. Inst. C.E. Sixth Edition, very carefully revised, with the addition of Mr. LAW'S Practical Examples for Setting out Railway Curves, and Mr. TRAUTWINE'S Field Practice of Laying out Circular Curves. With 7 Plates and numerous Woodcuts. 8vo, 8s. 6d. cloth. * * * TRAUTWINE on Curves, separate, price 5s.

"One of the most important text-books for the general surveyor, and there is scarcely a question connected with levelling for which a solution would be sought but that would be satisfactorily answered by consulting the volume."—*Mining Journal.*

"The text-book on levelling in most of our engineering schools and colleges."—*Engineer.*

"The publishers have rendered a substantial service to the profession, especially to the younger members, by bringing out the present edition of Mr. Simms's useful work."—*Engineering.*

Earthwork.

EARTHWORK TABLES, showing the Contents in Cubic Yards of Embankments, Cuttings, &c., of Heights or Depths up to an average of 80 feet. By JOSEPH BROADBENT, C.E., and FRANCIS CAMPIN, C.E. Cr. 8vo. oblong, 5s. cloth.

"Creditable to both the authors and the publishers. . . . The way in which accuracy is attained, by a simple division of each cross section into three elements, two of which are constant and one variable, is ingenious."—*Athenæum.*

"Likely to be of considerable service to engineers."—*Building News.*

"Contractors, builders, and engineers should not be without it."—*Builders' Weekly Reporter.*

"Cannot fail to come into general use."—*Mining Journal.*

Tunnelling.

PRACTICAL TUNNELLING. By F. W. SIMMS. An entirely new edition, revised and greatly enlarged by D. KINNEAR CLARK, C.E. Imp. 8vo. [In the Press.]

Strength of Cast Iron, &c.

A PRACTICAL ESSAY on the STRENGTH of CAST IRON and OTHER METALS. By the late THOMAS TREDGOLD, Mem. Inst. C.E., Author of "Elementary Principles of Carpentry," &c. Fifth Edition, Edited by EATON HODGKINSON, F.R.S.; to which are added EXPERIMENTAL RESEARCHES on the STRENGTH and OTHER PROPERTIES of CAST IRON. By the EDITOR. The whole Illustrated with 9 Engravings and numerous Woodcuts. 8vo, 12s. cloth.

* * HODGKINSON'S EXPERIMENTAL RESEARCHES ON THE STRENGTH AND OTHER PROPERTIES OF CAST IRON may be had separately. With Engravings and Woodcuts. 8vo, price 6s. cloth.

The High-Pressure Steam Engine.

THE HIGH-PRESSURE STEAM ENGINE; an Exposition of its Comparative Merits, and an Essay towards an Improved System of Construction, adapted especially to secure Safety and Economy. By Dr. ERNST ALBAN, Practical Machine Maker, Plau, Mecklenberg. Translated from the German, with Notes, by Dr. POLE, F.R.S., M. Inst. C.E., &c. &c. With 28 fine Plates, 8vo, 16s. 6d. cloth.

"A work like this, which goes thoroughly into the examination of the high-pressure engine, the boiler, and its appendages, &c., is exceedingly useful, and deserves a place in every scientific library."—*Steam Shipping Chronicle*.

Steam Boilers.

A TREATISE ON STEAM BOILERS: their Strength, Construction, and Economical Working. By ROBERT WILSON, late Inspector for the Manchester Steam Users' Association for the Prevention of Steam Boiler Explosions, and for the Attainment of Economy in the Application of Steam. Third Edition. 12mo, cloth boards, 328 pages, price 6s.

Tables of Curves.

TABLES OF TANGENTIAL ANGLES and MULTIPLES for setting out Curves from 5 to 200 Radius. By ALEXANDER BEAZELEY, M. Inst. C.E. Printed on 48 Cards, and sold in a cloth box, waistcoat-pocket size, price 3s. 6d.

"Each table is printed on a small card, which, being placed on the theodolite, leaves the hands free to manipulate the instrument—no small advantage as regards the rapidity of work. They are clearly printed, and compactly fitted into a small case for the pocket—an arrangement that will recommend them to all practical men."—*Engineer*.

"Very handy: a man may know that all his day's work must fall on two of these cards, which he puts into his own card-case, and leaves the rest behind."—*Athenaeum*.

Laying Out Curves.

THE FIELD PRACTICE of LAYING OUT CIRCULAR CURVES for RAILROADS. By JOHN C. TRAUTWINE, C.E. (Extracted from SIMMS's Work on Levelling). 8vo, 5s. sewed.

Estimate and Price Book.

THE CIVIL ENGINEER'S AND CONTRACTOR'S ESTIMATE AND PRICE BOOK for Home or Foreign Service : in reference to Roads, Railways, Tramways, Docks, Harbours, Forts, Fortifications, Bridges, Aqueducts, Tunnels, Sewers, Waterworks, Gasworks, Stations, Barracks, Warehouses, &c. &c. &c. With Specifications for Permanent Way, Telegraph Materials, Plant, Maintenance, and Working of a Railway ; and a Priced List of Machinery, Plant, Tools, &c. By W. D. HASKOLL, C.E. Plates and Woodcuts. Published annually. 8vo, cloth, 6s.

"As furnishing a variety of data on every conceivable want to civil engineers and contractors, this book has ever stood perhaps unrivalled."—*Architect*.

Surveying (Land and Marine).

LAND AND MARINE SURVEYING, in Reference to the Preparation of Plans for Roads and Railways, Canals, Rivers, Towns' Water Supplies, Docks and Harbours ; with Description and Use of Surveying Instruments. By W. DAVIS HASKOLL, C.E., Author of "The Engineer's Field Book," "Examples of Bridge and Viaduct Construction," &c. Demy 8vo, price 12s. 6d. cloth, with 14 folding Plates, and numerous Woodcuts.

"A most useful and well arranged book for the aid of a student. . . . We can strongly recommend it as a carefully-written and valuable text-book."—*Builder*.

"Mr. Haskoll has knowledge and experience, and can so give expression to it as to make any matter on which he writes, clear to the youngest pupil in a surveyor's office."—*Colliery Guardian*.

"A volume which cannot fail to prove of the utmost practical utility. . . . It is one which may be safely recommended to all students who aspire to become clean and expert surveyors."—*Mining Journal*.

Engineering Fieldwork.

THE PRACTICE OF ENGINEERING FIELDWORK, applied to Land and Hydraulic, Hydrographic, and Submarine Surveying and Levelling. Second Edition, revised, with considerable additions, and a Supplementary Volume on WATERWORKS, SEWERS, SEWAGE, and IRRIGATION. By W. DAVIS HASKOLL, C.E. Numerous folding Plates. Demy 8vo, 2 vols. in one, cloth boards, 1l. 1s. (published at 2l. 4s.)

Mining, Surveying and Valuing.

THE MINERAL SURVEYOR AND VALUER'S COMPLETE GUIDE, comprising a Treatise on Improved Mining Surveying, with new Traverse Tables ; and Descriptions of Improved Instruments ; also an Exposition of the Correct Principles of Laying out and Valuing Home and Foreign Iron and Coal Mineral Properties: to which is appended M. THOMAN'S (of the Crédit Mobilier, Paris) TREATISE on COMPOUND INTEREST and ANNUITIES, with LOGARITHMIC TABLES. By WILLIAM LINTERN, Mining and Civil Engineer. 12mo, strongly bound in cloth boards, with four Plates of Diagrams, Plans, &c., price 10s. 6d.

"Contains much valuable information given in a small compass, and which, as far as we have tested it, is thoroughly trustworthy."—*Iron and Coal Trades' Review*.

"The matter, arrangement, and illustration of this work are all excellent, and make it one of the best of its kind."—*Standard*.

Fire Engineering.

FIRES, FIRE-ENGINES, AND FIRE BRIGADES. With a History of Fire-Engines, their Construction, Use, and Management; Remarks on Fire-Proof Buildings, and the Preservation of Life from Fire; Statistics of the Fire Appliances in English Towns; Foreign Fire Systems; Hints on Fire Brigades, &c., &c. By CHARLES F. T. YOUNG, C.E. With numerous Illustrations, handsomely printed, 544 pp., demy 8vo, price 1*l.* 4*s.* cloth.

"We can most heartily commend this book. . . . It is really the only English work we now have upon the subject."—*Engineering*.

"We strongly recommend the book to the notice of all who are in any way interested in fires, fire-engines, or fire-brigades."—*Mechanics' Magazine*.

Manual of Mining Tools.

MINING TOOLS. For the use of Mine Managers, Agents, Mining Students, &c. By WILLIAM MORGANS, Lecturer on Practical Mining at the Bristol School of Mines. Volume of Text. 12mo. With an Atlas of Plates, containing 235 Illustrations. 4*to*.

Together, price 9*s.* cloth boards. [Recently published.]

"Students in the Science of Mining, and not only they, but subordinate officials in mines, and even Overmen, Captains, Managers, and Viewers may gain practical knowledge and useful hints by the study of Mr. Morgans's Manual."—*Colliery Guardian*.

"A very valuable work, which will tend materially to improve our mining literature."—*Mining Journal*.

Gas and Gasworks.

A TREATISE ON GASWORKS AND THE PRACTICE OF MANUFACTURING AND DISTRIBUTING COAL GAS. By SAMUEL HUGHES, C.E. Fourth Edition, revised by W. RICHARDS, C.E. With 68 Woodcuts, bound in cloth boards, 12mo, price 4*s.*

Waterworks for Cities and Towns.

WATERWORKS for the SUPPLY of CITIES and TOWNS, with a Description of the Principal Geological Formations of England as influencing Supplies of Water. By SAMUEL HUGHES, F.G.S., Civil Engineer. New and enlarged edition, 12mo, cloth boards, with numerous Illustrations, price 5*s.*

"One of the most convenient, and at the same time reliable works on a subject, the vital importance of which cannot be over-estimated."—*Bradford Observer*.

Coal and Coal Mining.

COAL AND COAL MINING: a Rudimentary Treatise on. By WARINGTON W. SMYTH, M.A., F.R.S., &c., Chief Inspector of the Mines of the Crown and of the Duchy of Cornwall. New edition, revised and corrected. 12mo., cloth boards, with numerous Illustrations, price 4*s.* 6*d.*

"Every portion of the volume appears to have been prepared with much care, and as an outline is given of every known coal-field in this and other countries, as well as of the two principal methods of working, the book will doubtless interest a very large number of readers."—*Mining Journal*.

"Certainly experimental skill and rule-of-thumb practice would be greatly enriched by the addition of the theoretical knowledge and scientific information which Mr. Warington Smyth communicates in combination with the results of his own experience and personal research."—*Colliery Guardian*.

Field-Book for Engineers.

THE ENGINEER'S, MINING SURVEYOR'S, and CONTRACTOR'S FIELD-BOOK. By W. DAVIS HASKOLL, Civil Engineer. Third Edition, much enlarged, consisting of a Series of Tables, with Rules, Explanations of Systems, and Use of Theodolite for Traverse Surveying and Plotting the Work with minute accuracy by means of Straight Edge and Set Square only; Levelling with the Theodolite, Casting out and Reducing Levels to Datum, and Plotting Sections in the ordinary manner; Setting out Curves with the Theodolite by Tangential Angles and Multiples with Right and Left-hand Readings of the Instrument; Setting out Curves without Theodolite on the System of Tangential Angles by Sets of Tangents and Offsets; and Earthwork Tables to 80 feet deep, calculated for every 6 inches in depth. With numerous wood-cuts, 12mo, price 12s. cloth.

"A very useful work for the practical engineer and surveyor. Every person engaged in engineering field operations will estimate the importance of such a work and the amount of valuable time which will be saved by reference to a set of reliable tables prepared with the accuracy and fulness of those given in this volume."—*Railway News*.

"The book is very handy, and the author might have added that the separate tables of sines and tangents to every minute will make it useful for many other purposes, the genuine traverse tables existing all the same."—*Athenaeum*.

"The work forms a handsome pocket volume, and cannot fail, from its portability and utility, to be extensively patronised by the engineering profession."—*Mining Journal*.

"We strongly recommend this second edition of Mr. Haskoll's 'Field Book' to all classes of surveyors."—*Colliery Guardian*.

Earthwork, Measurement and Calculation of.

A MANUAL on EARTHWORK. By ALEX. J. S. GRAHAM, C.E., Resident Engineer, Forest of Dean Central Railway. With numerous Diagrams. 18mo, 2s. 6d. cloth.

"As a really handy book for reference, we know of no work equal to it; and the railway engineers and others employed in the measurement and calculation of earth work will find a great amount of practical information very admirably arranged, and available for general or rough estimates, as well as for the more exact calculations required in the engineers' contractor's offices."—*Artisan*.

Harbours.

THE DESIGN and CONSTRUCTION of HARBOURS: A Treatise on Maritime Engineering. By THOMAS STEVENSON, F.R.S.E., F.G.S., M.I.C.E. Second Edition, containing many additional subjects, and otherwise generally extended and revised. With 20 Plates and numerous Cuts. Small 4to, 15s. cloth.

Mathematical and Drawing Instruments.

A TREATISE ON THE PRINCIPAL MATHEMATICAL AND DRAWING INSTRUMENTS employed by the Engineer, Architect, and Surveyor. By FREDERICK W. SIMMS, M. Inst. C.E., Author of "Practical Tunnelling," &c. Third Edition, with numerous Cuts. 12mo, price 3s. 6d. cloth.

Bridge Construction in Masonry, Timber, & Iron.

EXAMPLES OF BRIDGE AND VIADUCT CONSTRUCTION OF MASONRY, TIMBER, AND IRON; consisting of 46 Plates from the Contract Drawings or Admeasurement of select Works. By W. DAVIS HASKOLL, C.E. Second Edition, with the addition of 554 Estimates, and the Practice of Setting out Works, illustrated with 6 pages of Diagrams. Imp. 4to, price 2l. 12s. 6d. half-morocco.

"One of the very few works extant descending to the level of ordinary routine, and treating on the common every-day practice of the railway engineer. . . . A work of the present nature by a man of Mr. Haskoll's experience, must prove invaluable to hundreds. The tables of estimates appended to this edition will considerably enhance its value."—*Engineering*.

Mathematical Instruments, their Construction, &c.

MATHEMATICAL INSTRUMENTS: THEIR CONSTRUCTION, ADJUSTMENT, TESTING, AND USE; comprising Drawing, Measuring, Optical, Surveying, and Astronomical Instruments. By J. F. HEATHER, M.A., Author of "Practical Plane Geometry," "Descriptive Geometry," &c. Enlarged Edition, for the most part entirely rewritten. With numerous Wood-cuts. 12mo, cloth boards, price 5s.

Oblique Arches.

A PRACTICAL TREATISE ON THE CONSTRUCTION OF OBLIQUE ARCHES. By JOHN HART. Third Edition, with Plates. Imperial 8vo, price 8s. cloth.

Oblique Bridges.

A PRACTICAL and THEORETICAL ESSAY on OBLIQUE BRIDGES, with 13 large folding Plates. By GEO. WATSON BUCK, M. Inst. C.E. Second Edition, corrected by W. H. BARLOW, M. Inst. C.E. Imperial 8vo, 12s. cloth.

"The standard text-book for all engineers regarding skew arches, is Mr. Buck's treatise, and it would be impossible to consult a better."—*Engineer*.

Pocket-Book for Marine Engineers.

A POCKET BOOK FOR MARINE ENGINEERS. Containing useful Rules and Formulæ in a compact form. By FRANK PROCTOR, A.I.N.A. Second Edition, revised and enlarged. Royal 32mo, leather, gilt edges, with strap, price 4s.

"We recommend it to our readers as going far to supply a long-felt want."—*Naval Science*.

"A most useful companion to all marine engineers."—*United Service Gazette*.

"Scarcely anything required by a naval engineer appears to have been forgotten."—*Iron*.

"A very valuable publication . . . a means of saving much time and labour."—*New York Monthly Record*.

Weale's Dictionary of Terms.

A DICTIONARY of TERMS used in ARCHITECTURE, BUILDING, ENGINEERING, MINING, METALLURGY, ARCHÆOLOGY, the FINE ARTS, &c. By JOHN WEALE. Fourth Edition, enlarged and revised by ROBERT HUNT, F.R.S., Keeper of Mining Records, Editor of "Ure's Dictionary of Arts, &c." 12mo, cloth boards, price 6s.

Grantham's Iron Ship-Building, enlarged.

ON IRON SHIP-BUILDING ; with Practical Examples and Details. Fifth Edition. Imp. 4to, boards, enlarged from 24 to 40 Plates (21 quite new), including the latest Examples. Together with separate Text, 12mo, cloth limp, also considerably enlarged. By JOHN GRANTHAM, M. Inst. C.E., &c. Price 2l. 2s. complete.

Description of Plates.

1. Hollow and Bar Keels, Stem and Stern Posts. [Pieces.]
2. Side Frames, Floorings, and Bilge
3. Floorings continued—Keelsons, Deck Beams, Gunwales, and Stringers.
4. Gunwales continued—Lower Decks, and Orlop Beams.
- 4a. Gunwales and Deck Beam Iron.
5. Angle-Iron, T Iron, Z Iron, Bulb Iron, as Rolled for Building.
6. Rivets, shown in section, natural size ; Flush and Lapped Joints, with Single and Double Riveting.
7. Plating, three plans ; Bulkheads and Modes of Securing them.
8. Iron Masts, with Longitudinal and Transverse Sections.
9. Sliding Keel, Water Ballast, Moulding the Frames in Iron Ship Building, Levelling Plates.
10. Longitudinal Section, and Half-breadth Deck Plan of Large Vessels on a reduced Scale.
11. Midship Sections of Three Vessels.
12. *Large Vessel*, showing Details—*Fore End* in Section, and End View, with Stern Post, Crutches, &c.
13. *Large Vessel*, showing Details—*After End* in Section, with End View, Stern Frame for Screw, and Rudder.
14. *Large Vessel*, showing Details—*Midship Section*, half breadth.
15. *Machines* for Punching and Shearing Plates and Angle-Iron, and for Bending Plates ; Rivet Hearth.
- 15a. Beam-Bending Machine, Independent Shearing, Punching and Angle-Iron Machine.
- 15b. Double Lever Punching and Shearing Machine, arranged for cutting Angle and T Iron, with Dividing Table and Engine.
16. *Machines*.—Garforth's Riveting Machine, Drilling and Counter-Sinking Machine.
- 16a. Plate Planing Machine.
17. *Air Furnace* for Heating Plates and Angle-Iron : Various Tools used in Riveting and Plating.
18. *Gunwale* ; Keel and Flooring ; Plan for Sheathing with Copper.
- 18a. Grantham's Improved Plan of Sheathing Iron Ships with Copper.
19. Illustrations of the Magnetic Condition of various Iron Ships.
20. Gray's Floating Compass and Binnacle, with Adjusting Magnets, &c.
21. Corroded Iron Bolt in Frame of Wooden Ship ; Jointing Plates.
- 22-4. *Great Eastern*—Longitudinal Sections and Half-breadth Plans—Midship Section, with Details—Section in Engine Room, and Paddle Boxes.
- 25-6. Paddle Steam Vessel of Steel.
27. *Scarborough*—Paddle Vessel of Steel.
- 28-9. Proposed Passenger Steamer.
30. *Persian*—Iron Screw Steamer.
31. Midship Section of H.M. Steam Frigate, *Warrior*.
32. Midship Section of H.M. Steam Frigate, *Hercules*.
33. Stem, Stern, and Rudder of H.M. Steam Frigate, *Bellerophon*.
34. Midship Section of H.M. Troop Ship, *Serapis*.
35. Iron Floating Dock.

"A thoroughly practical work, and every question of the many in relation to iron shipping which admit of diversity of opinion, or have various and conflicting personal interests attached to them, is treated with sober and impartial wisdom and good sense. . . . As good a volume for the instruction of the pupil or student of iron naval architecture as can be found in any language."—*Practical Mechanics' Journal*.

"A very elaborate work. . . . It forms a most valuable addition to the history of iron shipbuilding, while its having been prepared by one who has made the subject his study for many years, and whose qualifications have been repeatedly recognised, will recommend it as one of practical utility to all interested in shipbuilding."—*Army and Navy Gazette*.

Steam.

THE SAFE USE OF STEAM : containing Rules for Unprofessional Steam Users. By an ENGINEER. Second Edition. 12mo. Sewed, 6d.

N. B.—*This little work should be in the hands of every person having to deal with a Steam Engine of any kind.*

"If steam-users would but learn this little book by heart, and then hand it to their stokers to do the same, and see that the latter do it, boiler explosions would become sensations by their rarity."—*English Mechanic*.

ARCHITECTURE, &c.

Construction.

THE SCIENCE of BUILDING : An Elementary Treatise on the Principles of Construction. By E. WYNDHAM TARN, M.A., Architect. Illustrated with 47 Wood Engravings. Demy 8vo, price 8s. 6d. cloth. *[Recently published.]*

"A very valuable book, which we strongly recommend to all students."—*Builder.*

"The treatise does credit alike to the author and the publisher."—*Engineer.*

"No architectural student should be without this hand-book."—*Architect.*

"The book is very far from being a mere compilation; it is an able digest of information which is only to be found scattered through various works, and contains more really original writing than many putting forth far stronger claims to originality."—*Engineering.*

Beaton's Pocket Estimator.

THE POCKET ESTIMATOR FOR THE BUILDING TRADES, being an easy method of estimating the various parts of a Building collectively, more especially applied to Carpenters' and Joiners' work, priced according to the present value of material and labour. By A. C. BEATON, Author of 'Quantities and Measurements.' 33 Woodcuts. Leather. Waistcoat-pocket size. 2s.

Beaton's Builders' and Surveyors' Technical Guide.

THE POCKET TECHNICAL GUIDE AND MEASURER FOR BUILDERS AND SURVEYORS: containing a Complete Explanation of the Terms used in Building Construction, Memoranda for Reference, Technical Directions for Measuring Work in all the Building Trades, with a Treatise on the Measurement of Timbers, and Complete Specifications for Houses, Roads, and Drains. By A. C. BEATON, Author of 'Quantities and Measurements.' With 19 Woodcuts. Leather. Waistcoat-pocket size. 2s.

Villa Architecture.

A HANDY BOOK of VILLA ARCHITECTURE; being a Series of Designs for Villa Residences in various Styles. With Detailed Specifications and Estimates. By C. WICKES, Architect, Author of "The Spires and Towers of the Mediaeval Churches of England," &c. First Series, consisting of 30 Plates; Second Series, 31 Plates. Complete in 1 vol. 4to, price 2l. 10s. half morocco. Either Series separate, price 1l. 7s. each, half morocco.

"The whole of the designs bear evidence of their being the work of an artistic architect, and they will prove very valuable and suggestive to architects, students, and amateurs."—*Building News.*

House Painting.

HOUSE PAINTING, GRAINING, MARBLING, AND SIGN WRITING : a Practical Manual of, containing full information on the Processes of House Painting in Oil and Distemper, the Formation of Letters and Practice of Sign Writing, the Principles of Decorative Art, a Course of Elementary Drawing for House Painters, Writers, &c., and a Collection of Useful Receipts. With 9 Coloured Plates of Woods and Marbles, and nearly 150 Wood Engravings. By ELLIS A. DAVIDSON, Author of 'Building Construction,' 'Drawing for Carpenters,' &c. 12mo, 6s. cloth boards.

Architecture, Ancient and Modern.

RUDIMENTARY ARCHITECTURE, Ancient and Modern. Consisting of VITRUVIUS, translated by JOSEPH GWILT, F.S.A., &c., with 23 fine copper plates; GRECIAN Architecture, by the EARL of ABERDEEN; the ORDERS of Architecture, by W. H. LEEDS, Esq.; The STYLES of Architecture of Various Countries, by T. TALBOT BURY; The PRINCIPLES of DESIGN in Architecture, by E. L. GARBETT. In one handsome volume, half-bound (pp. 1,100), copiously illustrated, price 12s.

* * Sold separately, in two vols., as follows, price 6s. each, hf.-bd.

ANCIENT ARCHITECTURE. Containing Gwilt's Vitruvius and Aberdeen's Grecian Architecture.

N.B.—This is the only edition of VITRUVIUS procurable at a moderate price.

MODERN ARCHITECTURE. Containing the Orders, by Leeds; The Styles, by Bury; and Principles of Design, by Garbett.

The Young Architect's Book.

HINTS TO YOUNG ARCHITECTS. By GEORGE WIGHTWICK, Architect, Author of "The Palace of Architecture," &c. &c. New Edition, revised and enlarged. By G. HUSKISSON GUILLAUME, Architect. With numerous illustrations. 12mo. cloth boards, 4s.

Drawing for Builders and Students.

PRACTICAL RULES ON DRAWING for the OPERATIVE BUILDER and YOUNG STUDENT in ARCHITECTURE. By GEORGE PYNE, Author of a "Rudimentary Treatise on Perspective for Beginners." With 14 Plates, 4to, 7s. 6d., boards.

CONTENTS.—I. Practical Rules on Drawing—Outlines. II. Ditto—the Grecian and Roman Orders. III. Practical Rules on Drawing—Perspective. IV. Practical Rules on Light and Shade. V. Practical Rules on Colour, &c. &c.

Cottages, Villas, and Country Houses.

DESIGNS and EXAMPLES of COTTAGES, VILLAS, and COUNTRY HOUSES; being the Studies of several eminent Architects and Builders; consisting of Plans, Elevations, and Perspective Views; with approximate Estimates of the Cost of each. In 4to, with 67 plates, price 1l. 1s., cloth.

Builder's Price Book.

LOCKWOOD & CO.'S BUILDER'S AND CONTRACTOR'S PRICE BOOK—with which is incorporated ATCHLEY'S, and portions of the late G. R. BURNELL'S Builders' Price Books—for 1875, containing the latest prices of all kinds of Builders' Materials and Labour, and of all Trades connected with Building; with many useful and important Memoranda and Tables; Lists of the Members of the Metropolitan Board of Works, of Districts, District Officers, and District Surveyors, and the Metropolitan Bye-laws. The whole revised and edited by FRANCIS T. W. MILLER, Architect and Surveyor. Fcap. 8vo, strongly half-bound, price 4s.

Handbook of Specifications.

THE HANDBOOK OF SPECIFICATIONS; or, Practical Guide to the Architect, Engineer, Surveyor, and Builder, in drawing up Specifications and Contracts for Works and Constructions. Illustrated by Precedents of Buildings actually executed by eminent Architects and Engineers. Preceded by a Preliminary Essay, and Skeletons of Specifications and Contracts, &c., &c., and explained by numerous Lithograph Plates and Woodcuts. By Professor THOMAS L. DONALDSON, President of the Royal Institute of British Architects, Professor of Architecture and Construction, University College, London, M.I.B.A., Member of the various European Academies of the Fine Arts. With A REVIEW OF THE LAW OF CONTRACTS, and of the Responsibilities of Architects, Engineers, and Builders. By W. CUNNINGHAM GLEN, Barrister-at-Law, of the Middle Temple. 2 vols., 8vo, with upwards of 1100 pp. of text, and 33 Lithographic Plates, cloth, 2*l.* 2*s.* (Published at 4*l.*)

"In these two volumes of 1,100 pages (together), forty-four specifications of executed works are given, including the specifications for parts of the new Houses of Parliament, by Sir Charles Barry, and for the new Royal Exchange, by Mr. Tite, M.P.

"Amongst the other known buildings, the specifications of which are given, are the Wiltshire Lunatic Asylum (Wyatt and Brandon); Tothill Fields Prison (R. Abraham); the City Prison, Holloway (Bunning); the High School, Edinburgh (Hamilton); Clothworkers' Hall, London (Angel); Wellington Collège, Sandhurst (J. Shaw); Houses in Grosvenor Square, and elsewhere; St. George's Church, Doncaster (Scott); several works of smaller size by the Author, including Messrs. Shaw's Warehouse in Fetter Lane, a very successful elevation; the Newcastle-upon-Tyne Railway Station (J. Dobson); new Westminster Bridge (Page); the High Level Bridge, Newcastle (R. Stephenson); various works on the Great Northern Railway (Brydone); and one French specification for Houses in the Rue de Rivoli, Paris (MM. Armand, Hittorff, Pellechet, and Rohault de Fleury, architects). The majority of the specifications have illustrations in the shape of elevations and plans.

"About 140 pages of the second volume are appropriated to an exposition of the law in relation to the legal liabilities of engineers, architects, contractors, and builders, by Mr. W. Cunningham Glen, Barrister-at-law. Donaldson's Handbook of Specifications must be bought by all architects."—*Builder*.

Specifications for Practical Architecture.

SPECIFICATIONS FOR PRACTICAL ARCHITECTURE: A Guide to the Architect, Engineer, Surveyor, and Builder; with an Essay on the Structure and Science of Modern Buildings. By FREDERICK ROGERS, Architect. With numerous Illustrations. Demy 8vo, price 15*s.*, cloth. (Published at 1*l.* 10*s.*)

*A volume of specifications of a practical character being greatly required, and the old standard work of Alfred Bartholomew being out of print, the author, on the basis of that work, has produced the above. Some of the specifications he has so altered as to bring in the now universal use of concrete, the improvements in drainage, the use of iron, glass, asphalt, and other material. He has also inserted specifications of works that have been erected in his own practice.

The House-Owner's Estimator.

THE HOUSE-OWNER'S ESTIMATOR; or, What will it Cost to Build, Alter, or Repair? A Price-Book adapted to the Use of Unprofessional People as well as for the Architectural Surveyor and Builder. By the late JAMES D. SIMON, A.R.I.B.A. Edited and Revised by FRANCIS T. W. MILLER, Surveyor. With numerous Illustrations. Second Edition, with the prices carefully revised to 1875. Crown 8vo, cloth, price 3*s.* 6*d.*

CARPENTRY, TIMBER, &c.

Tredgold's Carpentry, new, enlarged, and cheaper Edition.

THE ELEMENTARY PRINCIPLES OF CARPENTRY : a Treatise on the Pressure and Equilibrium of Timber Framing, the Resistance of Timber, and the Construction of Floors, Arches, Bridges, Roofs, Uniting Iron and Stone with Timber, &c. To which is added an Essay on the Nature and Properties of Timber, &c., with Descriptions of the Kinds of Wood used in Building ; also numerous Tables of the Scantlings of Timber for different purposes, the Specific Gravities of Materials, &c. By THOMAS TREDGOLD, C.E. Edited by PETER BARLOW, F.R.S. Fifth Edition, corrected and enlarged. With 64 Plates (11 of which now first appear in this edition), Portrait of the Author, and several Woodcuts. In 1 vol., 4to, published at 2*l.* 2*s.*, reduced to 1*l.* 5*s.*, cloth.

"'Tredgold's Carpentry' ought to be in every architect's and every builder's library, and those who do not already possess it ought to avail themselves of the new issue."—*Builder*.

"A work whose monumental excellence must commend it wherever skilful carpentry is concerned. The Author's principles are rather confirmed than impaired by time, and, as now presented, combine the surest base with the most interesting display of progressive science. The additional plates are of great intrinsic value."—*Building News*.

Grandy's Timber Tables.

THE TIMBER IMPORTER'S, TIMBER MERCHANT'S, and BUILDER'S STANDARD GUIDE. By RICHARD E. GRANDY. Comprising :—An Analysis of Deal Standards, Home and Foreign, with comparative Values and Tabular Arrangements for Fixing Nett Landed Cost on Baltic and North American Deals, including all intermediate Expenses, Freight, Insurance, &c., &c. ; together with Copious Information for the Retailer and Builder. Second Edition. Carefully revised and corrected. 12mo, price 3*s.* 6*d.* cloth.

"Everything it pretends to be : built up gradually, it leads one from a forest to a treenail, and throws in, as a makeweight, a host of material concerning bricks, columns, cisterns, &c.—all that the class to whom it appeals requires."—*English Mechanic*.

"The only difficulty we have is as to what is NOT in its pages. What we have tested of the contents, taken at random, is invariably correct."—*Illustrated Builder's Journal*.

Tables for Packing-Case Makers.

PACKING-CASE TABLES ; showing the number of Superficial Feet in Boxes or Packing-Cases, from six inches square and upwards. Compiled by WILLIAM RICHARDSON, Accountant. Oblong 4to, cloth, price 3*s.* 6*d.*

"Will save much labour and calculation to packing-case makers and those who use packing-cases."—*Grocer*. "Invaluable labour-saving tables."—*Ironmonger*.

Nicholson's Carpenter's Guide.

THE CARPENTER'S NEW GUIDE ; or, BOOK of LINES for CARPENTERS : comprising all the Elementary Principles essential for acquiring a knowledge of Carpentry. Founded on the late PETER NICHOLSON's standard work. A new Edition, revised by ARTHUR ASHPITEL, F.S.A., together with Practical Rules on Drawing, by GEORGE PYNE. With 74 Plates, 4to, 1*l.* 1*s.* cloth.

Dowsing's Timber Merchant's Companion.

THE TIMBER MERCHANT'S AND BUILDER'S COMPANION; containing New and Copious Tables of the Reduced Weight and Measurement of Deals and Battens, of all sizes, from One to a Thousand Pieces, and the relative Price that each size bears per Lineal Foot to any given Price per Petersburgh Standard Hundred; the Price per Cube Foot of Square Timber to any given Price per Load of 50 Feet; the proportionate Value of Deals and Battens by the Standard, to Square Timber by the Load of 50 Feet; the readiest mode of ascertaining the Price of Scantling per Lineal Foot of any size, to any given Figure per Cube Foot. Also a variety of other valuable information. By WILLIAM DOWSING, Timber Merchant. Second Edition. Crown 8vo, 3s. cloth.

"Everything is as concise and clear as it can possibly be made. There can be no doubt that every timber merchant and builder ought to possess it."—*Hull Advertiser*.

Timber Freight Book.

THE TIMBER IMPORTERS' AND SHIPOWNERS' FREIGHT BOOK: Being a Comprehensive Series of Tables for the Use of Timber Importers, Captains of Ships, Shipbrokers, Builders, and all Dealers in Wood whatsoever. By WILLIAM RICHARDSON, Timber Broker, author of "Packing Case Tables," &c. Crown 8vo, cloth, price 6s.

MECHANICS, &c.

Horton's Measurer.

THE COMPLETE MEASURER; setting forth the Measurement of Boards, Glass, &c., &c.; Unequal-sided, Square-sided, Octagonal-sided, Round Timber and Stone, and Standing Timber. With just allowances for the bark in the respective species of trees, and proper deductions for the waste in hewing the trees, &c.; also a Table showing the solidity of hewn or eight-sided timber, or of any octagonal-sided column. Compiled for the accommodation of Timber-growers, Merchants, and Surveyors, Stonemasons, Architects, and others. By RICHARD HORTON. Second edition, with considerable and valuable additions, 12mo, strongly bound in leather, 5s.

"The office of the architect, engineer, building surveyor, or land agent that is without this excellent and useful work cannot truly be considered perfect in its furnishing."—*Irish Builder*.

"We have used the improved and other tables in this volume, and have not observed any unfairness or inaccuracy."—*Builder*.

"The tables we have tested are accurate. . . . To the builder and estate agents this work will be most acceptable."—*British Architect*.

"Not only are the best methods of measurement shown, and in some instances illustrated by means of woodcuts, but the erroneous systems pursued by dishonest dealers are fully exposed. . . . The work must be considered to be a valuable addition to every gardener's library."—*Garden*.

Superficial Measurement.

THE TRADESMAN'S GUIDE TO SUPERFICIAL MEASUREMENT. Tables calculated from 1 to 200 inches in length, by 1 to 108 inches in breadth. For the use of Architects, Surveyors, Engineers, Timber Merchants, Builders, &c. By JAMES HAWKINGS. Fcp. 3s. 6d. cloth.

Mechanic's Workshop Companion.

THE OPERATIVE MECHANIC'S WORKSHOP COMPANION, and THE SCIENTIFIC GENTLEMAN'S PRACTICAL ASSISTANT; comprising a great variety of the most useful Rules in Mechanical Science; with numerous Tables of Practical Data and Calculated Results. By W. TEMPLETON, Author of "The Engineer's, Millwright's, and Machinist's Practical Assistant." Eleventh Edition, with Mechanical Tables for Operative Smiths, Millwrights, Engineers, &c.; together with several Useful and Practical Rules in Hydraulics and Hydrodynamics, a variety of Experimental Results, and an Extensive Table of Powers and Roots. 11 Plates. 12mo, 5s. bound.

"As a text-book of reference, in which mechanical and commercial demands are judiciously met, TEMPLETON'S COMPANION stands unrivalled."—*Mechanics Magazine*.

"Admirably adapted to the wants of a very large class. It has met with great success in the engineering workshop, as we can testify; and there are a great many men who, in a great measure, owe their rise in life to this little work."—*Building News*.

Engineer's Assistant.

THE ENGINEER'S, MILLWRIGHT'S, and MACHINIST'S PRACTICAL ASSISTANT; comprising a Collection of Useful Tables, Rules, and Data. Compiled and Arranged, with Original Matter, by W. TEMPLETON. 5th Edition. 18mo, 2s. 6d. cloth.

"So much varied information compressed into so small a space, and published at a price which places it within the reach of the humblest mechanic, cannot fail to command the sale which it deserves. With the utmost confidence we commend this book to the attention of our readers."—*Mechanics Magazine*.

"Every mechanic should become the possessor of the volume, and a more suitable present to an apprentice to any of the mechanical trades could not possibly be made."—*Building News*.

Designing, Measuring, and Valuing.

THE STUDENT'S GUIDE to the PRACTICE of MEASURING, and VALUING ARTIFICERS' WORKS; containing Directions for taking Dimensions, Abstracting the same, and bringing the Quantities into Bill, with Tables of Constants, and copious Memoranda for the Valuation of Labour and Materials in the respective Trades of Bricklayer and Slater, Carpenter and Joiner, Painter and Glazier, Paperhanger, &c. With 43 Plates and Woodcuts. Originally edited by EDWARD DOBSON, Architect. New Edition, re-written, with Additions on Mensuration and Construction, and useful Tables for facilitating Calculations and Measurements. By E. WYNNDHAM TARN, M.A., 8vo, 10s. 6d. cloth.

"This useful book should be in every architect's and builder's office. It contains a vast amount of information absolutely necessary to be known."—*The Irish Builder*.

"We have failed to discover anything connected with the building trade, from excavating foundations to bell-hanging, that is not fully treated upon in this valuable work."—*The Artizan*.

"Mr. Tarn has well performed the task imposed upon him, and has made many further and valuable additions, embodying a large amount of information relating to the technicalities and modes of construction employed in the several branches of the building trade."—*Colliery Guardian*.

"Altogether the book is one which well fulfils the promise of its title-page, and we can thoroughly recommend it to the class for whose use it has been compiled. Mr. Tarn's additions and revisions have much increased the usefulness of the work, and have especially augmented its value to students."—*Engineering*.

MATHEMATICS, &c.

Gregory's Practical Mathematics.

MATHEMATICS for PRACTICAL MEN ; being a Common-place Book of Pure and Mixed Mathematics. Designed chiefly for the Use of Civil Engineers, Architects, and Surveyors. Part I. PURE MATHEMATICS—comprising Arithmetic, Algebra, Geometry, Mensuration, Trigonometry, Conic Sections, Properties of Curves. Part II. MIXED MATHEMATICS—comprising Mechanics in general, Statics, Dynamics, Hydrostatics, Hydrodynamics, Pneumatics, Mechanical Agents, Strength of Materials. With an Appendix of copious Logarithmic and other Tables. By OLINTHUS GREGORY, LL.D., F.R.A.S. Enlarged by HENRY LAW, C.E. 4th Edition, carefully revised and corrected by J. R. YOUNG, formerly Professor of Mathematics, Belfast College ; Author of "A Course of Mathematics," &c. With 13 Plates. Medium 8vo, 1*l.* 1*s.* cloth.

"As a standard work on mathematics it has not been excelled."—*Artisan*.

"The engineer or architect will here find ready to his hand, rules for solving nearly every mathematical difficulty that may arise in his practice. The rules are in all cases explained by means of examples, in which every step of the process is clearly worked out."—*Builder*.

"One of the most serviceable books to the practical mechanics of the country. In the edition just brought out, the work has again been revised by Professor Young. He has modernised the notation throughout, introduced a few paragraphs here and there, and corrected the numerous typographical errors which have escaped the eyes of the former Editor. The book is now as complete as it is possible to make it. It is an instructive book for the student, and a Text-book for him who having once mastered the subjects it treats of, needs occasionally to refresh his memory upon them."—*Building News*.

The Metric System.

A SERIES OF METRIC TABLES, in which the British Standard Measures and Weights are compared with those of the Metric System at present in use on the Continent. By C. H. DOWLING, C. E. Second Edition, revised and enlarged. 8vo, 10*s.* 6*d.* strongly bound.

"Mr. Dowling's Tables, which are well put together, come just in time as a ready reckoner for the conversion of one system into the other."—*Athenæum*.

"Their accuracy has been certified by Professor Airy, the Astronomer-Royal."—*Builder*.

"Resolution 8.—That advantage will be derived from the recent publication of Metric Tables, by C. H. Dowling, C.E."—*Report of Section F, British Association, Bath*.

Comprehensive Weight Calculator.

THE WEIGHT CALCULATOR ; being a Series of Tables upon a New and Comprehensive Plan, exhibiting at one Reference the exact Value of any Weight from 1*lb.* to 15 tons, at 300 Progressive Rates, from 1 Penny to 168 Shillings per cwt., and containing 186,000 Direct Answers, which with their Combinations, consisting of a single addition (mostly to be performed at sight), will afford an aggregate of 10,266,000 Answers ; the whole being calculated and designed to ensure Correctness and promote Despatch. By HENRY HARBEN, Accountant, Sheffield, Author of 'The Discount Guide.' An entirely New Edition, carefully revised. Royal 8vo. strongly half-bound, 30*s.* [Just Published.

Inwood's Tables, greatly enlarged and improved.

TABLES FOR THE PURCHASING of ESTATES, Freehold, Copyhold, or Leasehold; Annuities, Advowsons, &c., and for the Renewing of Leases held under Cathedral Churches, Colleges, or other corporate bodies; for Terms of Years certain, and for Lives; also for Valuing Reversionary Estates, Deferred Annuities, Next Presentations, &c., together with Smart's Five Tables of Compound Interest, and an Extension of the same to Lower and Intermediate Rates. By WILLIAM INWOOD, Architect. The 20th edition, with considerable additions, and new and valuable Tables of Logarithms for the more Difficult Computations of the Interest of Money, Discount, Annuities, &c., by M. FÉDOR THOMAN, of the Société Crédit Mobilier of Paris. 12mo, 8s. cloth.

* * This edition (the 20th) differs in many important particulars from former ones. The changes consist, first, in a more convenient and systematic arrangement of the original Tables, and in the removal of certain numerical errors which a very careful revision of the whole has enabled the present editor to discover; and secondly, in the extension of practical utility conferred on the work by the introduction of Tables now inserted for the first time. This new and important matter is all so much actually added to INWOOD'S TABLES; nothing has been abstracted from the original collection: so that those who have been long in the habit of consulting INWOOD for any special professional purpose will, as heretofore, find the information sought still in its pages.

"Those interested in the purchase and sale of estates, and in the adjustment of compensation cases, as well as in transactions in annuities, life insurances, &c., will find the present edition of eminent service."—*Engineering*.

Geometry for the Architect, Engineer, &c.

PRACTICAL GEOMETRY, for the Architect, Engineer, and Mechanic; giving Rules for the Delineation and Application of various Geometrical Lines, Figures and Curves. By E. W. TARN, M.A., Architect, Author of "The Science of Building," &c. With 164 Illustrations. Demy 8vo. 12s. 6d.

"No book with the same objects in view has ever been published in which the clearness of the rules laid down and the illustrative diagrams have been so satisfactory."—*Scotsman*.

Compound Interest and Annuities.

THEORY of COMPOUND INTEREST and ANNUITIES; with Tables of Logarithms for the more Difficult Computations of Interest, Discount, Annuities, &c., in all their Applications and Uses for Mercantile and State Purposes. With an elaborate Introduction. By FÉDOR THOMAN, of the Société Crédit Mobilier, Paris. 12mo, cloth, 5s.

"A very powerful work, and the Author has a very remarkable command of his subject."—*Professor A. de Morgan*.

"We recommend it to the notice of actuaries and accountants."—*Athenæum*.

SCIENCE AND ART.

The Military Sciences.

AIDE-MÉMOIRE to the MILITARY SCIENCES. Framed from Contributions of Officers and others connected with the different Services. Originally edited by a Committee of the Corps of Royal Engineers. Second Edition, most carefully revised by an Officer of the Corps, with many additions; containing nearly 350 Engravings and many hundred Woodcuts. 3 vols. royal 8vo, extra cloth boards, and lettered, price 4*l.* 10*s.*

"A compendious encyclopædia of military knowledge."—*Edinburgh Review*.

"The most comprehensive work of reference to the military and collateral sciences."
—*Volunteer Service Gazette*.

Field Fortification.

A TREATISE on FIELD FORTIFICATION, the ATTACK of FORTRESSES, MILITARY, MINING, and RECON-NOITRING. By Colonel I. S. MACAULAY, late Professor of Fortification in the R. M. A., Woolwich. Sixth Edition, crown 8vo, cloth, with separate Atlas of 12 Plates, price 12*s.* complete.

Field Fortification.

HANDBOOK OF FIELD FORTIFICATION, intended for the Guidance of Officers preparing for Promotion, and especially adapted to the requirements of Beginners. By Major W. W. KNOLLYS, F.R.G.S., 93rd Sutherland Highlanders, &c. With 163 Woodcuts. Crown 8vo, 3*s.* 6*d.* cloth.

Storms.

STORMS: their Nature, Classification, and Laws, with the Means of Predicting them by their Embodiments, the Clouds. By WILLIAM BLASIUS. With Coloured Plates and numerous Wood Engravings. Crown 8vo, 12*s.* 6*d.* cloth boards.

Light-Houses.

EUROPEAN LIGHT-HOUSE SYSTEMS; being a Report of a Tour of Inspection made in 1873. By Major GEORGE H. ELLIOT, Corps of Engineers, U.S.A. Illustrated by 51 Engravings and 31 Woodcuts in the Text. 8vo, 21*s.* cloth.

Dye-Wares and Colours.

THE MANUAL of COLOURS and DYE-WARES: their Properties, Applications, Valuation, Impurities, and Sophistications. For the Use of Dyers, Printers, Dry Salters, Brokers, &c. By J. W. SLATER. Post 8vo, cloth, price 7*s.* 6*d.*

"A complete encyclopædia of the *materia tinctoria*. The information given respecting each article is full and precise, and the methods of determining the value of articles such as these, so liable to sophistication, are given with clearness, and are practical as well as valuable."—*Chemist and Druggist*.

Electricity.

A MANUAL of ELECTRICITY ; including Galvanism, Magnetism, Diamagnetism, Electro-Dynamics, Magno-Electricity, and the Electric Telegraph. By HENRY M. NOAD, Ph.D., F.C.S., Lecturer on Chemistry at St. George's Hospital. Fourth Edition, entirely rewritten. Illustrated by 500 Woodcuts. 8vo, 1*l.* 4*s.* cloth.

"The commendations already bestowed in the pages of the *Lancet* on the former editions of this work are more than ever merited by the present. The accounts given of electricity and galvanism are not only complete in a scientific sense, but, which is a rarer thing, are popular and interesting."—*Lancet*.

Text-Book of Electricity.

THE STUDENT'S TEXT-BOOK OF ELECTRICITY. By HENRY M. NOAD, Ph.D., Lecturer on Chemistry at St. George's Hospital. New Edition revised and enlarged, with additions on Telegraphy, by G. E. PREECE, Esq. Upwards of 400 Illustrations. [*In Preparation.*]

Rudimentary Magnetism.

RUDIMENTARY MAGNETISM : being a concise exposition of the general principles of Magnetical Science, and the purposes to which it has been applied. By Sir W. SNOW HARRIS, F.R.S. New and enlarged Edition, with considerable additions by Dr. NOAD, Ph.D. With 165 Woodcuts. 12mo, cloth, 4*s.* 6*d.*

"There is a good index, and this volume of 412 pages may be considered the best possible manual on the subject of magnetism."—*Mechanics' Magazine*.

"As concise and lucid an exposition of the phenomena of magnetism as we believe it is possible to write."—*English Mechanic*.

"Not only will the scientific student find this volume an invaluable book of reference, but the general reader will find in it as much to interest as to inform his mind. Though a strictly scientific work, its subject is handled in a simple and readable style."—*Illustrated Review*.

Chemical Analysis.

THE COMMERCIAL HANDBOOK of CHEMICAL ANALYSIS ; or Practical Instructions for the determination of the Intrinsic or Commercial Value of Substances used in Manufactures, in Trades, and in the Arts. By A. NORMANDY, Author of "Practical Introduction to Rose's Chemistry," and Editor of Rose's "Treatise of Chemical Analysis." *New Edition.* Enlarged, and to a great extent re-written, by Henry M. Noad, Ph.D., F.R.S. With numerous Illustrations. Crown 8vo, 12*s.* 6*d.* cloth.

[*Just ready.*]

"We recommend this book to the careful perusal of every one ; it may be truly affirmed to be of universal interest, and we strongly recommend it to our readers as a guide, alike indispensable to the housewife as to the pharmaceutical practitioner."—*Medical Times*.

"The very best work on the subject the English press has yet produced."—*Mechanics' Magazine*.

Mollusca.

A MANUAL OF THE MOLUSCA ; being a Treatise on Recent and Fossil Shells. By Dr. S. P. WOODWARD, A.L.S. With Appendix by RALPH TATE, A.L.S. F.G.S. With numerous Plates and 300 Woodcuts. Third Edition. Crown 8vo, 7*s.* 6*d.* cloth gilt.

Clocks, Watches, and Bells.

RUDIMENTARY TREATISE on CLOCKS, WATCHES, and BELLS. By Sir EDMUND BECKETT, Bart. (late E. B. Denison), LL.D., Q.C., F.R.A.S., Author of "Astronomy without Mathematics," &c. Sixth edition, thoroughly revised and enlarged, with numerous Illustrations. Limp cloth (No. 67, Weale's Series), 4s. 6d.; cloth boards, 5s. 6d.

"As a popular, and, at the same time, practical treatise on clocks and bells, it is unapproached."—*English Mechanic*.

"The best work on the subject probably extant So far as we know it has no competitor worthy of the name. The treatise on bells is undoubtedly the best in the language. It shows that the author has contributed very much to their modern improvement, if indeed he has not revived this art, which was decaying here To call it a rudimentary treatise is a misnomer, at least as respects clocks and bells. It is something more. It is the most important work of its kind in English."—*Engineering*.

"The only modern treatise on clock-making."—*Horological Journal*.

"Without having any special interest in the subject, and even without possessing any general aptitude for mechanical studies, a reader must be very unintelligent who cannot find matter to engage his attention in this work. The little book now appears revised and enlarged, being one of the most praiseworthy volumes in Weale's admirable scientific and educational series."—*Daily Telegraph*.

"We do not know whether to wonder most at the extraordinary cheapness of this admirable treatise on clocks, by the most able authority on such a subject, or the thorough completeness of his work even to the minutest details. The chapter on bells is singular and amusing, and will be a real treat even to the uninitiated general reader. The illustrations, notes, and indices, make the work completely perfect of its kind."—*Standard*.

"There is probably no book in the English language on a technical subject so easy to read, and to read through, as the treatise on clocks, watches, and bells, written by the eminent Parliamentary Counsel, Mr. E. B. Denison—now Sir Edmund Beckett, Bart."—*Architect*.

Science and Scripture.

SCIENCE ELUCIDATIVE OF SCRIPTURE, AND NOT ANTAGONISTIC TO IT; being a Series of Essays on—1. Alleged Discrepancies; 2. The Theory of the Geologists and Figure of the Earth; 3. The Mosaic Cosmogony; 4. Miracles in general—Views of Hume and Powell; 5. The Miracle of Joshua—Views of Dr. Colenso: The Supernaturally Impossible; 6. The Age of the Fixed Stars—their Distances and Masses. By Professor J. R. YOUNG, Author of "A Course of Elementary Mathematics," &c. &c. Fcap. 8vo, price 5s. cloth lettered.

"Professor Young's examination of the early verses of Genesis, in connection with modern scientific hypotheses, is excellent."—*English Churchman*.

"Distinguished by the true spirit of scientific inquiry, by great knowledge, by keen logical ability, and by a style peculiarly clear, easy, and energetic."—*Nonconformist*.

"No one can rise from its perusal without being impressed with a sense of the singular weakness of modern scepticism."—*Baptist Magazine*.

"A valuable contribution to controversial theological literature."—*City Press*.

Practical Philosophy.

A SYNOPSIS of PRACTICAL PHILOSOPHY. By the Rev. JOHN CARR, M.A., late Fellow of Trin. Coll., Cambridge. Second Edition. 18mo, 5s. cloth.

Dr. Lardner's Museum of Science and Art.

THE MUSEUM OF SCIENCE AND ART. Edited by DIONYSIUS LARDNER, D.C.L., formerly Professor of Natural Philosophy and Astronomy in University College, London. CONTENTS: The Planets; are they inhabited Worlds?—Weather Prognostics—Popular Fallacies in Questions of Physical Science—Latitudes and Longitudes—Lunar Influences—Meteoric Stones and Shooting Stars—Railway Accidents—Light—Common Things:—Air—Locomotion in the United States—Cometary Influences—Common Things: Water—The Potter's Art—Common Things: Fire—Locomotion and Transport, their Influence and Progress—The Moon—Common Things: The Earth—The Electric Telegraph—Terrestrial Heat—The Sun—Earthquakes and Volcanoes—Barometer, Safety Lamp, and Whitworth's Micrometric Apparatus—Steam—The Steam Engine—The Eye—The Atmosphere—Time—Common Things: Pumps—Common Things: Spectacles, the Kaleidoscope—Clocks and Watches—Microscopic Drawing and Engraving—Locomotive—Thermometer—New Planets: Leverrier and Adams's Planet—Magnitude and Minuteness—Common Things: The Almanack—Optical Images—How to observe the Heavens—Common Things: the Looking-glass—Stellar Universe—The Tides—Colour—Common Things: Man—Magnifying Glasses—Instinct and Intelligence—The Solar Microscope—The Camera Lucida—The Magic Lantern—The Camera Obscura—The Microscope—The White Ants: their Manners and Habits—The Surface of the Earth, or First Notions of Geography—Science and Poetry—The Bee—Steam Navigation—Electro-Motive Power—Thunder, Lightning, and the Aurora Borealis—The Printing Press—The Crust of the Earth—Comets—The Stereoscope—The Pre-Adamite Earth—Eclipses—Sound. With upwards of 1200 Engravings on Wood. In 6 Double Volumes, handsomely bound in cloth, gilt, price £1 1s.

"The 'Museum of Science and Art' is the most valuable contribution that has ever been made to the Scientific Instruction of every class of society."—*Sir David Brewster in the North British Review.*

"Whether we consider the liberality and beauty of the illustrations, the charm of the writing, or the durable interest of the matter, we must express our belief that there is hardly to be found among the new books, one that would be welcomed by people of so many ages and classes as a valuable present."—*Examiner.*

* * *Separate books formed from the above, suitable for Workmen's Libraries, Science Classes, &c.*

COMMON THINGS EXPLAINED. With 233 Illustrations, 5s. cloth.

THE ELECTRIC TELEGRAPH POPULARIZED. 100 Illustrations, 1s. 6d. cloth.

THE MICROSCOPE. With 147 Illustrations, 2s. cloth.

POPULAR GEOLOGY. With 201 Illustrations, 2s. 6d. cloth.

POPULAR PHYSICS. With 85 Illustrations. 2s. 6d. cloth.

POPULAR ASTRONOMY. With 182 Illustrations, 4s. 6d. cloth.

STEAM AND ITS USES. With 89 Illustrations, 2s. cloth.

THE BEE AND WHITE ANTS. With 135 Illustrations, cloth, 2s.

DR. LARDNER'S SCIENTIFIC HANDBOOKS.

Astronomy.

THE HANDBOOK OF ASTRONOMY. By DIONYSIUS LARDNER, D.C.L., formerly Professor of Natural Philosophy and Astronomy in University College, London. Fourth Edition. Revised and Edited by EDWIN DUNKIN, F.R.A.S., Superintendent of the Altazimuth Department, Royal Observatory, Greenwich. With 38 plates and upwards of 100 Woodcuts. In one thick vol., Crown 8vo, price 9s. 6d. cloth.

"We can cordially recommend it to all those who desire to possess a complete manual of the science and practice of astronomy."—*Astronomical Reporter*.

Optics.

THE HANDBOOK OF OPTICS. New Edition. Edited by T. OLVER HARDING, B.A. Lond., of University College, London. With 298 Illustrations. Small 8vo, cloth, 448 pages, price 5s.

Electricity.

THE HANDBOOK of ELECTRICITY, MAGNETISM, and ACOUSTICS. New Edition. Edited by GEO. CAREY FOSTER, B.A., F.C.S. With 400 Illustrations. Small 8vo, cloth, price 5s.

"The book could not have been entrusted to any one better calculated to preserve the terse and lucid style of Lardner, while correcting his errors and bringing up his work to the present state of scientific knowledge."—*Popular Science Review*.

Mechanics.

THE HANDBOOK OF MECHANICS. Revised and enlarged by B. LOEWY, F.R.A.S. [Reprinting.

Hydrostatics.

THE HANDBOOK of HYDROSTATICS and PNEUMATICS. New Edition, Revised and Enlarged by BENJAMIN LOEWY, F.R.A.S. With numerous Illustrations. 5s. [Just published.

Heat.

THE HANDBOOK OF HEAT. New Edition, Re-written and Enlarged. By BENJAMIN LOEWY, F.R.A.S. [Nearly Ready.

Animal Physics.

THE HANDBOOK OF ANIMAL PHYSICS. With 520 Illustrations. New edition, small 8vo, cloth, 7s. 6d. 732 pages.

Electric Telegraph.

THE ELECTRIC TELEGRAPH. New Edition. Revised and Re-written by E. B. BRIGHT, F.R.A.S. 140 Illustrations. Small 8vo, 2s. 6d. cloth.

"One of the most readable books extant on the Electric Telegraph."—*Eng. Mechanic*.

NATURAL PHILOSOPHY FOR SCHOOLS. By DR. LARDNER. 328 Illustrations. Fifth Edition. 1 vol. 3s. 6d. cloth.

"A very convenient class-book for junior students in private schools. It is intended to convey, in clear and precise terms, general notions of all the principal divisions of Physical Science."—*British Quarterly Review*.

ANIMAL PHYSIOLOGY FOR SCHOOLS. By DR. LARDNER.

With 190 Illustrations. Second Edition. 1 vol. 3s. 6d. cloth.

"Clearly written, well arranged, and excellently illustrated."—*Gardener's Chronicle*.

Geology and Genesis Harmonised.

THE TWIN RECORDS of CREATION; or, Geology and Genesis, their Perfect Harmony and Wonderful Concord. By GEORGE W. VICTOR LE VAUX. With numerous Illustrations. Fcap. 8vo, price 5s. cloth.

"We can recommend Mr. Le Vaux as an able and interesting guide to a popular appreciation of geological science."—*Spectator*.

"The author combines an unbounded admiration of science with an unbounded admiration of the Written Record."—*London Review*.

"No real difficulty is shirked, and no sophistry is left unexposed."—*The Rock*.

Geology, Physical.

PHYSICAL GEOLOGY. (Partly based on Major-General Portlock's Rudiments of Geology.) By RALPH TATE, A.L.S., F.G.S. Numerous Woodcuts. 12mo, 2s.

Geology, Historical.

HISTORICAL GEOLOGY. (Partly based on Major-General Portlock's Rudiments of Geology.) By RALPH TATE, A.L.S., F.G.S. Numerous Woodcuts. 12mo, 2s. 6d.

* * Or PHYSICAL and HISTORICAL GEOLOGY, bound in One Volume, price 5s.

Wood-Carving.

INSTRUCTIONS in WOOD-CARVING, for Amateurs; with Hints on Design. By A LADY. In emblematic wrapper, handsomely printed, with Ten large Plates, price 2s. 6d.

"The handicraft of the wood-carver, so well as a book can impart it, may be learnt from 'A Lady's' publication."—*Athenæum*.

"A real practical guide. It is very complete."—*Literary Churchman*.

"The directions given are plain and easily understood, and it forms a very good introduction to the practical part of the carver's art."—*English Mechanic*.

Popular Work on Painting.

PAINTING POPULARLY EXPLAINED; with Historical Sketches of the Progress of the Art. By THOMAS JOHN GULLICK, Painter, and JOHN TIMBS, F.S.A. Second Edition, revised and enlarged. With Frontispiece and Vignette. In small 8vo, 6s. cloth.

* * This Work has been adopted as a Prize-book in the Schools of Art at South Kensington.

"A work that may be advantageously consulted. Much may be learned, even by those who fancy they do not require to be taught, from the careful perusal of this unpretending but comprehensive treatise."—*Art Journal*.

"A valuable book, which supplies a want. It contains a large amount of original matter, agreeably conveyed, and will be found of value, as well by the young artist seeking information as by the general reader. We give a cordial welcome to the book, and augur for it an increasing reputation."—*Builder*.

Grammar of Colouring.

A GRAMMAR OF COLOURING, applied to Decorative Painting and the Arts. By GEORGE FIELD. New edition, enlarged and adapted to the use of the Ornamental Painter and Designer, by ELLIS A. DAVIDSON. With new Coloured Diagrams and numerous Engravings on Wood. 12mo, 3s. cloth boards.

"One of the most useful of student's books, and probably the best known of the few we have on the subject."—*Architect*.

"The book is a most useful *résumé* of the properties of pigments."—*Builder*.

"This treatise forms a most valuable *vade mecum* for the ornamental painter and designer."—*Scotsman*.

Delamotte's Works on Illumination & Alphabets.

A PRIMER OF THE ART OF ILLUMINATION ; for the use of Beginners : with a Rudimentary Treatise on the Art, Practical Directions for its Exercise, and numerous Examples taken from Illuminated MSS., printed in Gold and Colours. By F. DELAMOTTE. Small 4to, price 9s. Elegantly bound, cloth antique.

"A handy book, beautifully illustrated ; the text of which is well written, and calculated to be useful. . . . The examples of ancient MSS. recommended to the student, which, with much good sense, the author chooses from collections accessible to all, are selected with judgment and knowledge, as well as taste."—*Athenæum*.

ORNAMENTAL ALPHABETS, ANCIENT and MEDIÆVAL ; from the Eighth Century, with Numerals ; including Gothic, Church-Text, large and small, German, Italian, Arabesque, Initials for Illumination, Monograms, Crosses, &c. &c., for the use of Architectural and Engineering Draughtsmen, Missal Painters, Masons, Decorative Painters, Lithographers, Engravers, Carvers, &c. &c. &c. Collected and engraved by F. DELAMOTTE, and printed in Colours. Royal 8vo, oblong, price 4s. cloth.

"A well-known engraver and draughtsman has enrolled in this useful book the result of many years' study and research. For those who insert enamelled sentences round gilded chalices, who blazon shop legends over shop-doors, who letter church walls with pithy sentences from the Decalogue, this book will be useful."—*Athenæum*.

EXAMPLES OF MODERN ALPHABETS, PLAIN and ORNAMENTAL ; including German, Old English, Saxon, Italic, Perspective, Greek, Hebrew, Court Hand, Engrossing, Tuscan, Riband, Gothic, Rustic, and Arabesque ; with several Original Designs, and an Analysis of the Roman and Old English Alphabets, large and small, and Numerals, for the use of Draughtsmen, Surveyors, Masons, Decorative Painters, Lithographers, Engravers, Carvers, &c. Collected and engraved by F. DELAMOTTE, and printed in Colours. Royal 8vo, oblong, price 4s. cloth.

"To artists of all classes, but more especially to architects and engravers, this very handsome book will be invaluable. There is comprised in it every possible shape into which the letters of the alphabet and numerals can be formed, and the talent which has been expended in the conception of the various plain and ornamental letters is wonderful."—*Standard*.

MEDIÆVAL ALPHABETS AND INITIALS FOR ILLUMINATORS. By F. DELAMOTTE, Illuminator, Designer, and Engraver on Wood. Containing 21 Plates, and Illuminated Title, printed in Gold and Colours. With an Introduction by J. WILLIS BROOKS. Small 4to, 6s. cloth gilt.

"A volume in which the letters of the alphabet come forth glorified in gilding and all the colours of the prism interwoven and intertwined and intermingled, sometimes with a sort of rainbow arabesque. A poem emblazoned in these characters would be only comparable to one of those delicious love letters symbolized in a bunch of flowers well selected and cleverly arranged."—*Sun*.

THE EMBROIDERER'S BOOK OF DESIGN ; containing Initials, Emblems, Cyphers, Monograms, Ornamental Borders, Ecclesiastical Devices, Mediæval and Modern Alphabets, and National Emblems. Collected and engraved by F. DELAMOTTE, and printed in Colours. Oblong royal 8vo, 2s. 6d. in ornamental boards.

AGRICULTURE, &c.

Youatt and Burn's Complete Grazier.

THE COMPLETE GRAZIER, and FARMER'S and CATTLE-BREEDER'S ASSISTANT. A Compendium of Husbandry. By WILLIAM YOUATT, ESQ., V.S. 11th Edition, enlarged by ROBERT SCOTT BURN, Author of "The Lessons of My Farm," &c. One large 8vo volume, 784 pp. with 215 Illustrations. 1*l.* 1*s.* half-bd.

"The standard and text-book, with the farmer and grazier."—*Farmer's Magazine.*

"A valuable repository of intelligence for all who make agriculture a pursuit, and especially for those who aim at keeping pace with the improvements of the age."—*Bell's Weekly Messenger.*

"A treatise which will remain a standard work on the subject as long as British agriculture endures."—*Mark Lane Express.*

"One of the best books of reference that can be contained in the agriculturist's library. The word 'complete' expresses its character; since every detail of the subject finds a place, treated upon, and explained, in a clear, comprehensive, and practical manner."—*Magnet.*

Spooner on Sheep.

SHEEP; THE HISTORY, STRUCTURE, ECONOMY, AND DISEASES OF. By W. C. SPOONER, M.R.V.C., &c. Third Edition, considerably enlarged; with numerous fine engravings, including some specimens of New and Improved Breeds. Fcp. 8vo. 366 pp., price 6*s.* cloth.

"The book is decidedly the best of the kind in our language."—*Scotsman.*

"A reliable text-book."—*Stamford Mercury.*

"Mr. Spooner has conferred upon the agricultural class a lasting benefit by embodying in this work the improvements made in sheep stock by such men as Humphreys, Rawlence, Howard, and others."—*Hampshire Advertiser.*

"The work should be in possession of every flock-master."—*Banbury Guardian.*

"We can confidently recommend the work as useful and reliable, and of much practical utility to the class for whom it is intended."—*Salisbury and Winchester Journal.*

"Mr. Spooner has conferred a boon on agriculturists generally, and the farmer's library will be incomplete which does not include so admirable a guide to a very important branch of the business."—*Dorset County Chronicle.*

Scott Burn's System of Modern Farming.

OUTLINES OF MODERN FARMING. By R. SCOTT BURN. Soils, Manures, and Crops—Farming and Farming Economy, Historical and Practical—Cattle, Sheep, and Horses—Management of the Dairy, Pigs, and Poultry, with Notes on the Diseases of Stock—Utilisation of Town-Sewage, Irrigation, and Reclamation of Waste Land. New Edition. In 1 vol. 1250 pp., half-bound, profusely Illustrated, price 12*s.*

"There is sufficient stated within the limits of this treatise to prevent a farmer from going far wrong in any of his operations. . . . The author has had great personal experience, and his opinions are entitled to every respect."—*Observer.*

Horton's Underwood and Woodland Tables.

TABLES FOR PLANTING AND VALUING UNDERWOOD AND WOODLAND; also Lineal, Superficial, Cubical, Wages, Marketing, and Decimal Tables. Together with Tables for Converting Land-measure from one denomination to another, and Instructions for Measuring Round Timber. By RICHARD HORTON. 12mo. 2*s.* strongly bound in leather.

Ewart's Land Improvers' Pocket-Book.

THE LAND IMPROVERS' POCKET-BOOK OF FORMULÆ, TABLES, and MEMORANDA, required in any Computation relating to the Permanent Improvement of Landed Property. By JOHN EWART, Land Surveyor and Agricultural Engineer. Royal 32mo, oblong, leather, gilt edges, with elastic band, 4s.

"A compendium long required by land surveyors, agricultural engineers, &c."—*Sussex Daily News.*

"It is admirably calculated to serve the purpose for which it was intended."—*Scotsman.*

"A compendious and handy little volume."—*Spectator.*

Hudson's Tables for Land Valuers.

THE LAND VALUER'S BEST ASSISTANT: being Tables, on a very much improved Plan, for Calculating the Value of Estates. To which are added, Tables for reducing Scotch, Irish, and Provincial Customary Acres to Statute Measure; also, Tables of Square Measure, and of the various Dimensions of an Acre in Perches and Yards, by which the Contents of any Plot of Ground may be ascertained without the expense of a regular Survey; &c. By R. HUDSON, C.E. New Edition, royal 32mo, oblong, leather, gilt edges, with elastic band, 4s.

"Of incalculable value to the country gentleman and professional man."—*Farmer's Journal.*

Complete Agricultural Surveyors' Pocket-Book.

THE LAND VALUER'S AND LAND IMPROVER'S COMPLETE POCKET-BOOK; consisting of the above two works bound together, leather, gilt edges, with strap, 7s. 6d.

The above forms an unequalled and most compendious Pocket Vade-mecum for the Land Agent and Agricultural Engineer.

"We consider Hudson's book to be the best ready-reckoner on matters relating to the valuation of land and crops we have ever seen, and its combination with Mr. Ewart's work greatly enhances the value and usefulness of the latter-mentioned. . . It is most useful as a manual for reference to those for whom it is intended."—*North of England Farmer.*

House Property.

HANDBOOK OF HOUSE PROPERTY: a Popular and Practical Guide to the Purchase, Mortgage, Tenancy, and Compulsory Sale of Houses and Land; including the Law of Dilapidations and Fixtures; with Explanations and Examples of all kinds of Valuations, and useful Information and Advice on Building. By EDWARD LANCE TARBUCK, Architect and Surveyor. 12mo, 5s. cloth boards.

"We are glad to be able to recommend it."—*Builder.*

"The advice is thoroughly practical."—*Law Journal.*

Scott Burn's Introduction to Farming.

THE LESSONS of MY FARM: a Book for Amateur Agriculturists, being an Introduction to Farm Practice, in the Culture of Crops, the Feeding of Cattle, Management of the Dairy, Poultry, and Pigs, and in the Keeping of Farm-work Records. By ROBERT SCOTT BURN. With numerous Illustrations. Fcp. 6s. cloth.

"A most complete introduction to the whole round of farming practice."—*John Bull.*

"A Complete Epitome of the Laws of this Country."

EVERY MAN'S OWN LAWYER; a Handy-Book of the Principles of Law and Equity. By A BARRISTER. 12th Edition, carefully revised, including a Summary of The Building Societies Act, The Infants' Relief Act, The Married Women's Property Act, The Real Property Limitation Act, The Betting Act, The Hosiery Manufacture Act, a Summary of the Supreme Court of Judicature Act, &c., &c. With Notes and References to the Authorities. 12mo, price 6s. 8d. (saved at every consultation), strongly bound.

COMPRISING THE LAWS OF

BANKRUPTCY—BILLS OF EXCHANGE—CONTRACTS AND AGREEMENTS—COPYRIGHT—DOWER AND DIVORCE—ELECTIONS AND REGISTRATION—INSURANCE—LIBEL AND SLANDER—MORTGAGES—SETTLEMENTS—STOCK EXCHANGE PRACTICE—TRADE MARKS AND PATENTS—TRESPASS, NUISANCES, ETC.—TRANSFER OF LAND, ETC.—WARRANTY—WILLS AND AGREEMENTS, ETC. Also Law for Landlord and Tenant—Master and Servant—Workmen and Apprentices—Heirs, Devises, and Legatees—Husband and Wife—Executors and Trustees—Guardian and Ward—Married Women and Infants—Partners and Agents—Lender and Borrower—Debtor and Creditor—Purchaser and Vendor—Companies and Associations—Friendly Societies—Clergymen, Churchwardens—Medical Practitioners, &c.—Bankers—Farmers—Contractors—Stock and Share Brokers—Sportsmen and Gamekeepers—Farriers and Horse-Dealers—Auctioneers, House-Agents—Innkeepers, &c.—Pawnbrokers—Surveyors—Railways and Carriers, &c. &c.

"No Englishman ought to be without this book."—*Engineer*.

"It is a complete code of English Law, written in plain language which all can understand . . . should be in the hands of every business man, and all who wish to abolish lawyers' bills."—*Weekly Times*.

"A useful and concise epitome of the law."—*Law Magazine*.

"What it professes to be—a complete epitome of the laws of this country, thoroughly intelligible to non-professional readers."—*Bell's Life*.

Auctioneer's Assistant.

THE APPRAISER, AUCTIONEER, BROKER, HOUSE AND ESTATE AGENT, AND VALUER'S POCKET ASSISTANT, for the Valuation for Purchase, Sale, or Renewal of Leases, Annuities, and Reversions, and of property generally; with Prices for Inventories, &c. By JOHN WHEELER, Valuer, &c. Third Edition, enlarged, by C. NORRIS. Royal 32mo, cloth, 5s.


"A neat and, concise book of reference, containing an admirable and clearly-arranged list of prices for inventories, and a very practical guide to determine the value of furniture, &c."—*Standard*.

Pawnbrokers' Legal Guide.

THE PAWNBROKERS', FACTORS', and MERCHANTS' GUIDE to the LAW of LOANS and PLEDGES. With the Statutes and a Digest of Cases on Rights and Liabilities, Civil and Criminal, as to Loans and Pledges of Goods, Debentures, Mercantile, and other Securities. By H. C. FOLKARD, Esq., of Lincoln's Inn, Barrister-at-Law, Author of the "Law of Slander and Libel," &c. 12mo, cloth boards, price 7s.

The Laws of Mines and Mining Companies.

A PRACTICAL TREATISE on the LAW RELATING to MINES and MINING COMPANIES. By WHITTON ARUNDELL, Attorney-at-Law. Crown 8vo. 4s. cloth.



A SELECTION FROM WEALE'S SERIES.

MECHANICAL ENGINEERING, &c.

MECHANICS, Rudimentary Treatise on; being a concise Exposition of the General Principles of Mechanical Science, and their Applications. By C. TOMLINSON. Illustrated. 1s. 6d.

PNEUMATICS, for the Use of Beginners. By CHARLES TOMLINSON. Illustrated. 1s. 6d.

CRANES, the Construction of, and other Machinery for Raising Heavy Bodies for the Erection of Buildings, and for Hoisting Goods. By JOSEPH GLYNN, F.R.S., &c. Illustrated. 1s. 6d.

THE STEAM ENGINE, a Rudimentary Treatise on. By Dr. LARDNER. Illustrated. 1s. 6d.

THE STEAM ENGINE, a Treatise on the Mathematical Theory of, with Rules at length, and Examples for the use of Practical Men. By T. BAKER, C.E. Illustrated. 1s. 6d.

STEAM BOILERS: their Construction and Management. By R. ARMSTRONG, C.E. Illustrated. 1s. 6d.

AGRICULTURAL ENGINEERING: Farm Buildings, Motive Power, Field Machines, Machinery, and Implements. By G. H. ANDREWS, C.E. Illustrated. 3s.

CLOCKS, WATCHES, AND BELLS. By Sir EDMUND BECKETT (late E. B. DENISON, LL.D., &c. &c.) A New Edition, revised, with several additional Illustrations. 4s. 6d.

THE ECONOMY OF FUEL, particularly with reference to Reverberatory Furnaces for the Manufacture of Iron, and to Steam Boilers. By T. SYMES PRIDEAUX. 1s. 6d.

MARINE ENGINES AND STEAM VESSELS, a Treatise on. Together with Practical Remarks on the Screw and Propelling Power, as used in the Royal and Merchant Navy. By ROBERT MURRAY, C.E., Engineer-Surveyor to the Board of Trade. Fifth Edition, revised and enlarged. Illustrated. 3s.

THE POWER OF WATER, as applied to drive Flour Mills, and to give motion to Turbines and other Hydrostatic Engines. By J. GLYNN, F.R.S., &c. New Edition. Illustrated. 2s.

STATICS AND DYNAMICS, the Principles and Practice of; embracing a clear development of Hydrostatics, Hydrodynamics, and Pneumatics, with Central Forces and Super-Elevation of Exterior Rail. By T. BAKER, C.E. 1s. 6d.

STEAM AND THE STEAM ENGINE, Stationary and Portable, an Elementary Treatise on; being an Extension of Mr. JOHN SEWELL's "Treatise on Steam." By D. KINNAR CLARK, C.E., M.I.C.E., Author of "Railway Machinery," &c. With numerous Illustrations. 3s. 6d.

CROSBY LOCKWOOD & CO., 7, STATIONERS' HALL COURT, &c.

A SELECTION FROM WEALE'S SERIES.

MECHANISM, the Elements of; elucidating the Scientific Principles of the Practical Construction of Machines.

Specimens of Modern Machines, by T. BAKER, C.E.; and Remarks on Tools, &c., by J. NASMYTH, C.E. Plates. 2s. 6d.

MACHINERY, Rudimentary and Elementary Principles of the Construction and on the Working of. By C. D. ABEL, C.E. 1s. 6d.

THE COMBUSTION OF COAL AND THE PREVENTION OF SMOKE, Chemically and Practically Considered. With an Appendix. By C. WYB WILLIAMS, A.I.C.E. Plates. 3s.

THE ENGINEER'S GUIDE TO THE ROYAL AND MERCANTILE NAVIES. By a PRACTICAL ENGINEER. Carefully examined and revised by D. F. M'CARTHY. 3s.

THE BRASS FOUNDER'S MANUAL; Instructions for Modelling, Pattern-Making, Mounting, Alloying, Turning, Burnishing, Bronzing, &c. With numerous Tables and Notes on Prime Costs and Estimates. By W. GRAHAM. Illustrated. 2s. 6d.

MODERN WORKSHOP PRACTICE as applied to Marine, Land, and Locomotive Engines, Floating Docks, Bridges, Cranes, Ship-building, &c. By J. G. WINTON. Illustrated. 3s.

IRON AND HEAT, exhibiting the Principles concerned in the Construction of Iron Beams, Pillars, and Bridge Girders, and the Action of Heat in the Smelting Furnace. By J. ARMOUR, C.E. With numerous Illustrations. 2s. 6d.

POWER IN MOTION: Horse-power, Motion, Toothed-Wheel Gearing, Long and Short Driving Bands, Angular Forces. By J. ARMOUR, C.E. With 73 Diagrams. 2s. 6d.

THE APPLICATION OF IRON TO THE CONSTRUCTION OF BRIDGES, GIRDERS, ROOFS, AND OTHER WORKS. By FRANCIS CAMPIN, C.E. With numerous Illustrations. 2s.

MINING TOOLS. For the Use of Mine Managers, Agents, Students, &c. By WILLIAM MORGANS, Bristol School of Mines. 12mo. 2s. 6d. With an Atlas of Plates, containing 235 Illustrations. 4to. 4s. 6d.

THE WORKMAN'S MANUAL OF ENGINEERING DRAWING. By J. MAXTON, Instructor in Engineering Drawing, Royal Naval College, Greenwich, formerly of R.S.N.A., South Kensington, &c. &c. 7 Plates and nearly 350 Cuts. 3s. 6d.

METALLURGY OF IRON, a Treatise on the. Containing Methods of Assay, Processes of Manufacture of Iron and Steel, &c. By H. BAUERMAN, F.G.S., &c. Fourth Edition, revised and enlarged, with numerous Illustrations. 4s. 6d.

COAL AND COAL MINING: a Rudimentary Treatise on. By WARINGTON W. SMYTH, M.A., Chief Inspector of the Mines of the Crown and of the Colonies. With numerous Illustrations. 3s. 6d.

CROSBY LOCKWOOD & CO., 7, STATION

71

THE HISTORY OF THE
CITY OF LONDON

FROM THE FOUNDATION
TO THE PRESENT TIME

BY
JOHN STOW
AND
JAMES WARD

LONDON
PRINTED BY
J. STOW